



TECHNICAL SIGNS

7th July 2016

Kirklees Council
PO Box B93
Civic Centre 3
Huddersfield
HD1 2JR.

Dear Team,

SITE: PREZZO, 40-44 KING STREET, HUDDERSFIELD, HD1 2QT
HERITAGE STATEMENT



IoE Number: 1313518
Location: 40-44 King Street, Huddersfield, HD1 2QT
Date listed: 29 September 1978
Date of last amendment: 01 February 1972
Grade II
Listing NGR: SE146721656

KING STREET 1.5113 (South Side) No. 40-44 SE 1416 NE 2/741 Grade 11. Early C19 Ashlar. Pitched stone slate roof. 3 storeys. Stone brackets to gutter. Continuous sill band on 1st floor, 2 ranges of sashes, Mid C19 shopfront with panelled pilasters and moulded consoles.

Appearance

Please refer to drawing nos: 554677-1,2,3,4 and block plan no: 554677-5. Please also refer to Slug and Huddersfield Visual Rev A.

Registered in England No. 3028486

Hille Business Centre, 132 St Albans Road, Watford, Hertfordshire, WD24 4AE

T 01923 811999 **F** 01923 811998 **ISDN** 01923 226227 **E-MAIL** info@technicalsigns.co.uk



TECHNICAL SIGNS

3 SETS OF EXTERNALLY ILLUMINATED FASCIA TEXT – To replace existing.

Flat cut letters reading “SLUG & LETTUCE” have 2.5mm aluminium fronts which are finished black-grey RAL 7021 and which are bonded over 5mm live-edge lime green PMS 381 acrylic. Letters are screw fixed to the fascia panel with the fixings covered by the front piece. Flat cut smaller letters are two identical pieces of 2.5mm aluminium finished black-grey RAL 7021. Letters are counter sunk screw fixed to the fascia panel through one piece of aluminium and the other piece of aluminium is bonded over this. Externally illuminated by a steel trough which is finished black-grey RAL 7021 and which is fitted with low energy white LEDs.

1 SET OF INTERNALLY ILLUMINATED TEXT IN ALLEWAY – To replace existing.

Built up letters have 1.2mm brushed stainless steel faces and returns. Rebated 10mm lime green PMS 381 acrylic backs. Fitted with low energy white LEDs for halo illumination. Backs are fixed to the brickwork on locators.

1 EXTERNALLY ILLUMINATED PROJECTION SIGN – To replace existing. Existing

projection arm and trough lights are retained. Folded and welded 2.5mm aluminium panels are finished white and fit over a mild steel inner frame. 5mm live-edge lime PMS 381 acrylic letters are bonded to the panel faces. Flat cut 1.2mm descaled stainless steel letters are finished black-grey RAL 7021 and are bonded over the lime green acrylic. 5mm live-edge lime PMS 381 acrylic is also bonded around the sides of the outer panels. Sign hangs from existing projection arm and has the existing external illumination.

2 MENUS INTERNALLY ILLUMINATED – To replace existing. 1.2mm descaled stainless steel door and back box are finished matte black. 6mm toughened glass. 5mm opal polycarbonate panel with 900mm T8 30w coolwhite tubes behind. Continuous stainless steel hinge, standard cam locks and 1.2mm descaled stainless steel lock hooks. Vinyl text is printed warm grey PMS 422 with lime green PMS 381 outlines. Screw fixed to the wall.

Our design team have looked at all aspects of producing a signage scheme that compliments the surrounding conservation area and is sympathetic to the listed building. The greatest of care will be used by our experience team of fitters. We have replaced the signage like for like. We have replaced all signage like for like and we will be using all existing fittings and fixtures where possible.

We do not foresee any detrimental impact on the Heritage Assets of this building when installing the new signage scheme.

Registered in England No. 3028486

Hille Business Centre, 132 St Albans Road, Watford, Hertfordshire, WD24 4AE

T 01923 811999 **F** 01923 811998 **ISDN** 01923 226227 **E-MAIL** info@technicalsigns.co.uk