ARBORICULTURAL SAFETY SURVEY

at:

Huddersfield Grammar School
Royds Mount
Luck Lane
Marsh
Huddersfield
West Yorkshire
HD1 4QX

Client:
Huddersfield Grammar School

Client Address:
Royds Mount
Luck Lane
Marsh
Huddersfield
HD1 4QX

Client Telephone:
01484 424549

JCA Ref:
12699/TP

JCA Limited

Arboricultural Consultants

Contents

1. Introduction ***3***

1.1 Purpose of the Report **3**

1.2 Terms of Reference **3**

1.3 Scope of the Report **3**

1.4 Survey Details **3**

2. Explanation of Tree Descriptions ***4***

2.1 Measurements **4**

2.2 Evaluations **5**

2.3 Safety Categories **6**

3. Status of the Trees ***7***

4. Tree Descriptions and Recommendations ***7***

5. Discussion ***8***

6. Conclusion ***10***

Appendix 1: Tree Descriptions and Recommendations ***12***

Appendix 2: Explanation of Terms & Recommended Clearances ***13***

Appendix 3: Author Qualifications ***14***

Appendix 4: General Guidelines ***15***

Appendix 5: Site Plan ***16***

© JCA Limited 2016

1. Introduction

1.1 Purpose of the Report

1.1.1 This report details the findings of an expert arboricultural safety survey and risk assessment of the trees at:

Huddersfield Grammar School, Royds Mount, Luck Lane, Marsh, HD1 4QX.

1.1.2 This report details the relevant arboricultural information which is required to inform the owners of the condition of their trees and provides specific management actions that, once undertaken, demonstrate that a duty of care has been taken with regards to tree management.

1.2 Terms of Reference

1.2.1 I am instructed by Gordon Roberts, of Huddersfield Grammar School, to visit the site and prepare my findings in a report.

1.3 Scope of the Report

1.3.1 The trees have been inspected in order to assess and, if necessary, reduce their potential risk of harm.

1.3.2 All trees within the site boundary with a stem diameter above 75mm are included.

1.4 Survey Details

1.4.1 The survey was conducted during the month of February 2016 by Toby Parsons *Cert. Arb. (RFS), Tech. Cert. (Arbor.A).*

1.4.2 Inspection was made visually from ground level, in order to assess the trees condition and potential to cause harm. Where necessary, management recommendations have been made. This may include tree removal, pruning, future monitoring or the need for a further detailed inspection, such as climbed inspections or decay detection surveys.

1.4.3 Measurements were obtained using clinometers, specialist tapes or electronic distometers. Where this was not possible measurements were estimated.

© JCA Limited 2016

2. Explanation of Tree Descriptions

2.1 Measurements

2.1.1 *HEIGHT* of the tree is measured from the stem base to the top of the canopy.

2.1.2 *CROWN HEIGHT* is an indication of the height at which the main crown begins above ground level.

2.1.3 *STEM DIAMETER* is measured at 1.5 metres above (higher) ground level. Where the tree is multi-stemmed at this point; the diameter is measured close to ground level, just above the root buttress.

2.1.4 *CROWN SPREAD* is a measurement of the overall width of the crown, at its widest point.

© JCA Limited 2016

2.2 Evaluations

2.2.1 *AGE CLASS* of the tree is described as young, semi-mature, early-mature, mature, or over-mature.

2.2.2 *PHYSIOLOGICAL CONDITION* is classed as good, fair, poor, or dead. This is an indication of the health of the tree and takes into account vigour, presence of disease and dieback.

2.2.3 *STRUCTURAL CONDITION* is classed as good, fair or poor. This is an indication of the structural integrity of the tree and takes into account significant wounds, decay and quality of branch junctions.

2.2.4 *LIFE EXPECTANCY* is classed as; less than 10 years (<10), 10-20 years, 20-40 years, or more than 40 years (40+). This is an indication of the number of years before removal of the tree is likely to be required.

2.2.5 *TARGET VALUE* is classed as high, moderate or low. This is an indication of the likelihood of persons or objects, the latter having variable significance, being within falling distance of a tree or its branches.

2.2.6 *RE-INSPECTION TIMING* is classed as; 6 months (0.5), 1 year (1), 2 years (2), or within 5 years (5). This is an indication of the timescale in which a tree should be re-inspected; a specific time of year for the inspection may also be detailed in the recommendations.

2.2.7 *PRIORITIES.* A priority rating is given concerning the time periods in which the recommended works should be undertaken. LOW priority works should be undertaken within 12 months of the survey, MOD (moderate) priority works should be undertaken within 6 months and HIGH priority works should be completed as soon as practically possible. If no works are recommended, N/A (not applicable) will be used.

© JCA Limited 2016

2.3 Safety Categories

2.3.1 *SAFETY CATEGORY* values for the trees are as follows:

2.3.2 ***A (marked in green on the plan) = posing no immediate risk: no action required.***
These trees are considered to be in an acceptable condition at present and require no action at this time. However, these trees may require future management in order to ensure that they remain safe.

2.3.3 ***B (marked in light blue on the plan) = posing a potential risk: action required.***
These trees pose a potential risk and therefore require active management. This may include remedial pruning (crown cleaning) or target management.

Such trees may also require a further, more detailed, investigation (such as a climbing inspection or a decay detection analysis) or may require future monitoring (re-surveying and re-assessing) at a timescale specified within this report.

2.3.4 ***R (marked in red on the plan) = trees to be removed.***
These trees require removal usually because they are dead, dying or dangerous and are therefore potentially hazardous. Such trees shall usually require removal as a matter of high priority.

Trees may also require removal in order to prevent damage occurring to existing structures or buildings (where trees are growing within close proximity or are in actual contact) or in order to benefit adjacent trees (where trees are growing in direct competition, the poorer of the two trees may be removed). Such work is usually of a lower priority.

© JCA Limited 2016

3. Status of the Trees

3.1 A check was made on the 29th of February 2016 with: ***Kirklees Metropolitan Council.***

3.2 We are informed that the majority of trees within the site boundary are protected by a Tree Preservation Order.

3.3 Before any work is organised, all the necessary steps to get the permission of the Local Planning Authority must be taken.

3.4 ***No work must be done to any trees until permission has been granted.***

4. Tree Descriptions and Recommendations

4.1 Full details of all individual trees surveyed are recorded in the tables at **Appendix 1**. Please refer also to the site plan at **Appendix 5** for tree locations and **Section 2** for a full explanation of the tables.

© JCA Limited 2016

5. Discussion

5.1 In total **402** individual trees were surveyed, and they were generally found to be in fair condition.

5.2 Following is an overview of our observations and recommendations; please refer to **Appendix 1** for specific details on the condition of individual trees:

5.3 **Eighteen** trees (**T30, T51, T86, T120, T132, T136, T137, T142, T146, T154, T192, T193, T226, T233, T249, T260, T284** and **T391**) have been recommended for removal for arboricultural reasons, as detailed at **Appendix 1.**

5.3.1 The removal of these trees should be carried out as a matter of **moderate/low priority** as detailed at **Appendix 1**.

5.4 **Twenty** trees (**T10, T12, T14, T18, T98, T113, T122, T135, T191, T228, T243, T251, T255, T257, T267, T298, T303, T312, T314** and **T342**) require pruning, as detailed at **Appendix 1**.

5.4.1 The recommended works to **T12, T228** and **T298** should be undertaken as a matter of **high priority**.

5.4.2 The recommended work to **T10, T14, T18, T98, T113, T122, T135, T191, T243, T251, T255, T257, T267, T303, T312, T314** and **T342** is of **moderate priority**.

5.5 **Seventy seven** trees (**T5, T11, T14, T16, T17, T18, T19, T20, T34, T43, T44, T45, T46, T47, T48, T49, T50, T69, T91, T96, T101, T104, T105, T106, T108, T109, T110, T111, T112, T116, T125, T128, T129, T130, T133, T134, T138, T139, T140, T141, T143, T144, T147, T149, T151, T157, T158, T167, T181, T183, T188, T194, T202, T217, T220, T221, T225, T232, T235, T266, T268, T274, T291, T302, T307, T314, T316, T318, T322, T325, T327, T333, T340, T342, T352, T361** and **T373**) were noted to have structural or physiological defects, as detailed at **Appendix 1**. Although these trees were considered to be in an acceptable condition at the time of the inspection, the defects observed may lead to their early demise or render them unsafe in the future. As such, it is recommended that these trees be monitored (re-inspected) on an annual basis to assess if their condition is still acceptable.

5.6 A full detailed inspection of **seventy seven** trees (**T7, T15, T21, T22, T24, T25, T26, T27, T28, T29, T31, T32, T33, T35, T36, T37, T38, T41, T42, T52, T53, T54, T55, T56, T57, T58, T60, T61, T62, T64, T65, T70, T74, T80, T81, T82, T114, T115, T173, T174, T198, T204, T209, T210, T211, T213, T214, T215, T216, T239, T247, T258, T259, T261, T262, T263, T264, T265, T278, T285, T287, T290, T347, T348, T351, T353, T354, T355, T356, T363, T364, T368, T369, T371, T382, T383** and **T384)** was inhibited by the presence of Ivy, epicormic shoots or by dense understorey vegetation, as detailed at **Appendix 1**. These trees should be re-inspected for defects once the ivy/epicormic shoots/understorey vegetation has been removed.

© JCA Limited 2016

5.7 Further investigation in the form of decay detection analysis is recommended for **T296**. The condition of this tree could not be accurately assessed without the use of ultrasound or similar technology. Please contact the author for a quotation for this work.

5.8 The ground level appears to have been raised around the bases of **ten** trees (**T34, T44, T45, T46, T47, T48, T49, T50, T74** and **T80**) as detailed at **Appendix 1**. Raising the ground level within the rooting areas of trees will have a significant detrimental effect on their health, as it reduces the amount of available oxygen to the roots, essentially suffocating the tree. As such, it is recommended that the original ground level be reinstated around these trees in an attempt to reverse any damage that may have already been caused. This work **must** be carried out cautiously by using hand tools only and not by mechanical means, in order to avoid any further damage.

5.9 If these recommendations are undertaken, the trees surveyed can be considered to be in adequate condition in terms of public health and safety. We recommend that the trees are re-surveyed as per the recommended schedule and that a management plan is obtained and adhered to, in order to ensure the long term health and safety of the trees.

5.10 We would be happy to assist should you have any queries regarding the points raised in **Section 5**.

© JCA Limited 2016

6. Conclusion

6.1 The trees surveyed were generally found to be in fair condition.

6.2 **Eighteen** trees have been recommended for removal. These trees are discussed in **Section 5.3** and detailed at **Appendix 1**.

6.3 **Twenty** trees have been recommended for pruning. These trees are discussed in **Section 5.4** and detailed at **Appendix 1**.

6.4 **Seventy seven** trees require monitoring (re-inspecting and re-assessing) on an annual basis. These trees are discussed in **Section 5.5** and detailed at **Appendix 1**.

6.5 **Seventy seven** trees require a further detailed inspection as this was not possible at the time of the survey. These are discussed in **Section 5.6** and detailed at **Appendix 1**.

6.6 **One** tree requires a decay detection. This is discussed in **Section 5.7** and detailed at **Appendix 1**.

6.7 **Ten** trees require the raised ground level around their bases to be reinstated to its original level. These are discussed in **Section 5.8** and detailed at **Appendix 1**.

6.8 Upon instruction JCA will produce management plans, tree planting schemes, organise and supervise tree works, and if necessary undertake climbed inspections and ultrasound decay detection analysis.

© JCA Limited 2016

Appendices

Appendix 1: Tree Descriptions and Recommendations

© JCA Limited 2016

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 1	Semi-mature Sycamore *Acer pseudoplatanus*	14	4	29	4	Single stemmed and vertical with a balanced crown. The crown overhangs the car park. Occasional pruning wounds, generally healing well. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 2	Semi-mature Leyland Cypress *X Cupressocyparis leylandii*	10	0	17	2	Multiple stemmed at 0m. Vertical with a balanced crown. No major visible defects.	GOOD	GOOD	40+	HIGH	No action required.	N/A	A	2
T 3	Early-mature Common Beech *Fagus sylvatica*	18	3	75	13	Single stemmed, vertical with a balanced crown. The crown overhangs the car park and driveway. Occasional pruning wounds due to crown lifting, generally healing well. Deadwood noted (minor). Occasional tear wounds noted.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 4	Semi-mature Common Holly *Ilex aquifolium*	8	2	19	3	Twin stemmed at 0m. Vertical with a balanced crown. The crown overhangs the car park. Occasional pruning wounds due to crown lifting. Generally healing well. Tight union noted.	GOOD	GOOD	40+	HIGH	No action required.	N/A	A	2
T 5	Mature Common Ash *Fraxinus excelsior*	20	9	76	14	Twin stemmed at 0m. Vertical with a balanced crown. The crown overhangs the driveway and car park. Multiple pruning wounds due to crown lifting, healing slowly. Large pruning wounds with occasional cavities forming.	FAIR	FAIR	20-40	HIGH	Monitor cavities annually.	LOW	B	1
T 6	Early-mature Sycamore *Acer pseudoplatanus*	18	6	76	8	Single stemmed, vertical with a balanced crown. The crown overhangs the driveway. Multiple pruning wounds due to crown lifting, healing slowly. Deadwood noted (minor). Basal bark wounds.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 7	Mature Sycamore *Acer pseudoplatanus*	18	5	89	11	Single stemmed, vertical with a balanced crown. The crown overhangs the driveway. Multiple pruning wounds. Previously topped now with mature regrowth. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	0.5
T 8	Early-mature Common Holly *Ilex aquifolium*	14	3	32	6	Single stemmed, vertical with a balanced crown. The crown overhangs the driveway. Occasional pruning wounds due to crown lifting, generally healing well. Occasional bark wounds.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 9	Semi-mature Common Holly *Ilex aquifolium*	9	4	22	6	Twin stemmed at 0.3m. Suppressed specimen. Slightly unbalanced crown. The crown overhangs the driveway. Occasional pruning wounds due to crown lifting, generally healing well. Bark wounds. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 10	Mature Common Beech *Fagus sylvatica*	21	4	83	14	Twin stemmed at 1.2m. Vertical with a balanced crown. The crown overhangs the driveway and car park. Multiple pruning wounds due to crown lifting, healing slowly. Major rubbing limbs from 2.5 to 8m with significant wounding. Potential failure point. Crown reduce to limit potential failure.	FAIR	FAIR	20-40	HIGH	Reduce crown by 6m in height and blend the sides to re-balance.	MOD	B	1
T 11	Mature Sycamore *Acer pseudoplatanus*	20	6	89	12	Single stemmed, vertical with a balanced crown. The crown overhangs the driveway and car park. Occasional pruning wounds due to crown lifting, generally healing well. Previously topped now with mature regrowth. Sparse crown suggests the tree may be in decline.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 12	Early-mature Common Oak *Quercus robur*	21	5	77	14	Single stemmed, vertical with a balanced crown. The crown overhangs the car park and building. Multiple pruning wounds due to crown lifting, healing slowly. Minor deadwood and broken branch in lower crown over car park.	FAIR	FAIR	20-40	HIGH	Remove the broken branch and the larger deadwood.	HIGH	B	1
T 13	Early-mature Sessile Oak *Quercus petraea*	21	4	59	10	Single stemmed, vertical with a balanced crown. The crown overhangs the car park and building. Occasional pruning wounds due to crown lifting, generally healing well. Deadwood noted (minor). No major visible defects.	GOOD	FAIR	40+	HIGH	No action required.	N/A	A	2
T 14	Early-mature Common Ash *Fraxinus excelsior*	17	11	54	8	Twin stemmed at 5m. Vertical with a balanced crown. The crown overhangs the car park and boundary. Multiple pruning wounds due to crown lifting, generally healing well. Sparse crown with deadwood noted.	FAIR	FAIR	10-20	HIGH	Remove deadwood and monitor sparse crown annually.	MOD	B	1
T 15	Mature Sycamore *Acer pseudoplatanus*	20	4	89	13	Single stemmed, vertical with a balanced crown. The crown overhangs the car park. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 16	Early-mature Common Beech *Fagus sylvatica*	21	2	85	10	Single stemmed, vertical with a balanced crown. Crown overhangs the car park. Recent excavation/soil disturbance at base has potentially resulted in root damage. Monitor condition annually.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 17	Early-mature Sycamore *Acer pseudoplatanus*	16	4	41	8	Single stemmed, vertical with an unbalanced crown. Suppressed specimen. The crown overhangs the boundary. Recent excavation/soil disturbance at base has potentially resulted in root damage. Monitor condition annually.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 18	Early-mature Common Beech *Fagus sylvatica*	18	3	43	6	Single stemmed, vertical with a balanced crown. The crown overhangs the car park. Broken branch within crown. Recent excavation/soil disturbance at base has potentially resulted in root damage. Monitor condition annually.	FAIR	FAIR	10-20	HIGH	Remove the broken branch. Monitor annually.	MOD	B	1
T 19	Early-mature Common Ash *Fraxinus excelsior*	18	8	39	7	Single stemmed, vertical with a balanced crown. Crown overhangs the car park. Recent excavation/soil disturbance at base has potentially resulted in root damage. Monitor condition annually.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 20	Early-mature Common Ash *Fraxinus excelsior*	20	10	42	8	Single stemmed, vertical with a balanced crown. Crown overhangs the car park. New hard surface around base. Recent excavation/soil disturbance at base has potentially resulted in root damage. Monitor condition annually.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 21	Mature Common Ash *Fraxinus excelsior*	22	5	75	15	Twin stemmed at 4m. Vertical with a balanced crown. The crown overhangs the car park and boundary. Dense Ivy prevented a detailed inspection. Over extended branches noted.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	0.5
T 22	Early-mature Sycamore *Acer pseudoplatanus*	12	5	30	5	Single stemmed and vertical. Suppressed specimen. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	10-20	HIGH	Remove the Ivy and re-inspect.	HIGH	B	0.5
T 23	Early-mature Common Beech *Fagus sylvatica*	15	2	37	7	Single stemmed, vertical with a balanced crown. Close to car park. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 24	Early-mature Sycamore *Acer pseudoplatanus*	19	4	37	6	Single stemmed, vertical with a balanced crown. Dense vegetation at base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation and re-inspect.	MOD	B	1
T 25	Early-mature Sycamore *Acer pseudoplatanus*	15	9	35	8	Single stemmed, vertical with an unbalanced crown. Suppressed specimen. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 26	Mature Sycamore *Acer pseudoplatanus*	21	10	85	12	Single stemmed, vertical with a balanced crown. Dense vegetation at base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 27	Early-mature Sycamore *Acer pseudoplatanus*	17	3	30	6	Single stemmed, vertical with an unbalanced crown. Suppressed specimen. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 28	Early-mature Sycamore *Acer pseudoplatanus*	18	8	55	6	Single stemmed, vertical with an unbalanced crown. Suppressed specimen. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 29	Early-mature Sycamore *Acer pseudoplatanus*	19	7	39	8	Twin stemmed at 0m. Vertical with a slightly unbalanced crown. The crown overhangs the road. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 30	Early-mature Lombardy Poplar *Populus nigra 'Italica'*	20	16	69	3	Single stemmed, vertical with a balanced crown. Dense Ivy on stem. Unidentifiable degraded fungal fruiting bodies to the stem. Wound with significant decay at 5m. Limited long term future	POOR	FAIR	<10	HIGH	Remove.	HIGH	R	n/a
T 31	Early-mature Sycamore *Acer pseudoplatanus*	16	5	33	6	Single stemmed, vertical with a slightly unbalanced crown. The crown overhangs the road. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 32	Early-mature Sycamore *Acer pseudoplatanus*	21	16	37	6	Single stemmed, vertical with a slightly unbalanced crown. Drawn up specimen. Close to car park. Dense vegetation at base prevented detailed inspection	FAIR	FAIR	20-40	HIGH	Remove the vegetation and re-inspect.	HIGH	B	1
T 33	Early-mature Common Ash *Fraxinus excelsior*	23	17	34	7	Single stemmed, vertical with a slightly unbalanced crown. Drawn up specimen. Close to car park. Dense vegetation at base prevented detailed inspection	FAIR	FAIR	20-40	HIGH	Remove the vegetation and re-inspect.	HIGH	B	1
T 34	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	16	2	36	9	Single stemmed, vertical with a balanced crown. The ground level has been raised around the base.	FAIR	FAIR	<10	HIGH	Monitor annually. Reinstate original ground level.	HIGH	B	1
T 35	Early-mature Sycamore *Acer pseudoplatanus*	21	17	41	8	Single stemmed, vertical with a balanced crown. Drawn up specimen. Dense vegetation at base prevented detailed inspection.	FAIR	DEAD	20-40	HIGH	Remove the vegetation and re-inspect.	HIGH	B	1
T 36	Mature Sycamore *Acer pseudoplatanus*	22	16	73	8	Single stemmed, vertical with a balanced crown. Ivy prevented detailed inspection.	FAIR	FAIR	10-20	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 37	Early-mature Sycamore *Acer pseudoplatanus*	19	4	65	9	Single stemmed. Vertical with a slightly unbalanced crown. Crown overhangs the road. Dense Ivy and vegetation at base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and vegetation from base and re-inspect.	HIGH	B	0.5
T 38	Early-mature Common Beech *Fagus sylvatica*	17	4	54	8	Single stemmed, vertical with a balanced crown. Deadwood noted. Dense vegetation at base prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation and re-inspect.	HIGH	B	1
T 39	Early-mature Sycamore *Acer pseudoplatanus*	16	4	37	7	Single stemmed. Vertical with an unbalanced crown. Suppressed specimen. Crown overhangs the road. Deadwood noted (minor).	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 40	Early-mature Common Beech *Fagus sylvatica*	19	3	38	6	Single stemmed, vertical with a balanced crown. Close to road. Deadwood noted (minor). No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 41	Early-mature Sycamore *Acer pseudoplatanus*	18	4	36	7	Single stemmed, vertical with an unbalanced crown. Close to road. Epicormic growth and dense vegetation at base prevented detailed inspection.	FAIR	FAIR	10-20	HIGH	Remove epicormic growth and vegetation and re-inspect.	HIGH	B	1
T 42	Semi-mature Sycamore *Acer pseudoplatanus*	11	6	26	6	Single stemmed, vertical with an unbalanced crown. Suppressed specimen. The crown overhangs the footpath and road. Ivy prevented detailed inspection.	FAIR	FAIR	40+	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 43	Mature Common Ash *Fraxinus excelsior*	24	13	65	12	Single stemmed, vertical with a balanced crown. The crown overhangs the road. Sparse crown suggests the tree may be in decline.	FAIR	FAIR	10-20	HIGH	Monitor sparse crown annually.	MOD	B	1
T 44	Early-mature Common Ash *Fraxinus excelsior*	18	13	51	11	Single stemmed, vertical with a balanced crown. The ground level has been raised around the base.	FAIR	FAIR	<10	HIGH	Reinstate original ground level. Monitor.	HIGH	B	1
T 45	Early-mature Norway Maple *Acer platanoides*	18	5	52	9	Single stemmed, vertical with a balanced crown. The crown overhangs the car park. The ground level has been raised around the base.	FAIR	FAIR	10-20	HIGH	Monitor. Reinstate original ground level.	HIGH	B	1
T 46	Early-mature Common Ash *Fraxinus excelsior*	18	5	31	8	Single stemmed, vertical with an unbalanced crown. The crown overhangs the car park. The ground level has been raised around the base.	FAIR	FAIR	10-20	HIGH	Monitor. Reinstate original ground level.	HIGH	B	1
T 47	Semi-mature Sycamore *Acer pseudoplatanus*	13	9	16	3	Single stemmed, vertical with a balanced crown. The crown overhangs the car park. The ground level has been raised around the base.	FAIR	FAIR	10-20	HIGH	Monitor. Reinstate original ground level.	HIGH	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 48	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	15	4	27	7	Single stemmed, vertical with a balanced crown. The crown overhangs the car park. The ground level has been raised around the base.	FAIR	FAIR	10-20	HIGH	Monitor. Reinstate original ground level.	HIGH	B	1
T 49	Early-mature Norway Maple *Acer platanoides*	15	6	29	7	Single stemmed, vertical with an unbalanced crown. The crown overhangs the car park. The ground level has been raised around the base.	FAIR	FAIR	10-20	HIGH	Monitor. Reinstate original ground level.	HIGH	B	1
T 50	Early-mature Common Ash *Fraxinus excelsior*	21	13	41	9	Single stemmed, vertical with a balanced crown. The crown overhangs the car park. Previously topped. Crown overhangs the car park. The ground level has been raised around the base.	FAIR	FAIR	10-20	HIGH	Monitor. Reinstate original ground level.	HIGH	B	1
T 51	Early-mature Common Beech *Fagus sylvatica*	19	3	46	9	Single stemmed, vertical with a balanced crown. Crown overhangs the car park. The ground level has been raised around the base. 50% bark missing from around the base with the onset of decay. Limited long term future.	FAIR	FAIR	<10	HIGH	Remove.	MOD	R	n/a
T 52	Semi-mature Norway Maple *Acer platanoides*	13	4	10	6	Multiple stemmed at 1m. Vertical with a balanced crown. Dense vegetation at base prevented detailed inspection.	FAIR	FAIR	20-40	MOD	Remove the vegetation and re-inspect.	LOW	B	1
T 53	Early-mature Common Ash *Fraxinus excelsior*	22	15	37	9	Single stemmed, vertical with a balanced crown. Dense vegetation at base prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation and re-inspect.	HIGH	B	1
T 54	Early-mature Sycamore *Acer pseudoplatanus*	22	18	29	7	Single stemmed, slightly leaning with an unbalanced crown. Dense vegetation at base prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation and re-inspect.	HIGH	B	1
T 55	Mature Sycamore *Acer pseudoplatanus*	22	10	70	9	Single stemmed, vertical with a balanced crown. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 56	Semi-mature Sycamore *Acer pseudoplatanus*	17	11	24	4	Single stemmed, vertical with a slightly unbalanced crown. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 57	Early-mature Sycamore *Acer pseudoplatanus*	18	13	27	4	Single stemmed, vertical with an unbalanced crown. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 58	Semi-mature Sycamore *Acer pseudoplatanus*	15	7	21	4	Twin stemmed at 0m. Vertical with a slightly unbalanced crown. The crown overhangs the road. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 59	Semi-mature Sycamore *Acer pseudoplatanus*	10	6	17	3	Single stemmed, vertical with a slightly unbalanced crown. The crown overhangs the road. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 60	Semi-mature Sycamore *Acer pseudoplatanus*	13	6	26	5	Single stemmed, vertical with a balanced crown. The crown overhangs the road. Ivy prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 61	Early-mature Common Lime *Tilia europaea*	20	2	48	9	Single stemmed, vertical with a balanced crown. The crown overhangs the road. Ivy and epicormic growth at base prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove epicormic growth and Ivy and re-inspect.	HIGH	B	1
T 62	Early-mature Common Beech *Fagus sylvatica*	17	3	29	7	Single stemmed, vertical with a balanced crown. The crown overhangs the road. Ivy prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 63	Early-mature Lawson Cypress *Chamaecyparis lawsoniana*	16	2	27	3	Single stemmed, vertical with a balanced crown. Close to road. Ivy at base. Appears to be in an acceptable condition at present.	GOOD	FAIR	40+	HIGH	No action required.	N/A	A	2
T 64	Early-mature Common Beech *Fagus sylvatica*	15	3	27	6	Single stemmed, vertical with a balanced crown. The crown overhangs the road. Occasional pruning wounds due to crown lifting. Ivy on stem.	GOOD	GOOD	40+	HIGH	Remove Ivy.	LOW	B	2
T 65	Early-mature Silver Birch *Betula pendula*	20	10	28	5	Single stemmed, vertical with a balanced crown. Drawn up specimen. The crown overhangs the road. Ivy prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 66	Early-mature Common Oak *Quercus robur*	12	3	27	7	Single stemmed, slight lean. With a slightly unbalanced crown. Suppressed specimen. Close to road. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 67	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	8	1	23	5	Single stemmed, vertical with a slightly unbalanced crown. Close to road. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 68	Early-mature Common Ash *Fraxinus excelsior*	3	1.5	29	2	Twin stemmed at 1.5m. Previously topped.	FAIR	FAIR	10-20	MOD	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 69	Mature Sycamore *Acer pseudoplatanus*	17	6	71	11	Single stemmed, vertical with a balanced crown. Crown overhangs the road and footpath. Multiple pruning wounds due to crown lifting, healing slowly. Cavities in stem on old pruning wounds.	FAIR	FAIR	20-40	HIGH	Monitor cavities annually.	LOW	B	1
T 70	Early-mature Poplar *Populus sp.*	16	8	43	7	Single stemmed, slight lean with a slightly unbalanced crown. Close to road. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	10-20	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 71	Semi-mature Leyland Cypress *X Cupressocyparis leylandii*	11	2	18	2	Single stemmed, vertical with a balanced crown. Close to road. No major visible defects.	GOOD	GOOD	40+	HIGH	No action required.	N/A	A	2
T 72	Early-mature Leyland Cypress *X Cupressocyparis leylandii*	17	2	38	3	Single stemmed, vertical with a balanced crown. Close to road. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 73	Early-mature Common Holly *Ilex aquifolium*	12	0.5	23	6	Multiple stemmed at 0m with a balanced crown. Close to road. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 74	Early-mature Sycamore *Acer pseudoplatanus*	13	5	31	4	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs the road. Occasional pruning wounds due to crown lifting. Ivy prevented detailed inspection. The ground level has been raised around the base.	FAIR	FAIR	10-20	HIGH	Remove Ivy. Reinstate original ground level.	MOD	B	1
T 75	Semi-mature Sycamore *Acer pseudoplatanus*	16	5	27	6	Single stemmed, vertical with a slightly unbalanced crown. Close to road. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 76	Semi-mature Sycamore *Acer pseudoplatanus*	9	2	14	4	Single stemmed, vertical with a slightly unbalanced crown. Close to road. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 77	Semi-mature Leyland Cypress *X Cupressocyparis leylandii*	8	1	17	2	Single stemmed, vertical with a balanced crown. Close to road. No major visible defects.	GOOD	GOOD	20-40	HIGH	No action required.	N/A	A	2
T 78	Early-mature Silver Birch *Betula pendula*	16	2	27	5	Single stemmed, vertical with a balanced crown. Close to road. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 79	Semi-mature Sycamore *Acer pseudoplatanus*	8	3	15	3	Single stemmed, vertical with a slightly unbalanced crown. Close to road. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 80	Early-mature Sycamore *Acer pseudoplatanus*	15	6	37	7	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs the road. Dense Ivy prevented a detailed inspection. Ground level raised at base.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect. Reinstate original ground level.	MOD	B	1
T 81	Early-mature Sycamore *Acer pseudoplatanus*	15	4	26	6	Twin stemmed at 0.5m, vertical with a balanced crown. Dense vegetation at base prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation and re-inspect.	HIGH	B	1
T 82	Early-mature Sycamore *Acer pseudoplatanus*	17	6	47	8	Twin stemmed at 3.5m, vertical with a balanced crown. Crown overhangs the road. Multiple pruning wounds due to crown lifting. Epicormic growth and dense vegetation at base prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove epicormic growth and vegetation and re-inspect.	MOD	B	1
T 83	Early-mature Common Hawthorn *Crataegus monogyna*	8	3	22	2	Multiple stemmed at 1m. Vertical with a slightly unbalanced crown. Close to road. Occasional pruning wounds due to crown lifting. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 84	Early-mature Sycamore *Acer pseudoplatanus*	14	7	26	5	Twin stemmed at 0m, vertical with a slightly unbalanced crown. Close to road. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 85	Early-mature Sycamore *Acer pseudoplatanus*	14	5	29	5	Single stemmed, vertical with a balanced crown. Close to road. Occasional pruning wounds due to crown lifting. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 86	Dead Elm *Ulmus sp.*	8	8	29	0	Dead standing stem close to benches.	DEAD	DEAD	<10	MOD	Remove.	MOD	R	n/a
T 87	Early-mature Common Beech *Fagus sylvatica*	8	2	32	12	Single stemmed, vertical with a balanced crown. Suppressed specimen. Close to road. Appears to be in an acceptable condition at present.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 88	Early-mature Whitebeam *Sorbus aria*	12	6	26	5	Single stemmed, vertical with a balanced crown. Occasional pruning wounds due to crown lifting, generally healing well. No major visible defects.	FAIR	FAIR	10-20	MOD	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 89	Early-mature Common Lime *Tilia europaea*	18	3	54	11	Single stemmed, vertical with a balanced crown. Occasional pruning wounds due to crown lifting. Deadwood noted (minor). Over extended branches noted.	GOOD	FAIR	40+	HIGH	No action required.	N/A	A	2
T 90	Early-mature Mountain Ash *Sorbus aucuparia*	12	6	26	3	Single stemmed, vertical with a slightly unbalanced crown. No major visible defects.	GOOD	FAIR	10-20	MOD	No action required.	N/A	A	2
T 91	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	18	3	37	11	Twin stemmed at 1m, vertical with a slightly unbalanced crown. Close to road. Occasional pruning wounds due to crown lifting. Decay forming on secondary stem at 2m.	FAIR	FAIR	10-20	HIGH	Monitor progress of decay at 2m annually .	MOD	B	1
T 92	Early-mature Common Ash *Fraxinus excelsior*	19	2.5	39	9	Single stemmed, vertical with a slightly unbalanced crown. Close to road. Occasional pruning wounds. Minor deadwood and tear wounds noted.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 93	Semi-mature Common Beech *Fagus sylvatica*	9	2	12	3	Single stemmed, vertical with a balanced crown. Close to road. No major visible defects.	GOOD	GOOD	40+	MOD	No action required.	N/A	A	2
T 94	Early-mature Common Ash *Fraxinus excelsior*	17	9	37	11	Single stemmed, vertical with a slightly unbalanced crown. Close to road. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 95	Early-mature Sycamore *Acer pseudoplatanus*	17	7	27	6	Single stemmed, vertical with a balanced crown. Close to road. Occasional pruning wounds due to crown lifting. Generally healing well. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 96	Early-mature Sycamore *Acer pseudoplatanus*	17	9	37	8	Single stemmed, vertical with a balanced crown. Crown overhangs the road. Occasional pruning wounds due to crown lifting. Squirrel damage noted throughout.	FAIR	FAIR	20-40	HIGH	Monitor Squirrel damage.	LOW	B	1
T 97	Early-mature Common Oak *Quercus robur*	17	8	37	9	Single stemmed, vertical with an unbalanced crown. Crown overhangs the road. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 98	Early-mature Elm *Ulmus sp.*	17	9	32	8	Single stemmed., slight lean with an unbalanced crown. Crown overhangs the road. Dead branch in lower crown over road/footpath.	FAIR	FAIR	10-20	HIGH	Remove dead branch in lower crown.	MOD	B	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 99	Early-mature Whitebeam *Sorbus aria*	8	3	26	4	Single stemmed, vertical with a balanced crown. Suppressed specimen. Occasional pruning wounds due to crown lifting, generally healing well. Deadwood noted (minor).	GOOD	FAIR	10-20	MOD	No action required.	N/A	A	2
T 100	Early-mature Common Ash *Fraxinus excelsior*	19	13	33	6	Single stemmed, vertical with a balanced crown. Occasional pruning wounds due to crown lifting. Healing slowly. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 101	Semi-mature Common Beech *Fagus sylvatica*	9	3	26	5	Single stemmed, vertical with a balanced crown. Occasional pruning wounds. Bark wounding with decay at 0.4m	FAIR	FAIR	20-40	MOD	Monitor decay.	MOD	B	1
T 102	Early-mature Common Lime *Tilia europaea*	17	7	34	7	Single stemmed, vertical with a balanced crown. Occasional pruning wounds. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 103	Early-mature Common Ash *Fraxinus excelsior*	17	13	26	5	Single stemmed, vertical with a slightly unbalanced crown. Occasional pruning wounds due to crown lifting, healing slowly. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 104	Early-mature Common Ash *Fraxinus excelsior*	17	9	43	9	Multiple stemmed at 2.5m, vertical with a balanced crown. Occasional pruning wounds due to crown lifting. Area of missing bark with the onset of decay at 0 to 1m.	FAIR	FAIR	20-40	HIGH	Monitor decay annually.	MOD	B	1
T 105	Mature Sycamore *Acer pseudoplatanus*	18	2.5	65	9	Single stemmed, vertical with an unbalanced crown. Occasional pruning wounds due to crown lifting, healing slowly. Mechanical wound on underside of lowest branch with minor decay.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 106	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	12	3	26	4	Single stemmed, vertical with an unbalanced crown. Wounding with decay forming at base.	FAIR	FAIR	<10	MOD	Monitor annually.	MOD	B	1
T 107	Early-mature Common Lime *Tilia europaea*	18	8	39	7	Single stemmed, vertical with a balanced crown. Multiple pruning wounds due to crown lifting, healing slowly. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 108	Early-mature Common Ash *Fraxinus excelsior*	18	10	29	6	Single stemmed, vertical with a balanced crown. Drawn up specimen. Basal bark wounds with the onset of decay.	FAIR	FAIR	20-40	HIGH	Monitor progress of decay annually.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 109	Early-mature Common Ash *Fraxinus excelsior*	18	10	34	6	Single stemmed, vertical with a balanced crown. Drawn up specimen. Occasional pruning wounds due to crown lifting, healing slowly. Bark wounds. Bark wounding with decay at 1m.	FAIR	FAIR	20-40	HIGH	Monitor progress of decay annually.	MOD	B	1
T 110	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	18	3	45	9	Twin stemmed at 2m, vertical with a balanced crown. Crown overhangs the road. Occasional pruning wounds due to crown lifting. Early Bleeding Canker of Horse Chestnut. with linear bark cracking noted. Minor included bark at 2m.	FAIR	FAIR	10-20	HIGH	Monitor progress of the Bleeding Canker of Horse Chestnut annually.	MOD	B	1
T 111	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	17	2	27	5	Single stemmed, vertical with a s lightly unbalanced crown. The tree is showing the early symptoms of Bleeding Canker of Horse Chestnut.	FAIR	FAIR	20-40	MOD	Monitor progress of the Bleeding Canker of Horse Chestnut annually.	MOD	B	1
T 112	Early-mature Common Ash *Fraxinus excelsior*	19	5	45	9	Twin stemmed at 3m, vertical with a slightly unbalanced crown. Crown overhangs the road. Epicormic growth in the crown suggests possible stress.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 113	Early-mature Elm *Ulmus sp.*	7	5	45	4	1.5m tall stump with poorly attached regrowth.	FAIR	FAIR	<10	HIGH	Remove regrowth to avoid potential failure into the road.	MOD	B	2
T 114	Semi-mature Common Hawthorn *Crataegus monogyna*	7	1	24	3	Single stemmed, slight lean with a slightly unbalanced crown. Crown overhangs the footpath. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	2
T 115	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	17	5	41	9	Single stemmed, vertical with a balanced crown. Crown overhangs the road. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 116	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	19	3	42	11	Twin stemmed at 1m, vertical with a balanced crown. The tree is showing the early symptoms of Bleeding Canker of Horse Chestnut.	FAIR	FAIR	10-20	HIGH	Monitor progress of the Bleeding Canker of Horse Chestnut annually.	MOD	B	1
T 117	Early-mature Sycamore *Acer pseudoplatanus*	17	3	45	8	Single stemmed, vertical with a slightly unbalanced crown. The crown overhangs sports field. Occasional pruning wounds due to crown lifting. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 118	Early-mature Common Lime *Tilia europaea*	19	7	38	7	Single stemmed, vertical with a slightly unbalanced crown. The crown overhangs sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 119	Early-mature Sycamore *Acer pseudoplatanus*	19	2	40	11	Twin stemmed at 3m, vertical with an unbalanced crown. The crown overhangs sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor). Over extended branches noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 120	Early-mature Common Beech *Fagus sylvatica*	18	3	37	9	Twin stemmed at 1m, vertical with a balanced crown. The crown overhangs sports field. Decay forming at base with significant dark exudates to the stem. Limited long term future.	POOR	FAIR	<10	HIGH	Remove.	LOW	R	n/a
T 121	Semi-mature Common Lime *Tilia europaea*	12	9	12	3	Single stemmed, vertical with a balanced crown. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 122	Early-mature Common Ash *Fraxinus excelsior*	17	9	33	9	Single stemmed, vertical with a balanced crown. The crown overhangs sports field. Deadwood noted (major). Dead branch noted in mid crown	FAIR	FAIR	20-40	HIGH	Remove dead branch.	MOD	B	2
T 123	Early-mature Common Beech *Fagus sylvatica*	17	4	37	9	Twin stemmed at 1.5m, slightly leaning with an unbalanced crown. The crown overhangs sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 124	Early-mature Common Holly *Ilex aquifolium*	12	0	27	8	Multiple stemmed at 0m, vertical with a balanced crown. No major visible defects.	GOOD	GOOD	20-40	MOD	No action required.	N/A	A	2
T 125	Early-mature Common Oak *Quercus robur*	18	3	39	9	Single stemmed, vertical with a slightly unbalanced crown. The crown overhangs sports field. Cavities in stem and a large tear wound noted at 9m.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 126	Early-mature Whitebeam *Sorbus aria*	11	2	21	4	Single stemmed, vertical with a balanced crown. Suppressed specimen. Close to footpath. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 127	Early-mature Mountain Ash *Sorbus aucuparia*	12	1	27	5	Single stemmed, vertical with a slightly unbalanced crown. Close to footpath. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 128	Early-mature Sycamore *Acer pseudoplatanus*	17	7	43	9	Single stemmed, vertical with a balanced crown. Crown overhangs the road. Previously topped now with mature re-growth. Some decay likely at topping points.	FAIR	FAIR	20-40	LOW	Monitor annually.	MOD	B	1
T 129	Early-mature Common Ash *Fraxinus excelsior*	18	4	29	6	Single stemmed, vertical with a balanced crown. Cavities in stem. Cavities at 0 and 6m	GOOD	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 130	Semi-mature Common Ash *Fraxinus excelsior*	6	6	23	0	Dead standing stem. Acceptable condition at present due to position in relation to targets	DEAD	DEAD	<10	LOW	Monitor annually.	LOW	B	1
T 131	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	17	4	31	8	Single stemmed, vertical with a balanced crown. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 132	Mature Common Horse Chestnut *Aesculus hippocastanum*	19	3	65	9	Twin stemmed at 0m, vertical with a balanced crown. The crown overhangs sports field. Significant Bleeding Canker of Horse Chestnut noted with significant bark cracking with decay. Limited long term future.	FAIR	POOR	<10	HIGH	Remove.	MOD	R	n/a
T 133	Early-mature Elm *Ulmus sp.*	17	6	45	8	Single stemmed, vertical with an unbalanced crown. The crown overhangs sports field. Showing early symptoms of Dutch Elm Disease.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 134	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	14	2	37	7	Single stemmed. Vertical. Unbalanced crown. Suppressed specimen. Crown overhangs sports field. Bleeding Canker of Horse Chestnut.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 135	Early-mature Common Ash *Fraxinus excelsior*	21	3	68	12	Twin stemmed at 2m, vertical with a slightly unbalanced crown. The crown overhangs sports field. Occasional pruning wounds. Deadwood noted (major). Over extended branches observed.	FAIR	FAIR	20-40	HIGH	Deadwood.	MOD	B	2
T 136	Semi-mature Common Ash *Fraxinus excelsior*	11	11	21	0	Dead tree	DEAD	DEAD	<10	MOD	Remove.	MOD	R	n/a
T 137	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	11	2	19	4	Single stemmed, vertical with a slightly unbalanced crown. Cavity at base with worsening decay. Limited long term future.	FAIR	POOR	<10	MOD	Remove.	MOD	R	n/a

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 138	Early-mature Common Ash *Fraxinus excelsior*	19	11	29	8	Single stemmed, vertical with a slightly unbalanced crown. Close to road. Ground level raised at base.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 139	Semi-mature Common Lime *Tilia europaea*	9	2	12	4	Single stemmed, vertical with a balanced crown. Ground level raised at base.	FAIR	FAIR	10-20	LOW	Monitor annually.	MOD	B	1
T 140	Early-mature Common Ash *Fraxinus excelsior*	19	11	28	6	Single stemmed, vertical with a balanced crown. Ground level raised at base.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 141	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	17	1	33	7	Single stemmed, vertical with a balanced crown. Ground level raised at base.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 142	Early-mature Sycamore *Acer pseudoplatanus*	19	7	39	9	Single stemmed, vertical with an unbalanced crown. Crown overhangs the road. Previously topped now with mature regrowth but with a sparse crown. Decay suspected at topping point. Limited long term future.	POOR	FAIR	<10	HIGH	Remove.	MOD	R	n/a
T 143	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	16	2	23	5	Single stemmed, vertical with an unbalanced crown. Cavity in stem. Early symptoms of Bleeding Canker of Horse Chestnut observed. Ground level raised at base.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 144	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	5	5	27	0	Dead standing stem. Acceptable condition at present due to position in relation to target	DEAD	DEAD	<10	LOW	Monitor annually.	MOD	B	1
T 145	Early-mature Common Ash *Fraxinus excelsior*	20	14	35	7	Single stemmed, vertical with a balanced crown. Drawn up specimen. Occasional pruning wounds due to crown lifting, generally healing well. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 146	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	13	3	26	6	Single stemmed and vertical. Cavity with decay from 0 to 2m. Limited long term future.	FAIR	POOR	<10	MOD	Remove.	LOW	R	n/a
T 147	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	13	2	27	6	Single stemmed, vertical with a balanced crown. Cavity in stem at 1m with worsening decay.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 148	Early-mature Common Ash *Fraxinus excelsior*	19	8	34	6	Twin stemmed at 2m, vertical with a slightly unbalanced crown. Minor deadwood noted and tear wounds noted.	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 149	Early-mature Common Ash *Fraxinus excelsior*	21	8	36	9	Single stemmed. slight lean with a balanced crown. Crown overhangs the road. Occasional pruning wounds, healing slowly. Previously topped with suspected decay forming at topping points.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 150	Early-mature Elm *Ulmus sp.*	17	3	36	8	Single stemmed, vertical with an unbalanced crown. Crown overhangs the boundary. Deadwood noted (minor).	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 151	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	8	2	13	3	Twin stemmed at 1m, vertical with a slightly unbalanced crown. Cavities in stem with minor decay forming at 0.5m	FAIR	FAIR	10-20	MOD	Monitor annually.	MOD	B	1
T 152	Early-mature Common Ash *Fraxinus excelsior*	17	8	37	8	Twin stemmed at 2.5m, vertical with a balanced crown. Crown overhangs the boundary. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 153	Early-mature Elm *Ulmus sp.*	14	2	25	5	Single stemmed, slight lean with a slightly unbalanced crown. Deadwood noted (minor).	FAIR	FAIR	10-20	MOD	No action required.	N/A	A	2
T 154	Early-mature Sycamore *Acer pseudoplatanus*	17	4	27	6	Single stemmed, slight lean with an unbalanced crown. The crown overhangs the sports field. Decay forming at base and extending up the stem with no sign of compartmentalisation.	POOR	FAIR	<10	HIGH	Remove.	MOD	R	n/a
T 155	Early-mature Common Ash *Fraxinus excelsior*	18	10	35	6	Single stemmed, slight lean with an unbalanced crown. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 156	Semi-mature Elm *Ulmus sp.*	8	1	23	3	Twin stemmed at 2m, vertical with a slightly unbalanced crown. Crown overhangs the boundary. Deadwood noted (minor).	GOOD	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 157	Mature Common Ash *Fraxinus excelsior*	18	3	84	11	Multiple stemmed at 1.5m, vertical with a balanced crown. Crown overhangs the boundary. Decay forming on tear wound at 5m to limb to north.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 158	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	9	2	33	9	Single stemmed, slight lean with an unbalanced crown. Suppressed specimen. Crown overhangs sports field. Occasional pruning wounds. Tear wounds noted with the onset of decay forming. Over extended branches also noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 159	Semi-mature Common Beech *Fagus sylvatica*	7	2	19	5	Twin stemmed at 1m with a slight stem lean. Suppressed specimen. Minor decay forming at 1m. Acceptable condition at this time	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 160	Early-mature Sycamore *Acer pseudoplatanus*	18	3	43	9	Single stemmed, vertical with a balanced crown. Crown overhangs sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 161	Early-mature Common Hawthorn *Crataegus monogyna*	8	2	15	4	Twin stemmed at 0m, vertical with a balanced crown. Crown overhangs the boundary. Bark wounds. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 162	Semi-mature Sycamore *Acer pseudoplatanus*	12	2	17	4	Single stemmed, slight lean with a slightly unbalanced crown. Crown overhangs sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 163	Semi-mature Sycamore *Acer pseudoplatanus*	12	2	17	4	Single stemmed with an unbalanced crown. Crown overhangs sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 164	Early-mature Sycamore *Acer pseudoplatanus*	15	2	27	7	Single stemmed, slight lean with a slightly unbalanced crown. Crown overhangs the boundary. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 165	Early-mature Sycamore *Acer pseudoplatanus*	19	7	44	9	Single stemmed, vertical with an unbalanced crown. Crown overhangs the boundary. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 166	Semi-mature Sycamore *Acer pseudoplatanus*	12	3	18	5	Single stemmed, leaning with an unbalanced crown. Suppressed specimen. Crown overhangs sports field. Minor ivy on stem.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 167	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	16	1	37	7	Single stemmed, vertical with an unbalanced crown. Crown overhangs the boundary. Tear wounds with decay noted.	FAIR	FAIR	10-20	HIGH	Monitor progress of decay forming at tear wounds annually.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 168	Semi-mature Sycamore *Acer pseudoplatanus*	9	3	17	5	Single stemmed, leaning with an unbalanced crown. Suppressed specimen. Crown overhangs the boundary. Deadwood noted (minor).	FAIR	FAIR	10-20	MOD	No action required.	N/A	A	2
T 169	Mature Common Lime *Tilia europaea*	21	4	73	12	Single stemmed, vertical with a balanced crown. Crown overhangs the boundary and the sports field. Occasional pruning wounds. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 170	Semi-mature Sycamore *Acer pseudoplatanus*	8	2	23	4	Single stemmed, slight lean with an unbalanced crown. Suppressed specimen. Crown overhangs sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 171	Early-mature Sycamore *Acer pseudoplatanus*	17	1	38	7	Single stemmed, slight lean with an unbalanced crown. Crown overhangs the boundary. Ivy on stem. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 172	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	12	1	26	5	Single stemmed, slight lean with an unbalanced crown. Suppressed specimen. Crown overhangs the boundary. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 173	Over-mature Sycamore *Acer pseudoplatanus*	16	1	42	7	Single stemmed, slight lean with a slightly unbalanced crown. Suppressed specimen. Crown overhangs the boundary. Dense vegetation at base prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation and re-inspect.	HIGH	B	1
T 174	Mature Common Ash *Fraxinus excelsior*	22	6	91	13	Twin stemmed at 2m, vertical with a balanced crown. Crown overhangs the boundary ands sports field. Dense vegetation at base prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation and re-inspect.	HIGH	B	1
T 175	Semi-mature Sycamore *Acer pseudoplatanus*	7	1	16	4	Single stemmed, slight lean with an unbalanced crown. Suppressed specimen. Crown overhangs sports field. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 176	Semi-mature Sycamore *Acer pseudoplatanus*	7	1	13	3	Single stemmed, vertical with a slightly unbalanced crown. Suppressed specimen. Crown overhangs sports field. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 177	Semi-mature Sycamore *Acer pseudoplatanus*	6	1	14	3	Single stemmed, slight lean with an unbalanced crown. Crown overhangs sports field. Very minor decay forming at 0.75m	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 178	Early-mature Common Lime *Tilia europaea*	15	4	27	7	Single stemmed, vertical with an unbalanced crown. Crown overhangs the boundary. Deadwood noted (minor). Epicormic growth in the crown.	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 179	Early-mature Common Lime *Tilia europaea*	17	3	37	7	Single stemmed, slight lean with an unbalanced crown. Crown overhangs the boundary and sports field. Occasional pruning wounds due to crown lifting, healing slowly. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 180	Mature Sycamore *Acer pseudoplatanus*	19	4	82	13	Single stemmed, vertical with a balanced crown. Crown overhangs the boundary and sports field. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 181	Mature Common Ash *Fraxinus excelsior*	21	4	94	14	Twin stemmed at 3m, vertical with a balanced crown. Crown overhangs the boundary and sports field. Tear wound at 6m with the onset of decay.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 182	Semi-mature Mountain Ash *Sorbus aucuparia*	6	1	13	3	Single stemmed, slight lean with a slightly unbalanced crown. Suppressed specimen. No major visible defects.	FAIR	FAIR	10-20	MOD	No action required.	N/A	A	2
T 183	Semi-mature Common Ash *Fraxinus excelsior*	8	3	23	7	Single stemmed, leaning due to suppression with an unbalanced crown. Crown overhangs sports field. Significant lean. Decay forming at 1m.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 184	Early-mature Common Lime *Tilia europaea*	18	7	48	9	Single stemmed, leaning with an unbalanced crown. Crown overhangs sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 185	Early-mature Sycamore *Acer pseudoplatanus*	16	4	46	9	Single stemmed, vertical with a balanced crown. Crown overhangs the boundary. Occasional pruning wounds. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 186	Early-mature Norway Maple *Acer platanoides*	15	3	41	8	Single stemmed, slight lean with a slightly unbalanced crown. Crown overhangs sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 187	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	7	1	15	5	Single stemmed, vertical with a balanced crown. Suppressed specimen. Crown overhangs the boundary. Deadwood noted (minor).	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 188	Mature Common Ash *Fraxinus excelsior*	21	2	94	13	Single stemmed, slight lean with a balanced crown. Crown overhangs sports field. Decay forming at 2m.	FAIR	FAIR	20-40	HIGH	Monitor annually.	LOW	B	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 189	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	13	3	32	7	Single stemmed, vertical with a slightly unbalanced crown. Suppressed specimen. Crown overhangs sports field. Occasional pruning wounds. Deadwood noted (minor).	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 190	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	9	1	23	4	Single stemmed, vertical with an unbalanced crown. Suppressed specimen. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 191	Early-mature Common Lime *Tilia europaea*	21	6	30	11	Multiple stemmed at 0m. Slight lean with an unbalanced crown biased toward the sports field. Decay forming at base with a significant included union at base also. This tree in now very exposed due to the recent failure of the adjacent tree.	FAIR	FAIR	<10	HIGH	Pollard at 4m.	MOD	B	2
T 192	Early-mature Common Ash *Fraxinus excelsior*	12	3	27	9	Single stemmed with a major stem lean due to past suppression. This tree in now very exposed due to the recent failure of the adjacent tree. Limited long term future.	FAIR	POOR	<10	HIGH	Remove.	MOD	R	n/a
T 193	Early-mature Sycamore *Acer pseudoplatanus*	17	2	45	9	Single stemmed with a major stem lean due to past suppression. This tree in now very exposed due to the recent failure of the adjacent tree. Limited long term future.	FAIR	POOR	10-20	HIGH	Remove.	MOD	R	n/a
T 194	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	18	1	73	9	Twin stemmed at 5.5m, vertical with a balanced crown. Crown overhangs sports field. Early symptoms of Bleeding Canker of Horse Chestnut.	FAIR	FAIR	10-20	HIGH	Monitor progress of bleeding canker annually.	LOW	B	1
T 195	Early-mature Common Lime *Tilia europaea*	16	0.5	59	12	Twin stemmed at 0m, vertical with a balanced crown. Crown overhangs sports field. Occasional pruning wounds. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 196	Mature Sycamore *Acer pseudoplatanus*	18	2	79	11	Twin stemmed at 4m, slight lean with a balanced crown. Crown overhangs sports field. Occasional pruning wounds. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 197	Early-mature Common Ash *Fraxinus excelsior*	18	2	53	13	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs sports field. Occasional pruning wounds. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 198	Mature Sycamore *Acer pseudoplatanus*	20	2	119	13	Twin stemmed at 2m, vertical with a balanced crown. Crown overhangs sports field. Dense vegetation at base prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation and re-inspect.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 199	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	11	1	23	7	Twin stemmed at 0.5m with an unbalanced crown. Suppressed specimen. Occasional pruning wounds due to crown lifting. Crossing branches. Deadwood noted (minor).	FAIR	FAIR	10-20	MOD	No action required.	N/A	A	2
T 200	Early-mature Sycamore *Acer pseudoplatanus*	13	2	27	6	Single stemmed, slight lean with an unbalanced crown. Crown overhangs the boundary. Occasional pruning wounds. Deadwood noted (minor).	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 201	Early-mature Common Lime *Tilia europaea*	20	15	35	6	Single stemmed, vertical with an unbalanced crown. Drawn up specimen. Close to boundary. Deadwood noted (minor).	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 202	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	19	2	52	8	Single stemmed, vertical with an unbalanced crown. Occasional pruning wounds. Early symptoms of Bleeding Canker of Horse Chestnut observed.	FAIR	FAIR	20-40	MOD	Monitor progress of bleeding canker annually.	MOD	B	1
T 203	Early-mature Common Lime *Tilia europaea*	22	3	49	8	Single stemmed, slight lean with a balanced crown. Crown overhangs sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 204	Mature Common Ash *Fraxinus excelsior*	21	2	89	11	Single stemmed, vertical with a slightly unbalanced crown. Occasional pruning wounds. Dense vegetation at base prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation and re-inspect.	MOD	B	1
T 205	Semi-mature Common Ash *Fraxinus excelsior*	11	1	15	4	Single stemmed, slight lean with an unbalanced crown. Crown overhangs sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 206	Semi-mature Common Ash *Fraxinus excelsior*	9	2	21	6	Single stemmed, slight lean with a slightly unbalanced crown. Crown overhangs sports field. Occasional pruning wounds. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 207	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	7	1	21	6	Twin stemmed at 0m, slight lean with an unbalanced crown. Suppressed specimen. Occasional pruning wounds. Deadwood noted (minor).	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 208	Early-mature Common Lime *Tilia europaea*	16	7	26	5	Single stemmed, vertical with an unbalanced crown. Occasional pruning wounds. Epicormic growth on the stem.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 209	Early-mature Common Lime *Tilia europaea*	21	14	32	7	Single stemmed, vertical with a balanced crown. Drawn up specimen. Occasional pruning wounds. Ivy on stem.	FAIR	FAIR	20-40	HIGH	Remove Ivy.	LOW	B	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 210	Early-mature Sycamore *Acer pseudoplatanus*	18	2	51	9	Single stemmed, vertical with an unbalanced crown. Crown overhangs the boundary. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 211	Mature Common Ash *Fraxinus excelsior*	20	9	77	12	Single stemmed, vertical with a balanced crown. Crown overhangs the sports field. Occasional pruning wounds. Dense Ivy and understorey vegetation prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation and Ivy and re-inspect.	HIGH	B	1
T 212	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	11	1	32	8	Single stemmed, vertical with an unbalanced crown. Suppressed specimen. Crown overhangs the boundary. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 213	Mature Sycamore *Acer pseudoplatanus*	19	4	76	8	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs the boundary. Occasional pruning wounds. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 214	Early-mature Sycamore *Acer pseudoplatanus*	21	3	47	8	Single stemmed, vertical with an unbalanced crown. Crown overhangs the boundary. Occasional pruning wounds. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 215	Early-mature Common Ash *Fraxinus excelsior*	21	14	46	7	Twin stemmed at 4m. Vertical drawn up specimen. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 216	Semi-mature Sycamore *Acer pseudoplatanus*	14	4	22	6	Single stemmed, slight lean with an unbalanced crown. Suppressed specimen. Crown overhangs the boundary. Ivy on stem.	FAIR	FAIR	20-40	HIGH	Remove Ivy.	LOW	B	2
T 217	Early-mature Sycamore *Acer pseudoplatanus*	21	5	68	11	Twin stemmed at 3.5m, vertical with a balanced crown. Decay forming at tear wound at 3.5 to 5m.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 218	Early-mature Common Lime *Tilia europaea*	12	0	37	11	Single stemmed, significant lean with an unbalanced crown. Suppressed specimen. Crown overhangs sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	1
T 219	Early-mature Sycamore *Acer pseudoplatanus*	19	3	32	8	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 220	Early-mature Sycamore *Acer pseudoplatanus*	19	15	26	5	Single stemmed, vertical with a balanced crown. Drawn up specimen. Close to boundary. Decay forming at base.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 221	Early-mature Sycamore *Acer pseudoplatanus*	20	10	28	7	Single stemmed. Vertical drawn up specimen. Crown overhangs the boundary. Deadwood noted (minor). Sparse crown.	FAIR	FAIR	10-20	HIGH	Monitor sparse crown annually.	MOD	B	1
T 222	Semi-mature Common Holly *Ilex aquifolium*	9	0	21	4	Twin stemmed at 0m, vertical with a balanced crown. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 223	Early-mature Common Ash *Fraxinus excelsior*	5	3	39	2	Single stemmed. Previously pollarded to 4m with young regrowth .	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 224	Early-mature Sycamore *Acer pseudoplatanus*	17	3	37	7	Twin stemmed at 1.5m, vertical with a slightly unbalanced crown. Crown overhangs the boundary. Occasional pruning wounds. Deadwood noted (minor). Epicormic growth at the base.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 225	Early-mature Common Lime *Tilia europaea*	19	3	38	8	Single stemmed, vertical with a balanced crown. Crown overhangs the boundary. Decay to stem. at 1.5 to 3m.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 226	Early-mature Sycamore *Acer pseudoplatanus*	17	2.5	33	7	Single stemmed, vertical with a balanced crown. Significant decay forming at 1 to 3m with no compartmentalisation. Limited long term future.	FAIR	FAIR	<10	HIGH	Remove.	LOW	R	n/a
T 227	Semi-mature Sycamore *Acer pseudoplatanus*	12	8	17	3	Single stemmed, slight lean with a slightly unbalanced crown. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 228	Mature Common Oak *Quercus robur*	21	2	83	12	Single stemmed, vertical with a balanced crown. Crown overhangs sports field. Deadwood noted (major). Several dead branches in lower crown over sports pitch.	GOOD	FAIR	20-40	HIGH	Remove dead branches.	HIGH	B	2
T 229	Semi-mature Sycamore *Acer pseudoplatanus*	8	2	10	4	Single stemmed, vertical with a balanced crown. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 230	Semi-mature Sycamore *Acer pseudoplatanus*	13	2	21	5	Twin stemmed at 2m, vertical with a slightly unbalanced crown. Crown overhangs sports field. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 231	Semi-mature Common Ash *Fraxinus excelsior*	6	1	12	3	Single stemmed, vertical with a slightly unbalanced crown. No major visible defects.	GOOD	GOOD	40+	MOD	No action required.	N/A	A	2
T 232	Semi-mature Common Holly *Ilex aquifolium*	8	0	18	5	Twin stemmed at 0.5m, slight lean with a slightly unbalanced crown. Bark wounding with decay at 0 to 1m.	FAIR	FAIR	10-20	MOD	Monitor annually.	LOW	B	1
T 233	Early-mature Common Holly *Ilex aquifolium*	9	1	15	5	90% dead. No long term future.	POOR	POOR	<10	MOD	Remove.	MOD	R	n/a
T 234	Early-mature Common Holly *Ilex aquifolium*	8	1	13	5	Twin stemmed at 0m, vertical with an unbalanced crown. Suppressed specimen. Minor basal bark wounds observed.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 235	Over-mature Sycamore *Acer pseudoplatanus*	17	4	69	9	Single stemmed, vertical with a balanced crown. Occasional pruning wounds due to crown lifting, healing slowly. Decay forming at base and on old pruning wound at 1.5m.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 236	Early-mature Common Oak *Quercus robur*	18	5	46	8	Single stemmed, vertical with a balanced crown. Crown overhangs the boundary. Occasional pruning wounds due to crown lifting, healing slowly. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 237	Early-mature Sycamore *Acer pseudoplatanus*	15	5	35	7	Twin stemmed at 1.5m, vertical with a balanced crown. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 238	Early-mature Common Lime *Tilia europaea*	19	3	27	6	Single stemmed, vertical with a balanced crown. Drawn up specimen. Crown overhangs the boundary. Occasional pruning wounds due to crown lifting, generally healing well.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 239	Early-mature Sycamore *Acer pseudoplatanus*	17	4	25	5	Single stemmed, vertical with an unbalanced crown. Crown overhangs the boundary. Occasional pruning wounds due to crown lifting. Dense vegetation at base prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation and re-inspect.	MOD	B	1
T 240	Early-mature Common Holly *Ilex aquifolium*	13	0	27	5	Single stemmed, vertical with a slightly unbalanced crown. Occasional pruning wounds. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 241	Early-mature Common Holly *Ilex aquifolium*	8	0	23	4	Twin stemmed at 0m, slight lean with an unbalanced crown. Suppressed specimen. Occasional pruning wounds. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 242	Early-mature Common Ash *Fraxinus excelsior*	17	2	37	8	Single stemmed, slight lean with an unbalanced crown. Crown overhangs sports field. Occasional pruning wounds. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 243	Early-mature Sycamore *Acer pseudoplatanus*	18	3	43	7	Single stemmed, vertical with an unbalanced crown. Crown overhangs sports field. Occasional pruning wounds. Moderate deadwood in lower crown	GOOD	FAIR	20-40	HIGH	Remove larger deadwood.	MOD	B	2
T 244	Early-mature Sycamore *Acer pseudoplatanus*	19	8	49	10	Twin stemmed at 4m, vertical with a balanced crown. Occasional pruning wounds. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 245	Semi-mature Sycamore *Acer pseudoplatanus*	8	1	16	3	Single stemmed, vertical with an unbalanced crown. Suppressed specimen. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 246	Early-mature Elm *Ulmus sp.*	21	7	46	8	Twin stemmed at 3m, vertical with an unbalanced crown. Crown overhangs the boundary. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 247	Early-mature Common Lime *Tilia europaea*	18	6	27	7	Single stemmed, vertical with a balanced crown. Crown overhangs the boundary. Dense vegetation at base prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation and re-inspect.	MOD	B	1
T 248	Early-mature Sycamore *Acer pseudoplatanus*	19	2.5	51	9	Single stemmed, vertical with an unbalanced crown. Crown overhangs sports field. Occasional pruning wounds. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 249	Dead Mountain Ash *Sorbus aucuparia*	6	0	16	4	Dead hung up tree	DEAD	DEAD	<10	HIGH	Remove.	MOD	R	n/a
T 250	Semi-mature Common Holly *Ilex aquifolium*	8	0	12	4	Multiple stemmed at 0m, vertical with a balanced crown. No major visible defects.	GOOD	GOOD	20-40	MOD	No action required.	N/A	A	2
T 251	Early-mature Sycamore *Acer pseudoplatanus*	17	7	27	5	Single stemmed, vertical with an unbalanced crown. Crown overhangs the footpath. Deadwood noted (major). Deadwood over footpath.	FAIR	FAIR	20-40	HIGH	Deadwood.	MOD	B	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 252	Early-mature Common Lime *Tilia europaea*	8	2	24	5	Twin stemmed at 1m, slight lean with a balanced crown. Suppressed specimen. No major visible defects. Previously topped.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 253	Early-mature Sycamore *Acer pseudoplatanus*	18	8	37	7	Single stemmed, vertical with a balanced crown. Crown overhangs the boundary. Occasional pruning wounds due to crown lifting, healing slowly. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 254	Early-mature Mountain Ash *Sorbus aucuparia*	8	2	24	3	Twin stemmed at 1.5m, vertical with a slightly unbalanced crown. Suppressed specimen. Crown overhangs the footpath. Occasional pruning wounds due to crown lifting, healing slowly. Deadwood noted (minor).	FAIR	FAIR	10-20	MOD	No action required.	N/A	A	2
T 255	Early-mature Elm *Ulmus sp.*	20	10	33	9	Single stemmed, vertical with a balanced crown. Drawn up specimen. Crown overhangs the footpath. Large deadwood over footpath in lower crown	FAIR	FAIR	10-20	HIGH	Deadwood.	MOD	B	2
T 256	Semi-mature Field Maple *Acer campestre*	8	2	17	6	Twin stemmed at 1.5m, vertical with a slightly unbalanced crown. Suppressed specimen. Crown overhangs the footpath. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 257	Early-mature Common Oak *Quercus robur*	16	2	37	8	Single stemmed, vertical with an unbalanced crown. Crown overhangs sports field. Epicormic growth on the stem and in crown resulted in a limited inspection. Deadwood also noted in the crown.	FAIR	FAIR	20-40	HIGH	Remove larger deadwood and the epicormic growth from the stem and crown.	MOD	B	2
T 258	Early-mature Common Lime *Tilia europaea*	21	4	43	8	Single stemmed, slight lean with a slightly unbalanced crown. Crown overhangs sports field. Dense Ivy at base prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 259	Early-mature Common Beech *Fagus sylvatica*	17	2	26	6	Single stemmed, vertical with a balanced crown. Crown overhangs sports field. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 260	Early-mature Unknown Dead Tree	4	4	35	0	Dead ivy clad stem. Considered unstable.	DEAD	DEAD	<10	HIGH	Remove.	MOD	R	n/a
T 261	Semi-mature Field Maple *Acer campestre*	14	3	17	4	Single stemmed, vertical with a slightly unbalanced crown. Drawn up specimen. Crown overhangs sports field. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 262	Early-mature Sycamore *Acer pseudoplatanus*	16	5	26	6	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs the footpath. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 263	Early-mature Common Lime *Tilia europaea*	19	3	47	7	Single stemmed, vertical with a balanced crown. Crown overhangs the building and footpath. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 264	Early-mature Sycamore *Acer pseudoplatanus*	17	2	63	8	Single stemmed, vertical with an unbalanced crown. Crown overhangs sports field. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	HIGH	B	1
T 265	Early-mature Common Hornbeam *Carpinus betulus*	13	1	23	8	Multiple stemmed at 0m, slight lean with an unbalanced crown. Suppressed specimen. Crown overhangs sports field. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 266	Mature Sycamore *Acer pseudoplatanus*	19	3	87	12	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs the building and sports field. Cavities forming in old pruning wounds. Sparse crown noted.	GOOD	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 267	Early-mature Sycamore *Acer pseudoplatanus*	17	3	46	10	Twin stemmed at 3m, vertical with an unbalanced crown. Crown overhangs the sports court. Occasional pruning wounds due to crown lifting, healing slowly. Bark wounding to stem with the onset of decay at lowest branch junctions.	FAIR	FAIR	20-40	HIGH	Remove branches affected by stem decay in low crown to the south.	MOD	B	1
T 268	Mature Sycamore *Acer pseudoplatanus*	21	6	83	11	Single stemmed, vertical with a balanced crown. Crown overhangs the building and footpath. Multiple pruning wounds due to crown lifting. Tear wounds and cavities forming at old pruning wounds.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 269	Early-mature Common Holly *Ilex aquifolium*	9	3	26	4	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs the footpath. Multiple pruning wounds due to crown lifting, generally healing well. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 270	Early-mature Common Holly *Ilex aquifolium*	8	4	24	4	Single stemmed, vertical with a balanced crown. Crown overhangs the building. Occasional pruning wounds due to crown lifting, generally healing well. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 271	Early-mature Common Holly *Ilex aquifolium*	10	4	26	6	Twin stemmed at 0m, vertical with a balanced crown. Crown overhangs the footpath. Occasional pruning wounds due to crown lifting, generally healing well. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 272	Early-mature Common Holly *Ilex aquifolium*	11	4	24	4	Single stemmed, vertical with a balanced crown. Crown overhangs the footpath. Occasional pruning wounds due to crown lifting, generally healing well. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 273	Semi-mature Common Holly *Ilex aquifolium*	9	4	13	4	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs the footpath. Occasional pruning wounds due to crown lifting. Generally healing well. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 274	Early-mature Common Holly *Ilex aquifolium*	8	3	24	4	Multiple stemmed at 0m, vertical with a balanced crown. Crown overhangs the footpath. Sparse upper crown suggests the tree may be in decline.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 275	Semi-mature Common Holly *Ilex aquifolium*	7	2	16	4	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs the footpath. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 276	Early-mature Common Holly *Ilex aquifolium*	10	2	25	4	Twin stemmed at 0m, vertical with a balanced crown. Crown overhangs the footpath. Occasional pruning wounds due to crown lifting, generally healing well. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 277	Early-mature Common Holly *Ilex aquifolium*	11	3	15	4	Twin stemmed at 0m, vertical with a balanced crown. Crown overhangs the footpath. Occasional pruning wounds due to crown lifting, generally healing well. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 278	Early-mature Common Holly *Ilex aquifolium*	9	3	25	4	Multiple stemmed at 0m, vertical with a balanced crown. Crown overhangs the footpath. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 279	Early-mature Common Holly *Ilex aquifolium*	11	3	27	4	Single stemmed, vertical with a balanced crown. Crown overhangs the footpath. Occasional pruning wounds due to crown lifting, healing slowly.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 280	Semi-mature Common Holly *Ilex aquifolium*	6	2	12	3	Twin stemmed at 0.3m, vertical with a balanced crown. Crown overhangs the footpath. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 281	Semi-mature Common Holly *Ilex aquifolium*	5	2	13	3	Twin stemmed at 0m, vertical with a balanced crown. Crown overhangs the footpath. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 282	Semi-mature Common Holly *Ilex aquifolium*	5	2	15	3	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs the footpath. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 283	Early-mature European Larch *Larix decidua*	18	4	37	11	Single stemmed, vertical with a balanced crown. Crown overhangs the footpath and building. Occasional pruning wounds due to crown lifting, healing slowly. Deadwood noted (minor). No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 284	Early-mature Common Holly *Ilex aquifolium*	8	0.5	18	4	Single stemmed, vertical with a balanced crown. Crown overhangs the footpath and building. One stem is dead with the other having significant bark wounding with the onset of decay. Limited future.	POOR	FAIR	<10	HIGH	Remove.	MOD	R	n/a
T 285	Early-mature Common Beech *Fagus sylvatica*	18	4	37	9	Single stemmed, vertical with a balanced crown. Crown overhangs the boundary. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	10-20	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 286	Early-mature Common Beech *Fagus sylvatica*	19	2	42	11	Single stemmed, vertical with a balanced crown. Crown overhangs the boundary. Occasional pruning wounds due to crown lifting, generally healing well. Deadwood noted (minor). Appears to be in an acceptable condition at this time.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 287	Early-mature Sycamore *Acer pseudoplatanus*	18	5	73	9	Single stemmed, vertical with a balanced crown. Crown overhangs the boundary. Basal bark wounds. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 288	Mature Common Ash *Fraxinus excelsior*	21	9	72	10	Twin stemmed at 3m, vertical with a balanced crown. Crown overhangs the building and footpath. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 289	Early-mature Common Beech *Fagus sylvatica*	17	3	65	10	Single stemmed, vertical with a balanced crown. Crown overhangs the boundary and building. Occasional pruning wounds due to crown lifting. healing slowly. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 290	Mature Sycamore *Acer pseudoplatanus*	18	3	75	9	Single stemmed, vertical with a balanced crown. Crown overhangs the boundary. Occasional pruning wounds due to crown lifting, generally healing well. Dense Ivy on stem prevented detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 291	Mature Sycamore *Acer pseudoplatanus*	21	5	89	12	Twin stemmed at 6m, vertical with a balanced crown. Crown overhangs the boundary and building. Multiple pruning wounds due to crown lifting, healing slowly. Cavities forming at old pruning wounds with decayed wood present.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 292	Mature Common Lime *Tilia europaea*	21	3	75	8	Single stemmed, vertical with a balanced crown. Crown overhangs the footpath and building. Occasional pruning wounds due to crown lifting. Deadwood noted (minor). Epicormic growth at the base.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 293	Semi-mature Common Holly *Ilex aquifolium*	8	1	12	3	Twin stemmed at 0m, vertical with a balanced crown. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 294	Semi-mature Common Holly *Ilex aquifolium*	8	1	15	3	Single stemmed, vertical with a balanced crown. No major visible defects.	GOOD	GOOD	20-40	HIGH	No action required.	N/A	A	2
T 295	Semi-mature Common Holly *Ilex aquifolium*	8	1	15	3	Single stemmed, vertical with a balanced crown. No major visible defects.	GOOD	GOOD	20-40	HIGH	No action required.	N/A	A	2
T 296	Mature Sycamore *Acer pseudoplatanus*	18	7	89	11	Twin stemmed at 2m, vertical with a balanced crown. Major areas of dying bark to stem with the early onset of decay. Decay detection required to determine the extent of decay and possible remedial works required.	FAIR to POOR	FAIR	<10	HIGH	Decay detection survey required.	HIGH	B	n/a
T 297	Early-mature Common Holly *Ilex aquifolium*	9	2	24	4	Single stemmed, vertical with a balanced crown. Basal bark wounds noted.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 298	Mature Common Lime *Tilia europaea*	22	6	71	11	Twin stemmed at 4m, vertical with a balanced crown. Crown overhangs the driveway, footpath and building. Occasional pruning wounds due to crown lifting, generally healing well. Deadwood noted (major).	FAIR	FAIR	20-40	HIGH	Remove larger deadwood.	HIGH	B	1
T 299	Early-mature Common Holly *Ilex aquifolium*	8	2	17	4	Single stemmed, slight lean with a balanced crown. Suppressed specimen. No major visible defects.	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 300	Early-mature Common Holly *Ilex aquifolium*	11	1	27	5	Twin stemmed at 0m, slight lean with a slightly unbalanced crown. Crown overhangs the road. Occasional pruning wounds due to crown lifting, generally healing well. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 301	Early-mature Common Holly *Ilex aquifolium*	12	1	26	5	Multiple stemmed at 0m, vertical with a slightly unbalanced crown. Occasional pruning wounds due to crown lifting, healing slowly. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 302	Mature Common Lime *Tilia europaea*	21	10	47	11	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs the road. Necrotic bark to stem. possibly in decline.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 303	Early-mature Goat Willow *Salix caprea*	15	10	37	9	Twin stemmed at 0m, vertical with a balanced crown. Decay and strips of dead bark throughout. Possibly in decline. Pollard to 3m and allow the crown to rejuvenate.	POOR	FAIR	10-20	HIGH	Pollard to 3m and maintain.	MOD	B	2
T 304	Early-mature Common Holly *Ilex aquifolium*	8	2	24	4	Twin stemmed at 0m, vertical with an unbalanced crown. Suppressed specimen. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 305	Early-mature Norway Maple *Acer platanoides*	16	3	27	8	Multiple stemmed at 0m, vertical with a balanced crown. Crown overhangs the footpath and road. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 306	Mature Common Holly *Ilex aquifolium*	15	4	36	8	Twin stemmed at 0m, vertical with a balanced crown. Crown overhangs the road. Occasional pruning wounds due to crown lifting, generally healing well. Appears to be in an acceptable condition at this time	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 307	Early-mature Common Holly *Ilex aquifolium*	11	3	26	5	Single stemmed, slight lean with a balanced crown. Crown overhangs the footpath. Occasional pruning wounds due to crown lifting. Bark wounding with onset of decay at 2 to 3m	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 308	Early-mature Common Holly *Ilex aquifolium*	11	3	26	5	Twin stemmed at 0m, vertical with a balanced crown. Multiple pruning wounds due to crown lifting, generally healing well. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 309	Early-mature Common Holly *Ilex aquifolium*	8	4	12	4	Multiple stemmed at 0m, slight lean with a slightly unbalanced crown. Suppressed specimen. Occasional pruning wounds due to crown lifting, generally healing well.	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 310	Mature Common Lime *Tilia europaea*	18	7	75	11	Single stemmed, vertical with a balanced crown. Crown overhangs the footpath. Occasional pruning wounds due to crown lifting, generally healing well. Deadwood noted (minor). Epicormic growth in the crown. Appears to be in an acceptable condition at this time.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 311	Semi-mature Common Holly *Ilex aquifolium*	6	2	14	4	Multiple stemmed at 0m, vertical with a slightly unbalanced crown. Suppressed specimen. Occasional pruning wounds due to crown lifting. No major visible defects.	FAIR	FAIR	10-20	MOD	No action required.	N/A	A	2
T 312	Mature Common Lime *Tilia europaea*	21	8	73	10	Single stemmed, vertical with a balanced crown. Crown overhangs the road. Occasional pruning wounds due to crown lifting, generally healing well. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	Remove larger deadwood over targets.	MOD	B	1
T 313	Semi-mature Common Holly *Ilex aquifolium*	5	2	14	3	Single stemmed, vertical with a balanced crown. Crown overhangs the road. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 314	Mature Sycamore *Acer pseudoplatanus*	18	9	74	11	Single stemmed, slight lean with a balanced crown. Crown overhangs the road. Multiple pruning wounds due to crown lifting, healing slowly. Sparse crown suggests the tree may be in decline. Deadwood over benches.	FAIR	FAIR	10-20	HIGH	Remove larger deadwood over targets and monitor annually.	MOD	B	1
T 315	Early-mature Common Holly *Ilex aquifolium*	11	3	27	4	Twin stemmed at 0m, slight lean with a slightly unbalanced crown. Crown overhangs the footpath. Multiple pruning wounds due to crown lifting, generally healing well. Bark wounds. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 316	Early-mature Common Holly *Ilex aquifolium*	11	3	26	4	Multiple stemmed at 0m, slight lean with a slightly unbalanced crown. Crown overhangs the footpath. Occasional pruning wounds due to crown lifting. Necrotic bark wounding with decay forming at 4m.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 317	Semi-mature Common Holly *Ilex aquifolium*	11	2	18	4	Single stemmed, vertical with a slightly unbalanced crown. Occasional pruning wounds due to crown lifting, generally healing well. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 318	Early-mature Common Holly *Ilex aquifolium*	11	2.5	27	7	Single stemmed, significant lean due to suppression with a balanced crown. Crown overhangs the road. Occasional pruning wounds due to crown lifting, generally healing well.	FAIR	FAIR	10-20	HIGH	Monitor lean annually.	MOD	B	1
T 319	Early-mature Common Holly *Ilex aquifolium*	12	0	19	4	Twin stemmed at 0.5m, vertical with a balanced crown. Tight union noted. Appears to be in an acceptable condition at this time.	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 320	Mature Common Holly *Ilex aquifolium*	13	0.5	27	6	Multiple stemmed at 0m, vertical with a slightly unbalanced crown. Multiple pruning wounds due to crown lifting, healing slowly. Basal bark wounds noted. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 321	Mature Common Holly *Ilex aquifolium*	12	1	32	6	Multiple stemmed at 0m, vertical with a slightly unbalanced crown. Crown overhangs the road. Multiple pruning wounds due to crown lifting, generally healing well. Basal bark wounds noted. Deadwood noted (minor).	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 322	Mature Weeping Ash *Fraxinus pendula*	16	3	78	11	Single stemmed, vertical with a balanced crown. Crown overhangs sports field. Decay forming at large poorly executed pruning wound at 2.5m.	FAIR	FAIR	10-20	HIGH	Monitor progress of decay annually.	MOD	B	1
T 323	Early-mature Silver Birch *Betula pendula*	17	3	45	8	Single stemmed, vertical with an unbalanced crown. Suppressed specimen. Crown overhangs the adjacent building. Occasional pruning wounds. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 324	Mature Silver Lime *Tilia tormentosa*	19	2	109	14	Single stemmed, vertical with a balanced crown. Crown overhangs the adjacent building and footpath. Multiple pruning wounds due to crown lifting, generally healing well. Deadwood noted (minor). Several over-extended branches. Appears to be in an acceptable condition at this time	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 325	Early-mature Common Holly *Ilex aquifolium*	12	1	31	5	Twin stemmed at 0m, slight lean with an unbalanced crown. Suppressed specimen. Crown overhangs sports field. Occasional pruning wounds due to crown lifting, healing slowly. Tight union with significant included bark at 2m.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 326	Early-mature Common Holly *Ilex aquifolium*	17	1	39	7	Single stemmed, slight lean with a slightly unbalanced crown. Drawn up specimen. Crown overhangs sports field. Multiple pruning wounds due to crown lifting, healing slowly. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 327	Early-mature Common Holly *Ilex aquifolium*	17	1	38	7	Twin stemmed at 0m, slight lean with a slightly unbalanced crown. Crown overhangs the footpath and sports field. Occasional pruning wounds due to crown lifting, healing slowly. Tight union with included bark at base and decay forming at 0.5m.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 328	Semi-mature Flowering Cherry *Prunus sp.*	8	2	25	4	Twin stemmed at 1.5m, vertical with a slightly unbalanced crown. Crown overhangs the footpath. Occasional pruning wounds due to crown lifting, healing slowly. Tight union at 1.5m.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 329	Semi-mature Common Holly *Ilex aquifolium*	12	2	24	4	Single stemmed, vertical with a balanced crown. Crown overhangs the building and footpath. Occasional pruning wounds due to crown lifting, generally healing well. Ivy on stem.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 330	Early-mature Common Holly *Ilex aquifolium*	12	3	27	4	Single stemmed, slight lean with a slightly unbalanced crown. Crown overhangs the footpath. Occasional pruning wounds due to crown lifting, generally healing well.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 331	Semi-mature Common Holly *Ilex aquifolium*	9	1	10	3	Multiple stemmed at 0m, vertical with a slightly unbalanced crown. Crown overhangs the building. Occasional pruning wounds due to crown lifting, generally healing well. Deadwood noted (minor).	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 332	Semi-mature Common Holly *Ilex aquifolium*	9	1	13	4	Multiple stemmed at 0m, vertical with a balanced crown. Occasional pruning wounds due to crown lifting, generally healing well.	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 333	Semi-mature Common Ash *Fraxinus excelsior*	16	4	31	6	Twin stemmed at 0.5m, vertical with a balanced crown. Crown overhangs the building. Rubbing branches observed which are slowly causing wounds.	FAIR	FAIR	10-20	HIGH	Monitor wounding caused by rubbing branches annually.	MOD	B	1
T 334	Semi-mature Common Holly *Ilex aquifolium*	7	2	10	3	Twin stemmed at 0m, slight lean with a slightly unbalanced crown. Suppressed specimen. Crown overhangs the building. Occasional pruning wounds due to crown lifting.	GOOD	GOOD	20-40	MOD	No action required.	N/A	A	2
T 335	Semi-mature Common Holly *Ilex aquifolium*	6	3	15	4	Single stemmed, vertical with a balanced crown. Occasional pruning wounds due to crown lifting. No major visible defects.	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 336	Semi-mature Common Holly *Ilex aquifolium*	6	2	10	3	Single stemmed, vertical with a balanced crown. No major visible defects.	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 337	Semi-mature Common Holly *Ilex aquifolium*	6	1	14	3	Single stemmed, slight lean with a slightly unbalanced crown. No major visible defects.	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 338	Mature Sycamore *Acer pseudoplatanus*	18	5	69	10	Single stemmed, vertical with a balanced crown. Crown overhangs play area. Occasional pruning wounds due to crown lifting. Deadwood noted (minor). Tear wounds noted.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 339	Semi-mature Common Holly *Ilex aquifolium*	7	2.5	10	3	Single stemmed, vertical with a slightly unbalanced crown. Suppressed specimen. Occasional pruning wounds due to crown lifting. Generally healing well. No major visible defects.	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 340	Early-mature Silver Birch *Betula pendula*	16	5	29	9	Twin stemmed at 2.5m, vertical with a balanced crown. Crown overhangs play area. Occasional pruning wounds due to crown lifting, healing slowly. Cavity with the onset decay at 2m.	GOOD	FAIR	20-40	HIGH	Monitor progress of the decay annually.	MOD	B	1
T 341	Semi-mature Common Holly *Ilex aquifolium*	9	2	17	4	Twin stemmed at 0m, slight lean with an unbalanced crown. Suppressed specimen. Crown overhangs play area. Occasional pruning wounds due to crown lifting, generally healing well. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 342	Early-mature Common Lime *Tilia europaea*	17	5	64	9	Single stemmed, vertical with a balanced crown. Crown overhangs play area. Moderate deadwood noted. Dark exudates from the stem at 3m suggests possible fungal or viral infection.	FAIR	FAIR	10-20	HIGH	Remove larger deadwood. Monitor annually.	MOD	B	1
T 343	Semi-mature Common Holly *Ilex aquifolium*	6	2	12	3	Single stemmed, vertical with a slightly unbalanced crown. Suppressed specimen. Crown overhangs play area. Occasional pruning wounds due to crown lifting, generally healing well.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 344	Semi-mature Common Holly *Ilex aquifolium*	9	2	27	5	Single stemmed, leaning with an unbalanced crown. Suppressed specimen. Crown overhangs play area. Occasional pruning wounds due to crown lifting, generally healing well.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 345	Semi-mature Common Holly *Ilex aquifolium*	9	2	26	4	Twin stemmed at 2.5m, vertical with a balanced crown. Crown overhangs play area. Occasional pruning wounds due to crown lifting, generally healing well.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 346	Semi-mature Common Holly *Ilex aquifolium*	2	0	13	3	Single stemmed, vertical with a balanced crown. No major visible defects.	GOOD	GOOD	20-40	MOD	No action required.	N/A	A	2
T 347	Early-mature Sycamore *Acer pseudoplatanus*	15	2	18	7	Multiple stemmed at 0m, vertical with a balanced crown. Crown overhangs the building and sports court. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 348	Early-mature Sycamore *Acer pseudoplatanus*	15	6	24	6	Multiple stemmed at 0m, vertical with a balanced crown. Crown overhangs sports court. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 349	Semi-mature Mountain Ash *Sorbus aucuparia*	11	7	15	4	Single stemmed, vertical with a balanced crown. Drawn up specimen. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 350	Semi-mature Common Ash *Fraxinus excelsior*	14	8	26	5	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs sports court. Occasional pruning wounds due to crown lifting. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 351	Early-mature Common Ash *Fraxinus excelsior*	16	5	36	9	Single stemmed, vertical with a balanced crown. Crown overhangs sports court. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 352	Early-mature Sycamore *Acer pseudoplatanus*	13	7	33	6	Single stemmed, slight lean with a balanced crown. Suppressed specimen. Crown overhangs sports court. Sparse crown.	FAIR	FAIR	20-40	HIGH	Monitor sparse crown annually.	MOD	B	1
T 353	Semi-mature Sycamore *Acer pseudoplatanus*	7	2	13	3	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs sports court. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	MOD	Remove the Ivy and re-inspect.	MOD	B	1
T 354	Early-mature Sycamore *Acer pseudoplatanus*	16	7	37	8	Single stemmed, vertical with an unbalanced crown. Crown overhangs sports court. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 355	Early-mature Scots Pine *Pinus sylvestris*	16	5	27	3	Single stemmed, vertical with a balanced crown. Crown overhangs play area. Deadwood noted (minor). Ivy on stem.	GOOD	FAIR	20-40	HIGH	Remove Ivy.	LOW	B	2
T 356	Early-mature Silver Birch *Betula pendula*	14	7	27	7	Single stemmed, leaning with an unbalanced crown. Suppressed specimen. Crown overhangs sports court. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 357	Semi-mature Common Holly *Ilex aquifolium*	8	1	23	4	Single stemmed, vertical with a slightly unbalanced crown. Suppressed specimen. Crown overhangs play area. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 358	Early-mature Corsican Pine *Pinus nigra var.maritima*	17	6	37	4	Single stemmed, vertical with a balanced crown. Crown overhangs play area. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 359	Early-mature Common Holly *Ilex aquifolium*	9	2	23	3	Single stemmed, slight lean with an unbalanced crown. Suppressed specimen. Crown overhangs play area. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 360	Semi-mature Common Holly *Ilex aquifolium*	8	2	12	3	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs sports court.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 361	Early-mature Sycamore *Acer pseudoplatanus*	17	7	29	7	Single stemmed, vertical with a balanced crown. Crown overhangs sports court. Basal bark wounding with the onset of decay.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 362	Semi-mature Common Holly *Ilex aquifolium*	9	2	12	4	Twin stemmed at 0m, vertical with a slightly unbalanced crown. Crown overhangs play area.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 363	Early-mature Sycamore *Acer pseudoplatanus*	15	7	34	7	Single stemmed, vertical with an unbalanced crown. Crown overhangs sports court. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 364	Semi-mature Sycamore *Acer pseudoplatanus*	8	2	13	3	Single stemmed, vertical with a balanced crown. Crown overhangs sports court. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation and re-inspect.	MOD	B	1
T 365	Semi-mature Common Holly *Ilex aquifolium*	8	1	14	3	Single stemmed, vertical with a balanced crown. No major visible defects.	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 366	Semi-mature Sycamore *Acer pseudoplatanus*	9	3	23	4	Single stemmed, slight lean with a slightly unbalanced crown. Crown overhangs play area. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 367	Semi-mature Common Holly *Ilex aquifolium*	8	1	13	3	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs play area. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 368	Early-mature Flowering Cherry *Prunus sp.*	9	3	31	7	Single stemmed, slight lean with a slightly unbalanced crown. Crown overhangs sports court. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 369	Semi-mature Sycamore *Acer pseudoplatanus*	7	2	13	3	Single stemmed, vertical with a balanced crown. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 370	Semi-mature Common Holly *Ilex aquifolium*	7	0	12	3	Multiple stemmed at 0m, vertical with a balanced crown. Crown overhangs the footpath. Occasional pruning wounds due to crown lifting.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 371	Early-mature Common Hawthorn *Crataegus monogyna*	6	2	19	3	Twin stemmed at 0.75m, vertical with a balanced crown. Crown overhangs the footpath. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 372	Semi-mature Common Holly *Ilex aquifolium*	7	0.5	13	3	Single stemmed, vertical, with a slightly unbalanced crown. Crown overhangs the footpath.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 373	Early-mature Goat Willow *Salix caprea*	14	2	21	7	Twin stemmed at 0m, vertical with a balanced crown. Crown overhangs sports field and sports court. Occasional pruning wounds due to crown lifting. Tight union with included bark at base.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 374	Mature Goat Willow *Salix caprea*	14	2	83	8	Multiple stemmed at 1m, vertical with a balanced crown. Crown overhangs the footpath, sports court and sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 375	Semi-mature Common Ash *Fraxinus excelsior*	14	9	15	4	Twin stemmed at 0m, vertical with a balanced crown. Crown overhangs sports court. Occasional pruning wounds due to crown lifting.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 376	Semi-mature Common Hawthorn *Crataegus monogyna*	6	3	15	4	Single stemmed, leaning with a unbalanced crown. Suppressed specimen. Crown overhangs the footpath. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 377	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	15	4	32	9	Single stemmed, vertical with an unbalanced crown. Crown overhangs the footpath and sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 378	Early-mature Common Lime *Tilia europaea*	18	4	51	11	Single stemmed, vertical with a balanced crown. Crown overhangs sports field and sports court. Occasional pruning wounds due to crown lifting, healing slowly. Deadwood noted (minor). Bark wounds.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 379	Early-mature Common Lime *Tilia europaea*	18	6	54	9	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs sports court and sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 380	Early-mature Common Lime *Tilia europaea*	16	6	47	11	Single stemmed, vertical with an unbalanced crown. Crown overhangs sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor). Suppressed specimen with unusual form.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 381	Early-mature Common Ash *Fraxinus excelsior*	14	9	26	5	Single stemmed, vertical with a balanced crown. Crown overhangs sports court. Occasional pruning wounds due to crown lifting, healing slowly.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 382	Semi-mature Common Ash *Fraxinus excelsior*	14	1	12	6	Multiple stemmed at 0m, vertical with a balanced crown. Crown overhangs sports court and sports field. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 383	Early-mature Sycamore *Acer pseudoplatanus*	14	2	27	5	Single stemmed, vertical with a balanced crown. Crown overhangs sports court. Ivy on stem.	GOOD	FAIR	20-40	HIGH	Remove Ivy.	LOW	B	2
T 384	Early-mature Common Ash *Fraxinus excelsior*	13	9	15	4	Single stemmed, vertical with a balanced crown. Crown overhangs sports court. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy and re-inspect.	MOD	B	1
T 385	Early-mature Common Ash *Fraxinus excelsior*	14	9	24	6	Twin stemmed at 0m, vertical with a balanced crown. Crown overhangs sports court. Multiple pruning wounds due to crown lifting, healing slowly.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 386	Semi-mature Sycamore *Acer pseudoplatanus*	9	2	13	4	Single stemmed, vertical with an unbalanced crown. Crown overhangs sports court. Occasional pruning wounds due to crown lifting, healing slowly.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 387	Semi-mature Sycamore *Acer pseudoplatanus*	8	2	13	4	Twin stemmed at 0m, vertical with an unbalanced crown. Crown overhangs sports field. Minor dieback observed. Appears to be in an acceptable condition at this time.	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 388	Early-mature Common Oak *Quercus robur*	16	2	45	8	Single stemmed, vertical with an unbalanced crown. Crown overhangs sports field. Multiple pruning wounds due to crown lifting, healing slowly.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 389	Early-mature Leyland Cypress *X Cupressocyparis leylandii*	19	0	75	7	Twin stemmed at 2m, vertical with a balanced crown. Crown overhangs sports court and sports field. Occasional pruning wounds due to crown lifting, healing slowly.	GOOD	FAIR	40+	HIGH	No action required.	N/A	A	2
T 390	Semi-mature Common Ash *Fraxinus excelsior*	9	2	12	4	Multiple stemmed at 0m, vertical with a slightly unbalanced crown. Suppressed specimen. Crown overhangs sports field. Multiple pruning wounds due to crown lifting.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 391	Semi-mature Sycamore *Acer pseudoplatanus*	13	2	17	6	Multiple stemmed at 0m with a balanced crown. Crown overhangs sports court and sports field. Decay forming at base where other stems have been previously removed. Dieback throughout. Limited future.	FAIR	POOR	<10	HIGH	Remove.	MOD	R	n/a
T 392	Semi-mature Sycamore *Acer pseudoplatanus*	10	2	10	4	Multiple stemmed at 0m, vertical with a balanced crown. Crown overhangs sports field. Occasional pruning wounds due to crown lifting.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 393	Semi-mature Common Ash *Fraxinus excelsior*	12	2	12	4	Multiple stemmed at 0m, vertical with a balanced crown. Crown overhangs sports field.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 394	Semi-mature Sycamore *Acer pseudoplatanus*	6	2	11	3	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs sports court.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 395	Semi-mature Common Ash *Fraxinus excelsior*	12	3	14	4	Single stemmed, vertical with a balanced crown. Crown overhangs sports court.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 396	Semi-mature Sycamore *Acer pseudoplatanus*	9	1	21	5	Multiple stemmed at 0m, vertical with an unbalanced crown. Crown overhangs sports court and sports field. Occasional pruning wounds due to crown lifting, healing slowly. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 397	Semi-mature Common Ash *Fraxinus excelsior*	9	1	12	4	Twin stemmed at 0m, vertical with a balanced crown. Crown overhangs sports field.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 398	Semi-mature Common Ash *Fraxinus excelsior*	11	1	9	5	Multiple stemmed at 0m, vertical with a balanced crown. Crown overhangs sports field. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 399	Semi-mature Sycamore *Acer pseudoplatanus*	8	3	23	4	Single stemmed, vertical with a balanced crown. Crown overhangs sports court. Occasional pruning wounds due to crown lifting. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 400	Semi-mature Common Ash *Fraxinus excelsior*	15	3	27	7	Twin stemmed at 0.3m, vertical with a balanced crown. Crown overhangs sports court and sports field. Multiple pruning wounds due to crown lifting, healing slowly. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 401	Semi-mature Common Oak *Quercus robur*	4	0.5	24	5	Single stemmed, vertical with an unbalanced crown. Previously topped. Crown overhangs sports court. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 402	Semi-mature Common Oak *Quercus robur*	9	1	13	4	Single stemmed, vertical with a slightly unbalanced crown. Crown overhangs sports field. No major visible defects.	GOOD	GOOD	40+	HIGH	No action required.	N/A	A	2

Appendix 2: Explanation of Terms & Recommended Clearances

Canker Disease damaged area of a tree, usually caused by fungus or bacteria.

Co-dominant Stem A stem which has grown in direct competition to the main stem and which has formed a substantial size influencing the appearance of the tree.

Crown lift The removal of the lowest branches, usually to a given height. It allows more residual light and greater clearance underneath for vehicles etc.

Crown reduce The reduction of a tree's height or spread while preserving its natural shape.

Crown thin The removal of some of the density of a tree's crown**,** usually 5-25% allowing more light through its canopy and reducing wind resistance.

Deadwood The removal of all dead, dying and diseased branches from a tree.

Dieback Where branches are beginning to show signs of death usually at the tips in the crown.

Epicormic shoots Small branches that grow in uncharacteristic clusters around the base or the stem of a tree, usually as a result of bad pruning or some other stress factor.

Included bark Where the bark on two adjoining branches or stems is growing tight together, forming a joint with limited physical strength.

Pollarding A method of tree management in which the main trunk of the tree is cut at about 4m, and the resulting branches are then cropped on a regular basis.

Remedial pruning The removal of old stubs, deadwood, epicormic growth, rubbing or crossing branches and other unwanted items from the tree's crown. Sometimes referred to as crown cleaning.

Recommended Clearances

JCA recommend the following distances are maintained:

Height for pedestrian access:	No less than 2.5m
Height for vehicular access:	No less then 4m for a minor road
	No less than 6m for major roads or where buses will pass.
Distance from overhead cables:	No less than 2m
Distance from building or other structure:	No less than 2m
Distance from lamppost or sign	Sufficient to not impede visibility for 2 years.

© JCA Limited 2016

Appendix 3: Author Qualifications

Principal Consultant and Managing Director

Jonathan Cocking *F.R.E.S., Tech. Cert. (Arbor.A), PDipArb (RFS) FArborA CBiol MSB. MICFor.* Jonathan is a Registered Consultant and Fellow of the Arboricultural Association and sits on its Professional Committee. He has 31 years experience in the Arboricultural profession and served for eight years as Senior Arboriculturist with a large local authority before establishing JCA in 1997. Jonathan has since developed JCA's portfolio of services and its extensive client base. He is a Chartered Biologist, a Chartered Arboriculturalist and an Expert Witness with much experience of litigation work.

Technical Coordinator

Toby Thwaites *BSc (Hons), HND (Arboriculture).* Toby joined JCA in 1998 after graduating in Ecology at the University of Huddersfield and has since graduated in Arboriculture at the University of Central Lancashire. A former JCA team leader and Consulting Arboriculturist, Toby was promoted to Technical Coordinator and now oversees all office and on-site activities at JCA and is on hand to offer technical support and advice.

Consulting Staff: Arboriculture

Andy Bagshaw *FdSc (Arboriculture).* Andy joined JCA in 2005 having gained several years experience in tree surgery and landscaping. He is trained in aerial rescue and is JCA's principal first aid person. Andy has obtained a foundation degree in Arboriculture at the University of Central Lancashire, is QTRA qualified and is a JCA team leader who manages an office of Consulting Arboriculturists.

Toby Parsons *Cert. Arb. (RFS), Tech. Cert. (Arbor.A).* Toby joined JCA after spending 6 years working as a senior climber for various Arboricultural contractors in the East Midlands and the South-West. He has gained the Level 2 Certificate in Arboriculture (RFS) and an Arboricultural Technicians Certificate. Toby is LANTRA certified in Professional Tree Inspection.

Scott Reid *ND (Arboriculture and Forestry).* Scott joined JCA after working with other consultancy companies in the south of England. He specialises in trees in relation to development and holds a National Diploma, various NPTC qualifications and is currently studying for his Level 4 Diploma in Arboriculture.

Andrew Bussey. Andrew joined JCA having spent 12 years working as a tree surgeon for various private companies and a Local Authority. He has various NPTC qualifications, is QTRA qualified and is currently studying for his Arboricultural Technicians Certificate.

Phil Humeniuk *FdSc (Arboriculture).* Phil joined JCA having spent 3 years working for various tree surgery companies and as a Tree Officer for a Local Authority. He also has several years experience working as a consultant both for JCA and for another consultancy. Phil obtained his foundation degree in Arboriculture at the University of Central Lancashire and has various NPTC's and is LANTRA certified in Professional Tree Inspection.

Emily Wilde *FdSc (Arboriculture).* Emily joined JCA having previously worked for various private tree surgery and consultancy companies over the past 8 years. She initially obtained a ND in Forestry & Arboriculture, followed by a FdSc in Arboriculture at Askham Bryan College, York. Emily has various NPTC certificates and is QTRA qualified.

Charles Cocking. Charles joined JCA in January 2014 as an Apprentice having previously worked for the company on a part time basis during 2013. In between his roles at JCA, Charles will be studying at Askham Bryan College, York, undertaking a two year course in order to obtain a Foundation Degree in Arboriculture (*FdSc Arboriculture*).

Consulting Staff: Ecology

David Ryder. David joined JCA as our in-house ecologist. He brings with him over 8 years experience in the field of ecological consultancy. David holds a Natural England Licence to disturb and handle bats and is currently undergoing assessment for Chartered Institute of Ecology & Environmental Management (CIEEM) membership.

Josie Collier: *BSc (Hons) Ecology.* Josie joined JCA as part of our expanding ecology department. She brings with her a degree in Ecology and Environmental Biology from the University of Leeds. Josie has gained experience from working with a local authority and is seeking to become a member of the Chartered Institute of Ecology and Environmental Management (CIEEM).

Administrative Staff

Sue Guest Administrative Team Leader.
Simeon Haigh *BSc (Hons).* IT Officer.
Lorraine Spink Administrative Assistant.
Yasmin Shahzad Administrative Assistant.
Catherine Cocking Accounts Manager.

© JCA Limited 2016

Appendix 4: General Guidelines

A4.1 All work must be to BS 3998: 2010 - '*Recommendations for tree work'*.

A4.2 Staff carrying out the work must be qualified, experienced and ideally be Arboricultural Association approved contractors, and should be covered by adequate public liability insurance.

A4.3 This report is based upon a visual inspection. The consultant shall not be responsible for events which happen after this time due to factors which were not apparent at the time, and the acceptance of this report constitutes an agreement with the guidelines and the terms listed in this report.

A4.4 Any defects seen by a contractor or the employer that were not apparent to the consultant must be brought to the consultant's attention immediately.

A4.5 No liability can be accepted by the consultant in respect of the trees unless the recommendations of this report are carried out under his supervision and within his timescale.

A4.6 It is advisable to have trees inspected by an arboricultural consultant regularly. In this instance it is recommended that these inspections are made as per the recommended re-inspection timings at **Appendix 1**.

© JCA Limited 2016

Appendix 5: Site Plan

© JCA Limited 2016

N

W E

S

Huddersfield Grammar School

Luck Lane

94

Appendix 5: Site Plan

SCALE 1:500	PAPER SIZE A1

ADDRESS: Huddersfield Grammar School, Royds Mount, Luck Lane, Marsh, Huddersfield, HD1 4QX.
JCA REF: 12699/TP

SURVEYED BY: TP	DRAWN BY: TP	APPROVED BY: TT

JCA Limited

Arboricultural & Forestry Consultants


SAFETY CATEGORIES

Detailed definitions of the safety categories can be found in Section 2.3 of the arboricultural report.

○	SAFETY CATEGORY A: NO WORKS REQUIRED
○	SAFETY CATEGORY B: WORKS OR MONITORING REQUIRED
○	SAFETY CATEGORY R: TREE TO BE REMOVED
●	STEM OF TREE
●	STEM OF TREE TO BE REMOVED

I hope that this report provides all the necessary information, but should any further advice be needed please do not hesitate to contact the author.

Signed



.....

Toby Parsons *Cert. Arb. (RFS), Tech. Cert. (Arbor.A).*

3rd March 2016

For and on behalf of ***JCA Ltd***

Registered Office:


Unit 80
Bowers Mill
Branch Road
Barkisland
Halifax
HX4 OAD

Tel. 01422 376335
Fax. 01422 376232
Email: jon@jcaac.com

www.jcaac.com

Report printed on recycled paper

© JCA Limited 2016



JCA Ltd. Arboricultural Consultants
Professional Tree Advice • Nationwide Service

Tree Advice for Architects and Developers

- British Standard 5837 Tree Surveys
- Arboricultural Implication Studies
- Arboricultural Method Statements
- TPO/Planning advice/project management

Tree Advice for Engineers, Loss Adjusters and Insurers

- Tree surveys for subsidence
- Heave assessment
- Tree root identification

Tree Advice for Landowners, Homeowners, and Homebuyers

- Tree Safety/health surveys
- Tree surveys for mortgage purposes
- Planting advice/scheme design
- Garden tree and shrub maintenance plans

Tree Advice for Local Authorities and Estate Managers

- Tree Inventories and Risk Assessments
- TPO re-surveys
- Trees in Historic Parks and Gardens
- Veteran trees
- Woodland Management Plans
- Ancient woodland
- Tree planting schemes

Tree Advice for the Legal Profession

- Litigating subsidence claims
- Personal Injury cases
- Expert witness for planning inquiries and appeals

Registered Office:
Unit 80 Bowers Mill Branch Road Barkisland Halifax HX4 0AD
Tel: 01422 376335 Fax: 01422 376232 Mobile: 07778 391986
Email: jon@jcaac.com Website: www.jcaac.com
Company Reg No. 05005041 VAT No. 686 4674 78

Directors:

Jonathan Cocking
F. R. E. S., Tech. Cert. (Arbor A), P. Dip. Arb.
(R. F. S.), F. Arbor. A., CBiol, MIBiol

Catherine Cocking
RGN RM

Photo front cover: Sluice at Bowers Mill

Printed on recycled paper

Arboricultural Association