

EXTRACTION SPECIFICATION

2017 07 04

1.01 STANDARDS AND PROVISIONS

All installation to comply with relevant manufacturer's specifications and requirements.

All installation to be in accordance with current and approved Building Regulations, adhering to relevant British Standards. To be conducted by experienced and fully qualified Sub-Contractor.

1.02 SPECIFICATION

Extraction system to be comprised of: (1) canopy grease filter, (2) particulate control unit, (3) ON100 ambient air unit with associated damper control and Venturi Spigot, (4) fans.

Fans to be: ZSP450-41 extract, ZSP400-41 fresh air input.

Odor abatement to be provided by ON100 series ambient air unit.

System to be fitted with 50mm deep stainless-steel Baffle Filters to ensure grease retention, to aid in odor abatement and ensure high level of hygiene.

1.03 ADDITIONAL INFORMATION

Please see ON100 manufacturer's brochure for details regarding treatment of emissions.