

Home/Ventilation Products/Residential Ventilation



SILENT FAN

- Only 14dB(A)
- Silent intermittent bathroom fan with two speeds selectable at installation
- Stylish discrete design
- Back draught shutters included (remove when ceiling mounting)
- High efficiency motor
- 2 year guarantee
- IP24 rated
- Standard thermal overload protection on motor
- Suitable for wall, ceiling, window and panel mounting
- Meets current Building Regulations Approved Document F and L

Select a product

446658 : Silent Fan VASF100B ▼

Technical

PERFORMANCE:

Speed	l/s	Watts	Sound dB(A)@3m
1	15	4.3	14
2	21	6.8	26

DIMENSIONS:

A	B	C	D	E	FØ
159	159	117	37	80	99