



Gun applied sealant to front & back of window heads.

Window / Door Frames to be positioned to have a minimum frame overlap of 30mm to comply with Accredited Construction Detail Ref: MCI-WD-03

New windows to be Timber framed double glazed units with internally glazed 4/20/4 hermetically sealed double glazed units. All units to either top or side hung, weather stripped, with easy clean hinges & espagnolette locking system. The glazed cavity is to be Argon filled. Obscure glazing to all bathrooms. Window construction to achieve an average glass and frame U-value of 1.4 W/m2k. Transmittance of 0.7 to be used

**01** WINDOW DETAILS  
SCALE 1:5

Rev	Date	Initial
--	--	--

Client  
**Mr Keon Ryall**

Project  
**3 Two Gates,  
Slaithwaite,  
HUDDERSFIELD  
HD7 5UG**

Drawing  
**Window Details**

Drawing number	<b>1106 (PL) 12</b>	rev
		--

Scale	1:5@A1	Drawn	OP
Date	01.06.20	Checked	--