

Contractor must verify all dimensions on site before commencing any work or shop drawings.

Only figured dimensions to be taken from this drawing.
Do not scale off this drawing.

Drawings based on Ordnance Survey and / or existing record drawings – design and drawing content subject to Site Survey, Structural Survey, Site Investigations, Planning and Statutory Requirements and Approvals.

Authorised reproduction from Ordnance Survey Map with permission of the Controller of Her Majesty's Stationery Office. Crown Copyright reserved.

Revisions		Date	Ch
Rev	Des		

Topsoil shall be a minimum of 400mm depth over planting beds and graded to fall. Imported topsoil must be BS3882:2007 compliant and existing topsoil must be cultivated in accordance with BS3882:2007. No cultivation should take place in wet/waterlogged conditions.

Regulations 1986 (as amended 1997 or, otherwise, updated/superseded legislation) and following manufacturer's instructions by qualified staff. The topsoil shall then be cultivated to 150mm depth.

whichever is greater. Tree to be supported by 1Nr stake (1500mm long, per tree, 600mm above ground, 75mm diameter) and 1Nr bio-degradeable tie. Alginure soil improver and 150g Enmag (or, equivalent) to be incorporated into the soil of all new tree pits. Trees to be planted centrally within a tree pit.

Herbicide: Spot treat with herbicide throughout the maintenance period in accordance with the manufacturer's instructions.

Plant position: Final position of trees and shrubs subject to confirmation of service location and approval of statutory undertakers.

Ornamental hedging: Hedges to comprise a single row of plants. 400mm wide trench excavated to take plants and topsoil cultivated to 400mm depth prior to application of fertiliser

Planting Season: Bare-root shrubs to be planted between mid-November and mid-March dependant upon the planting season.

Nr	Code	Plant Name	Ht(cm)	Root	Cntr(l)	Nr/m ²
121	BrS	Brachyolottis 'Sunshine'	30-40	C	5	3.00

No	Code	Plant Name	Ht(cm)	Root	Cntr(l)	Nr/m ²
121	BrS	Brachyglottis 'Sunshine'	30-40	C	5	3.00
120	CtS	Choisya ternata 'Sundance'	30-40	C	5	3.00
122	Coorb	Cistus corbariensis	30-40	C	5	4.00
97	EfEG	Eunomys fortunei 'Emerald 'n' Gold'	15-30	C	5	5.00
144	EfE	Eunomys fortunei 'Emerald Gaiety'	15-30	C	5	5.00
102	HpS	Hebe pinguifolia 'Sutherlandian'	30-40	C	5	4.00
129	LaH	Lavandula angustifolia 'Hidcote'	30-40	C	5	4.00
80	LnBg	Lonicera nitida 'Baggesen's Gold'	30-40	C	5	3.00
112	Vt	Viburnum nitida	40-60	C	5	3.00

Nr	Code	Plant Name	Form	Ht(cm)	Girth(cm)	CStm(cm)	Root
8	Ac	Acer campestre	Standard (Selected)	300-350	10-12	175-200	B
5	ApCK	Acer platanoides 'Crimson King'	Standard (Selected)	300-350	10-12	175-200	B
6	Ag	Alnus glutinosa	Standard (Selected)	300-350	10-12	175-200	B
6	Apse	Acer pseudoplatanus	Standard (Selected)	300-350	10-12	175-200	B
17	Bp	Betula pendula	Standard (Selected)	300-350	10-12	175-200	B
1	CIPS	Crataegus laevigata 'Pauli's Scarlet'	Standard (Selected)	300-350	10-12	175-200	B
9	MJD	Malus 'John Downie'	Standard (Selected)	300-350	10-12	175-200	B
13	Pp	Prunus padus	Standard (Selected)	300-350	10-12	175-200	B
3	Qr	Quercus robur	Standard (Selected)	300-350	10-12	175-200	B
14	Sar	Sorbus aria	Standard (Selected)	300-350	10-12	175-200	B

Project: FORMER BOWLING CLUB NEWSOME, HUDDERSFIELD	Job No: 2019-115
Title: proposed Landscape and boundary treatment plan	

Scale:	Drawn by:
1:200@A1	AP
Date:	Checked by:
22.05.19	-
Drawing No:	Revision No:
(08)003	C