

SECOND FLOOR

Remove partitions forming bedroom and kitchen, together with all fittings, modify toilet area to form WC cubicle and ventilated lobby, using 75 x 50 mm studding with 12.5 mm plasterboard with skim finish with new WC and basin waste and plumbing as basement spec. Fit 100 x 50 mm sink unit connected to adjacent water and waste systems.

Remove damaged ceiling following reroofing works and fit 12.5 plaster board ceiling skim finish. Rewire the two rooms and toilet as per electrical layout. The suite to have a separate supply fused to 60 amps with consumer unit serving lighting and power circuits. Decorate all surfaces with emulsion or gloss as per general specification.

Drawing to be read in conjunction with drawings numbered 001 to 003 of lower floors.

PROPOSED ALTERATIONS TO SECONSD FLOOR OF
92 NEW NORTH ROAD, EDGERTON, HUDDERSFIELD

Scale 1 to 100

February 2020

DRWG 004 B

Amended April 2020

