

Subject: Land east of, Leeds Road, Chidswell, Shaw Cross, Dewsbury- 2020/92331
Date: 14 August 2020 12:18:58

Hi Victor

Please arrange for the inclusion of the following conditions for the above:

1. Before the development commences a scheme detailing the location and cross sectional information together with the proposed design and construction details for all new retaining walls/ building retaining walls adjacent to the existing/ proposed adoptable highways shall be submitted to and approved by the Highway Authority in writing. The approved scheme shall be implemented prior to the commencement of the proposed development and thereafter retained during the life of the development.
2. Before the development commences a scheme detailing the location and cross sectional information together with the proposed design and construction details for all new surface water attenuation tanks/pipes/manholes located within the proposed highway footprint shall be submitted to and approved by the Highway Authority in writing. The approved scheme shall be implemented prior to the commencement of the proposed development and thereafter retained during the life of the development. See <https://www.kirklees.gov.uk/beta/regeneration-and-development/highways-guidance-and-standards.aspx> for further details.

Important Notes:

All new storm water attenuation tanks/pipes/culverts with internal diameter/ spans exceeding 0.9m must be located off the adoptable highway. Any decision to locate these facilities within the adoptable highway footprint must be accompanied with a full risk evaluation report with particular reference to their proposed inspection, structural assessment and maintenance regime in compliance with the CDM Regulations 2015 requirements.

The adopting authority (i.e. Yorkshire Water) will also be required to produce and submit a legally binding agreement to the Highway Authority explicitly stating that they will be fulfilling their obligations in relation to the systematic and cyclical inspection and structural assessment of any attenuation structure located within the highway footprint, in full compliance with CS450- Inspection of Highway structures.

Furthermore, all new precast pipes/ culverts/storage tanks proposed for use within the footprint of an adoptable highway must comply with the Specification for Highway Works (SHW-Series 500 or 2500) and must be accredited with a BBA (The British Board of Agrément Roads and Bridges) or HAPAS (Highway Authority Product Approval Scheme) or equivalent certificate.

(Condition No 2 should only be included if the provision of a storm water attenuation

facility is conditioned by the Flood Management team).

Regards

Farhad Khatibi

Bridges & Structures Manager
Structures Section
Highways and Operations
Kirklees Council

Environment Services | Flint Street | Fartown | Huddersfield | HD1 6LG

☎ **External:** 01484 221000 **Internal:** 74199

Mobile: None

✉ **Email:** farhad.khatibi@kirklees.gov.uk

