



GENERAL NOTES

This drawing shows the detailed design only and is not to be used for construction. Any change or modification to the design shall be approved by the Engineer. No part of this drawing shall be used for setting out purposes unless specified.

This drawing is based on a topographical/surface survey provided by others.

KEYING NOTES

Concrete items abutting terraced surfacing are to be finished with a sloped 2:1 batter and 200mm blurring.

Any kerbs that are to be replaced in situ and are either damaged or are out of horizontal / vertical alignment will need replacing within the S178 / S278 area.

CONSTRUCTION NOTES

Concrete items excavating until firm ground is to be compacted in 150mm layers and to be compacted in blinding layers.

Pavement construction to be used would be selected on the basis of CBR values obtained on the subgrade (see drawing for a summary).

Gravel sub-base (see drawing) to be compacted in depth.

Concrete items to be finished with a sloped 2:1 batter.

For all concrete items S178 & S278 items shall be less than 1.0m, concrete items S178 & S278 items shall be used in lieu. The width of the concrete will vary depending on the width of the excavation. The total thickness of the concrete will not be less than 100mm.

The maximum depth of subsoil is required on top of the S178 / S278 area.

Placed concrete shall be cured by a ready-bred form. More than 24 hour cure requires a hot water applied blanket. Hot cost in accordance with the specification.

A further classification and interpretation details to be provided.