



TREE CARE CONSULTANCY
CLIFTON VILLA, HALL CLIFFE ROAD, HORBURY
WAKEFIELD, WEST YORKSHIRE, WF4 6BY
TEL. 01924-270619
EMAIL; info@treecareconsultancy.co.uk

TITLE: Soft Landscape Scheme

AT: Land at 4 Butternab Road Beaumont Park Huddersfield

Tree planting

Species	Ref	Form	Girth (cm) root condition	No required
Betula pendula	BP	heavy standard	12-14	2
Carpinus betulus Frans Fontaine	CB	heavy standard	12-14	3
Sorbus Aucuparia	SA	heavy standard	12-14	2

Tree planting specification, aftercare & maintenance

1. - Trees to be planted in tree pits 600 x 600 x 600mm with incorporation of irrigation tube. The back fill shall include 3 litres peat free tree & shrub compost.
2. - "Enmag" slow release fertilizer to be added to pits.
3. - Trees to be staked with min 8cm diam. peeled round softwood stake. Top of stake to finish approx 1.7m above ground. Stake to be driven beneath base of pit until stable.
4. - Trees to be fastened with a single tie and rubber spacer.
5. - 10 litres of water to added to tree pits on a weekly basis in dry weather during the months of May to August for a period of 2 years post planting
6. - Adjust tree ties in years 2, 3 and 4 and remove in year 5.
7. - Trees that fail or become diseased within 5 years of planting shall be replaced.
8. - 1.0m in diameter around each tree to mulched to 75mm depth with coarse forest bark mulch and maintained weed free.
9. - Final position of trees subject to confirmation of service location and approval of statutory undertakers

Amendments;



KEY

-  - Proposed New Tree Planting
-  - Tree To Be Retained



Soft Landscaping Plan
4 Butternab Road, Beaumont Park

SCALE : 500@ A4

DATE :
17/08/2021

MAP FILENAME : TCC-1350-3



Tree Care Consultancy Ltd, Clifton Villa, 37 Hall Cliffe Road
Horbury, Wakefield, West Yorkshire, WF4 6BY
Phone: 01924 270619, Email: info@treecareconsultancy.co.uk