

PROPOSED INDUSTRIAL DEVELOPMENT

Former Bierley Treatment Works

CLECKHEATON

Planting Schedule

*Based on the Site Landscape Plan – Drawing No: 823/LA1 & the
Detailed Landscape Plan & Bed Planting Plans - Drawing No: 823/LA2*

Item	Name	PD	Size
<i>TREES IN HEDGEROWS AND IN PLANTING BEDS – BR means bare root</i>			
1	Acer campestre 'Elsrijk'	-	EHS h425-600cm, g14-16, BR
2	Betula utilis jacquemontii (multi-stem)		MS 150-200cm, 15L pot
3	Malus sylvestris		HS h350-425cm, g12-14, BR
4	Prunus avium		HS h350-425cm, g12-14, BR
5	Sorbus aucuparia		HS h350-425cm, g12-14, BR
<i>TREES AROUND BASIN AND ON BANKS – BR means bare root & RB means root balled</i>			
6	Alnus glutinosa		SS h300-350cm, g10-12, BR
7	Betula pendula		S h250-300cm, g8-10, RB
8	Malus sylvestris		S h250-300cm, g8-10, BR
9	Prunus avium		SS h300-350cm, g10-12, BR
10	Quercus petrea		HS h350-425cm, g12-14, BR
11	Sorbus aucuparia		SS h300-350cm, g10-12, BR
12	Tilia cordata		HS h350-425cm, g12-14, BR
<i>BEECH HEDGE – set out as two staggered rows with 450mm between the rows and 450mm between the plants</i>			
13	Fagus sylvatica 80%	450	60-80cm, 3L pot
14	Fagus sylvatica 'Purpurea' 20%	450	60-80cm, 3L pot
<i>NATIVE SPECIES HEDGE – set out as two staggered rows with 450mm between the rows and 450mm between the plants</i>			
15	Acer campestre 10%	450	h100cm, BR
16	Corylus avellana 10%	450	h100cm, BR
17	Crataegus monogyna 40%	450	h100cm, BR
18	Ilex aquifolium 5%	450	h40cm, P9
19	Lonicera periclymenum	2 metre centres	P9

20	Prunus spinosa 15%	450	h100cm, BR
21	Rosa canina 10%	450	h100cm, BR
22	Viburnum opulus 10%	450	h100cm, BR
<i>SHRUBS</i>			
23	Cornus alba 'Elegantissima'	750	40-60cm, 3L pot
24	Cornus stolonifera 'White Gold'	600	40-60cm, 3L pot
25	Hypericum calycinum	450	2L pot
26	Prunus laurocerasus 'Otto Luyken'	750	30-40cm, 3L pot
<i>BASIN EDGE SHRUBS</i>			
27	Cornus sanguinea 30%	750	h60-90cm, BR
28	Corylus avellana 30%	750	h60-90cm, BR
29	Salix caprea 20%	750	h60-90cm, BR
30	Salix cinerea 10%	750	h60-90cm, BR
31	Salix repens 10%	750	h40-50cm, BR
<i>AMENITY SEED MIX</i>			
32	A19 All purpose landscaping mix from Germinal Seeds	-	
<i>WILDFLOWER MEADOW SEED MIX</i>			
33	Emorsgate EM3	-	
<i>WILDFLOWER MEADOW SEED MIX TO ATTENUATION BASIN BANKS</i>			
34	Emorsgate EP1	-	