

DRAINAGE DESIGN INFORMATION

for a development at

KNOWL GROVE, MIRFIELD

Undertaken on behalf of

KIRKLEES NEIGHBOURHOOD HOUSING

Report Title:	Drainage Design Information
Report Reference:	9738/DDI/01
Client:	Kirklees Neighbourhood Housing
Issue Date:	June 2021
Drafted By:	Kevin Tyldesley
Authorised By:	Sam Seddon

This document has been prepared for the titled project (or named part thereof) and should not be relied upon or used for any other project without an independent check being carried out as to its suitability and prior written authorization being obtained from WML Consulting. WML accepts no responsibility or liability for the consequences of the use of this document, wholly or in part, for any other purpose than that for which it was commissioned. Any persons so using or relying upon this document for such other purpose do so at their own risk.

This report was prepared for the sole use of the Client and shall not be relied upon or transferred to any other party without the express written authorisation of WML. It May contain material subject to copyright or obtained subject to license; unauthorised copying of this report will be in breach of copyright/license.

The findings and opinions provided in this document are given in good faith and are subject to the limitations imposed by employing site assessment methods and techniques, appropriate to the time of investigation and within the limitations and constraints defined within this document. The findings and opinions are relevant to the dates when the assessment was undertaken, but should not necessarily be relied upon to represent conditions at a substantially later date.

The findings and opinions conveyed in this report are based on information obtained from a variety of sources as detailed and which WML assumes to be reliable, but has not been independently confirmed. Therefore, WML cannot and does not guarantee the authenticity or reliability of third party information it has relied upon.

Where opinions expressed in this report are based on current available guidelines and legislation, no liability can be accepted by WML for the effects of any future changes to such guidelines and legislation.

The limitations of liability of WML for the contents of this document have been agreed with the Client, as set out in the terms and conditions of offer and related contract documentation.

WML Consulting Ltd
No. 8 Oak Green,
Earl Road,
Stanley Green Business Park,
Cheadle Hulme,
Cheshire
SK8 6QL


Tel: 0161 482 0600
Email: info@wmlconsulting.com
www.wmlconsulting.com

1.0 INTRODUCTION

- 1.1 WML Consulting have been commissioned by Kirklees Neighbourhood Housing to provide drainage design information for a residential development at Knowl Grove, Mirfield.
- 1.2 This document contains a drawing at appendix 01 that indicates the below ground foul and surface water drainage proposals and outlines the surface water drainage strategy.
- 1.3 Appendix 02 contains supporting surface water drainage calculations.

APPENDIX 01

Proposed drainage layout plan



THE SURFACE WATER DRAINAGE PROPOSALS HAVE BEEN DESIGNED IN ACCORDANCE WITH BS EN 752-4 AND THE BUILDING REGULATIONS APPROVED DOCUMENT H (2010), WHICH INDICATES THE FOLLOWING HIERARCHY FOR THE DISPOSAL OF SURFACE WATER DRAINAGE FROM DEVELOPMENT SITES:-

- THESE OPTIONS ARE DISCUSSED IN FURTHER DETAIL BELOW

FROM THE ONLINE BGS RECORDS THE GROUND CONDITIONS AT THE SITE APPEAR UNLIKELY TO SUIT THE USE OF INFILTRATION TECHNIQUES FOR DRAINING THE PROPOSED DWELLINGS AND THEIR ASSOCIATED HARD LANDSCAPED AREAS. THE GROUND CONDITIONS SHOULD BE CONFIRMED BY INTRUSIVE INVESTIGATION BEFORE WORK COMMENCES ON SITE, AND IF IT IS FOUND THAT THEY ARE SUITED TO INFILTRATION TECHNIQUES THEN THE PROPOSALS SHOWN CAN BE AMENDED TO SUIT.

THERE ARE NO WATERCOURSES WITHIN OR ADJACENT TO THE SITE, HENCE IT WILL NOT BE FEASIBLE TO DISCHARGE THE SURFACE WATER RUNOFF TO A WATERCOURSE.

GIVEN THE ABOVE IT WILL BE NECESSARY TO DISCHARGE THE SURFACE WATER RUNOFF GENERATED BY THE DWELLINGS AND THEIR ASSOCIATED HARD LANDSCAPED AREAS TO THE PUBLIC SEWER NETWORK.

THE EXISTING SITE HAS A DRAINED AREA OF 820m sq. APPLYING A 50mm / hr RAINFALL INTENSITY TO THIS AREA GIVES AN EXISTING DISCHARGE RATE OF 11.4 / sec.

TO ENSURE THAT THE ALLOWABLE DISCHARGE RATE IS NOT EXCEEDED, A HYDRO-BRAKE FLOW CONTROL DEVICE WILL BE EMPLOYED AT THE DOWNSTREAM END OF THE PROPOSED DRAINAGE SYSTEM, WITH ATTENUATION STORAGE PROVIDED IN A GEO-CELLULAR TANK.

1. NO SURCHARGING OF SEWERS FOR THE CRITICAL 1 IN 1 YEAR STORM EVENT.
2. NO SURFACE FLOODING FOR THE CRITICAL 1 IN 30 YEAR EVENT.
3. NO SURFACE FLOODING THAT MAY AFFECT BUILDINGS ON OR OFF SITE FOR THE CRITICAL 1 IN 100 YEAR EVENT INCLUDING A 30% CLIMATE CHANGE ALLOWANCE.

THE SURFACE WATER DRAINAGE PROPOSALS INDICATED ARE RELATIVELY TRADITIONAL IN NATURE, AND SHOULD PROVIDE YEARS OF RELATIVELY LOW MAINTENANCE OPERATION IN RELATION TO THE ANTICIPATED LIFESPAN OF THE PROPOSED DEVELOPMENT.

IN LINE WITH CURRENT GOOD PRACTICE:-

- PRELIMINARY

DO NOT SCALE FROM THIS DRAWING WORK TO FIGURED DIMENSIONS ONLY.

ALL DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ALL ARCHITECTS,
ENGINEERS AND SPECIALISTS DRAWINGS AND THE SPECIFICATION.

THE CONTRACTOR SHALL INCORPORATE ALL THE REQUIREMENTS OF THE PRE-TENDER STAGE HEALTH AND SAFETY PLAN.

FOR DETAILS OF MATERIALS AND WORKMANSHIP REFER TO THE SPECIFICATION.

THE CONTRACTOR IS RESPONSIBLE FOR CHECKING INVERT LEVELS AND POSITIONS OF ALL EXISTING DRAINS, SEWERS, INSPECTION CHAMBERS AND MANHOLES SHOWN ON THIS DRAWING IMMEDIATELY ON SITE ESTABLISHMENT. ANY DISCREPANCIES MUST BE REPORTED TO WML CONSULTING IMMEDIATELY.

WHERE THE NEW SITE DRAINAGE CONNECTS IN TO EXISTING MANHOLES IN CARRIAGEWAYS AND / OR EXISTING ADOPTED SEWERS, THE CONTRACTOR IS RESPONSIBLE FOR ALL LIAISON WITH THE RELEVANT STATUTORY UNDERTAKER AND LOCAL AUTHORITY WITH REGARD TO ROAD CLOSURES, TRAFFIC MANAGEMENT, PERMITS TO WORK, SUBMISSION OF CONTRACTORS METHOD STATEMENTS AND RISK ASSESSMENTS AND OTHER DOCUMENTATION AND CORRESPONDENCE ASSOCIATED WITH THE SITE STAGE (PART 2) ELEMENT OF THE WORKS.

ROCKER PIPES TO BE PROVIDED AT ALL CONCRETE CASED INTERFACES.

PROVIDE ADEQUATE PROTECTION TO MAINTAIN MINIMUM COVER TO DRAINS DURING THE CONSTRUCTION PERIOD.

COVER LEVELS ON THIS DRAWING ARE APPROXIMATE AND INDICATIVE ONLY
ARCHITECT TO CONFIRM COVER LEVELS TO ALL MANHOLES AND GULLIES PRIOR TO
CONSTRUCTION.

THE LAYOUT OF DRAINAGE ON THIS DRAWING IS INDICATIVE ONLY ARCHITECT TO
CONFIRM EXACT LOCATION OF MANHOLES AND GULLIES.

UNLESS NOTED OTHERWISE PIPEWORK AND FITTINGS TO BE:-

- UPTO 225 DIA (AND INCLUDING) TO BE SUPERSLEVE VITRIFIED CLAY PIPES OR SIMILAR.
- 300 DIA AND ABOVE TO BE CONCRETE BY STANTON BONNA OR SIMILAR.

ALL COVERS AND RODDING ACCESS POINTS TO BE SEALED AND SCREWED TIGHT.

SETTING OUT OF ALL INTERNAL GULLY / PLUMBING CONNECTIONS TO BE
CO-ORDINATED BETWEEN THE SERVICE ENGINEERS AND THE ARCHITECT.

ALL INTERNAL GULLIES, PLUMBING CONNECTIONS, SOIL STACKS, SVPS AND ALL OTHER CONNECTIONS OF FOUL AND SURFACE WATER DRAINS TO BELOW GROUND TO BE FITTED WITH ACCESSIBLE RODDING POINTS ABOVE SLAB LEVEL..

ALL CONNECTIONS TO BE MADE IN ACCORDANCE WITH STANDARD DETAIL
DRAWINGS.

ALL PIPEWORK TO BE INSTALLED WITH SOFFITS LEVEL (E.G. AT CHANGES IN PIPE SIZE) U.N.O.

ON COMPLETION OF DRAINAGE WORKS, THE NEW DRAINAGE SYSTEM IS TO BE THOROUGHLY CLEANED AND A CCTV SURVEY CARRIED OUT TO CONFIRM NO CONSTRUCTION DEBRIS OR BLOCKAGES REMAIN.

ALL PRIVATE DRAINAGE IS TO COMPLY WITH BS EN 752 AND BUILDING REGS. PART H

PIPE GRADIENTS ARE INDICATIVE MINIMUMS.

SURFACE CHANNEL DRAINS TO BE ACO MULTIDRAIN OR SIMILAR.

MANHOLE COVERS TO BE EN124 CLASS D400 IN VEHICULAR AREAS AND EN124 CLASS C250 IN NON - VEHICULAR AREAS.

REFER TO ARCHITECTS DRAWINGS FOR DETAILS OF ANY MANHOLE COVERS WHICH REQUIRE INSET PANELS.

P01	PRELIMINARY ISSUE	18.06.21	KPT	SS
Rev.	Amendment	Date	By	Chk

Client	KIRKLEES NEIGHBOURHOOD HOUSING
--------	--------------------------------

Title
PROPOSED DRAINAGE LAYOUT

WML Job No. 9738	Drawn KPT	Checked SS	Date JUNE 2021	Scale 1:100 @ A
----------------------------	--------------	---------------	-------------------	--------------------

WML CONSULTING
Civil, Structural & Geotechnical Engineers

No.8 Oak Green
Earl Road
Stanley Green Business Park
Cheadle Hulme
Cheshire SK8 6DL
Tel 0161 482 0600
Fax 0161 485 9210
e-mail info@wmlconsulting.com
www.wmlconsulting.com

Drawing No.							
Project	Originator	Volume	Level	Type	Role	Number	Rev
9738 - WML -	00 -	XX -	DR -	C -	1001	P0	

APPENDIX 02

Surface water drainage calculations

WML Consulting Ltd		Page 1
No. 8 Oak Green Stanley Green Business Park Earl Rd, Cheadle Hulme, SK8 6QL	9738 - KNOWL GROVE MIRFIELD REV 01	
Date JUNE 2021 File 9738 - SW - 01.MDX	Designed by KPT Checked by DB	
Innovyze	Network 2014.1.1	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	1	Add Flow / Climate Change (%)	0
M5-60 (mm)	19.000	Minimum Backdrop Height (m)	0.200
Ratio R	0.338	Maximum Backdrop Height (m)	0.000
Maximum Rainfall (mm/hr)	5	Min Design Depth for Optimisation (m)	0.000
Maximum Time of Concentration (mins)	30	Min Vel for Auto Design only (m/s)	1.00
Foul Sewage (l/s/ha)	0.000	Min Slope for Optimisation (1:X)	500
Volumetric Runoff Coeff.	0.750		

Designed with Level Soffits

Time Area Diagram for Storm

Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.055	4-8	0.015

Total Area Contributing (ha) = 0.070

Total Pipe Volume (m³) = 1.496

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Auto Design
1.000	17.000	0.170	100.0	0.010	5.00	0.0	0.600	o	150	
1.001	6.000	0.060	100.0	0.010	0.00	0.0	0.600	o	150	
1.002	9.000	0.090	100.0	0.010	0.00	0.0	0.600	o	150	
1.003	13.000	0.130	100.0	0.010	0.00	0.0	0.600	o	150	
1.004	9.000	0.300	30.0	0.010	0.00	0.0	0.600	o	150	
2.000	24.000	0.700	34.3	0.010	5.00	0.0	0.600	o	100	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	5.00	5.28	65.250	0.010	0.0	0.0	0.0	1.00	17.8	0.1
1.001	5.00	5.38	65.080	0.020	0.0	0.0	0.0	1.00	17.8	0.3
1.002	5.00	5.53	65.020	0.030	0.0	0.0	0.0	1.00	17.8	0.4
1.003	5.00	5.75	64.930	0.040	0.0	0.0	0.0	1.00	17.8	0.5
1.004	5.00	5.83	64.800	0.050	0.0	0.0	0.0	1.84	32.6	0.7
2.000	5.00	5.30	65.250	0.010	0.0	0.0	0.0	1.32	10.4	0.1

WML Consulting Ltd		Page 2
No. 8 Oak Green Stanley Green Business Park Earl Rd, Cheadle Hulme, SK8 6QL	9738 - KNOWL GROVE MIRFIELD REV 01	
Date JUNE 2021 File 9738 - SW - 01.MDX	Designed by KPT Checked by DB	
Innovyze	Network 2014.1.1	

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Auto Design
1.005	15.000	0.150	100.0	0.010	0.00	0.0	0.600	o	150	
1.006	5.000	0.100	50.0	0.000	0.00	0.0	0.600	o	150	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.005	5.00	6.08	64.500	0.070	0.0	0.0	0.0	1.00	17.8	0.9
1.006	5.00	6.13	64.350	0.070	0.0	0.0	0.0	1.43	25.2	0.9

WML Consulting Ltd		Page 3
No. 8 Oak Green Stanley Green Business Park Earl Rd, Cheadle Hulme, SK8 6QL	9738 - KNOWL GROVE MIRFIELD REV 01	
Date JUNE 2021 File 9738 - SW - 01.MDX	Designed by KPT Checked by DB	
Innovyze	Network 2014.1.1	

Online Controls for Storm

Hydro-Brake Optimum® Manhole: 8, DS/PN: 1.006, Volume (m³): 1.9

Unit Reference	MD-SHE-0113-5700-0950-5700
Design Head (m)	0.950
Design Flow (l/s)	5.7
Flush-Flo™	User Defined
Objective	Minimise upstream storage
Diameter (mm)	113
Invert Level (m)	64.350
Minimum Outlet Pipe Diameter (mm)	150
Suggested Manhole Diameter (mm)	1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.950	5.7
Flush-Flo™	0.282	5.7
Kick-Flo®	0.618	4.6
Mean Flow over Head Range	-	4.9

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.9	1.200	6.3	3.000	9.7	7.000	14.5
0.200	5.5	1.400	6.8	3.500	10.4	7.500	15.0
0.300	5.6	1.600	7.2	4.000	11.1	8.000	15.5
0.400	5.5	1.800	7.6	4.500	11.8	8.500	15.9
0.500	5.3	2.000	8.0	5.000	12.4	9.000	16.4
0.600	4.8	2.200	8.4	5.500	13.0	9.500	16.8
0.800	5.2	2.400	8.7	6.000	13.5		
1.000	5.8	2.600	9.1	6.500	14.0		

WML Consulting Ltd		Page 4
No. 8 Oak Green Stanley Green Business Park Earl Rd, Cheadle Hulme, SK8 6QL	9738 - KNOWL GROVE MIRFIELD REV 01	
Date JUNE 2021 File 9738 - SW - 01.MDX	Designed by KPT Checked by DB	
Innovyze Network 2014.1.1		

Storage Structures for Storm

Cellular Storage Manhole: 8, DS/PN: 1.006

Invert Level (m) 64.500 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	14.0	0.0	0.801	0.0	0.0
0.800	14.0	0.0			

©1982-2014 XP Solutions

WML Consulting Ltd		Page 6	
No. 8 Oak Green		9738 - KNOWL GROVE	
Stanley Green Business Park		MIRFIELD	
Earl Rd, Cheadle Hulme, SK8 6QL		REV 01	
Date JUNE 2021		Designed by KPT	
File 9738 - SW - 01.MDX		Checked by DB	
Innovyze		Network 2014.1.1	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	1
Number of Online Controls	1	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Ratio R	0.357
Region	England and Wales	Cv (Summer)	0.750
M5-60 (mm)	18.000	Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0	DVD Status	OFF
Analysis Timestep	Fine	Inertia Status	OFF
DTS Status	ON		

Profile(s)

Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
Return Period(s) (years)	1, 30, 100
Climate Change (%)	0, 0, 40

PN	Storm	Return Period	Climate Change	First X Surchage	First Y Flood	First Z Overflow	O/F Act.	Lvl Exc.
1.000	15 Winter	30	0%	100/15 Summer				
1.001	15 Winter	30	0%	100/15 Summer				
1.002	15 Winter	30	0%	100/15 Summer				
1.003	15 Winter	30	0%	100/15 Summer				
1.004	15 Winter	30	0%	100/15 Summer				
2.000	15 Winter	30	0%	100/15 Winter				
1.005	15 Winter	30	0%	30/15 Summer				
1.006	30 Winter	30	0%	1/15 Summer				

PN	US/MH Name	Water		Flooded		Pipe		Status
		Level (m)	Surch'd Depth (m)	Volume (m³)	Flow / Cap. (l/s)	O'flow (l/s)	Flow (l/s)	
1.000	1	65.293	-0.107	0.000	0.18	0.0	2.9	OK
1.001	2	65.147	-0.083	0.000	0.41	0.0	6.0	OK
1.002	3	65.103	-0.067	0.000	0.58	0.0	9.1	OK
1.003	4	65.029	-0.051	0.000	0.75	0.0	12.2	OK
1.004	5	64.929	-0.021	0.000	0.52	0.0	14.8	OK
2.000	6	65.287	-0.063	0.000	0.29	0.0	2.9	OK
1.005	7	64.870	0.220	0.000	1.14	0.0	18.6	SURCHARGED
1.006	8	64.805	0.305	0.000	0.29	0.0	5.6	SURCHARGED

©1982-2014 XP Solutions

