


Typical Manhole Construction

Type A (SFA 6th Edition)
Type 1 (SFA 7th Edition)


For use on manholes of depth from cover level to soffit level between 3000mm and 6000mm.



Section View

Typical Manhole Plan View

Type A & B (SFA 6th Edition)
Type 1 & 2 (SFA 7th Edition)




Manhole Diameters	
Nominal internal diameter of largest pipe in manhole (mm)	Minimum nominal internal dimension of manhole (mm)
Up to 300	1200
375-450	1350
500-750	1500
750-900	1800
Greater than 900	Specific detailed drawing required

Typical Manhole Construction

Type B (SFA 6th Edition)
Type 2 (SFA 7th Edition)

Maximum depth from cover level to soffit of pipe 3000mm




Section View

Shallow Manhole Construction

Type B1E (SFA 6th Edition)
Type 2.1E (SFA 7th Edition)


Construction of manhole where depth from soffit to cover level less than 1.5m



Where Type B1E manholes are 1500mm or greater in diameter a double bay 1200mm x 675mm cover and frame is required directly over the chamber.

Shallow Manhole Plan View


Type B1.E (SFA 6th Edition)
Type 2.1.E (SFA 7th Edition)



Typical Widewall Manhole Construction

Type A Alternative Wide Wall Manhole Construction (SFA 6th Edition)
Type 1 Alternative Wide Wall Manhole Construction (SFA 7th Edition)


For use on manholes of depth from cover level to soffit level between 3000mm and 6000mm.
Wide wall manhole ring construction



Section View

Typical Widewall Manhole Plan View


Type A & B (SFA 6th Edition)
Type 1 & 2 (SFA 7th Edition)



Typical Widewall Manhole Construction

Type B Alternative Wide Wall Manhole Construction (SFA 6th Edition)
Type 2 Alternative Wide Wall Manhole Construction (SFA 7th Edition)

Maximum depth from cover level to soffit of pipe 3000mm
Wide wall manhole ring construction




Section View

Shallow Manhole Construction

Type B1E Alternative Wide Wall Manhole Construction (SFA 6th Edition)
Type 2.1E Alternative Wide Wall Manhole Construction (SFA 7th Edition)


Construction of manhole where depth from soffit to cover level less than 1500mm



Where the manhole has a diameter of 1.5m or greater a double bay 1200mm x 675mm cover and frame is required directly over the channel



Shallow Widewall Manhole Plan View

Type B1.E (SFA 6th Edition)
Type 2.1.E (SFA 7th Edition)




REFER TO 1st LATERAL SCHEDULE FOR DEMARCATION CHAMBER DETAILS & SPECIFICATION.



Backdrop details



Backdrop plan view



Shallow Manhole detail



Section View

PLEASE NOTE WHERE MANHOLES HAVE BACKDROP CONNECTIONS A FULL 150MM CONCRETE SURROUND TO THE MANHOLE IS REQUIRED

1. ALL ADAPTABLE SEWER WORKS AND MATERIAL TO BE IN ACCORDANCE WITH 'CODES FOR ADOPTION' THE RELEVANT BRITISH/EUROPEAN AND YORKSHIRE WATER'S STANDARD REQUIREMENTS/ADDENDUM TO THE MECHANICAL AND ELECTRICAL SPECIFICATION AND KITEMARKED.
2. MANHOLE COVERS SHALL HAVE A CLEAR OPENING OF 600mm AND SHALL BE CLASS D400 TO BS EN 124 WITH 150mm DEEP FRAMES IN HIGHWAYS.
3. FILLED GROUND MUST BE FILLED AND CONSOLIDATED UNDER THE SUPERVISION AND TO THE SATISFACTION OF YORKSHIRE WATER BEFORE ANY SEWER WORKS ARE CARRIED OUT.
4. YORKSHIRE WATER IS NOT OBLIGED TO ACCEPT FILTER DRAIN/LAND DRAINAGE RUNOFF INTO THE PUBLIC SEWER NETWORK OR ADAPTABLE DRAINAGE SYSTEM (DIRECTLY OR INDIRECTLY). AN ALTERNATIVE METHOD OF DISPOSAL OF THE LAND DRAINAGE RUNOFF WILL THEREFORE BE REQUIRED AND YOU WILL HAVE TO COME WITH THE LOCAL AUTHORITY, LAND DRAINAGE SECTION WITH REGARD TO THE DISPOSAL OF THE FILTER DRAIN/LAND DRAINAGE RUNOFF.
5. COVER SLABS MUST CARRY THE BS KITEMARK OR WILL BE REJECTED BY YORKSHIRE WATER INSPECTOR, WHERE THE CLEAR OPENING OF THE KITEMARKED PRODUCT IS DIFFERENT TO THAT OF THE COVER AND FRAME. A LOADING BEARING SLAB SHOULD BE FITTED ABOVE THE COVER SLAB TO BRING THE SIZE DOWN TO 600x600mm FOR THE YORKSHIRE WATER SPECIFIED COVER SIZE. PLEASE REFER TO CONCRETE PIPE SYSTEMS ASSOCIATION (CPSA) TECHNICAL BULLETIN ISSUED AUTUMN 2004 FOR KITEMARKED COVER SLAB OPENING SIZES.
6. SULPHATE RESISTANT CEMENT (C20/C25) AND PRECAST CONCRETE PRODUCTS MUST BE USED OR A LABORATORY REPORT PROVIDED PROVING THAT SUCH PRECAUTIONS ARE NOT NECESSARY.
7. THE ADAPTABLE SEWERS SHOULD BE A MINIMUM OF 1m AND MANHOLES 0.5m FROM KERB FACES.
8. SEWERS MUST HAVE 5m CLEARANCE FROM TREES AND HEDGES.
9. SEWERS TO BE LAID IN CLASS 'B' BEDDING ON 100mm GRANULAR BED AND SURROUND, WHERE DEPTH OF COVER TO TOP OF THE SEWER IS LESS THAN 1.2m IN HIGHWAYS AND VERGES (OR LESS THAN 800mm IN NONE VEHICULAR ACCESS AREAS) THEN A 75mm CONCRETE SLAB OVER SEWER SHALL BE PROVIDED.
10. ALL PIPEWORK 300mm DIA. OR LESS TO BE VITRIFIED CLAY CONFORMING WITH BS 65 MINIMUM CRUSHING STRENGTHS TO BE AS FOLLOWS: 100mm DIA. 40kN/m, 150mm DIA 40kN/m, 225mm DIA 45kN/m, 300mm DIA 72kN/m.
11. ALL PIPEWORK 375mm DIA. OR GREATER TO BE CONCRETE CLASS 120 TO EN 1916 / BS 5911-1:2002.
12. THE CHAMBER SIZE OF MANHOLES WITH MORE THAN ONE CONNECTION IN THEM MAY NEED TO BE INCREASED AN INCREMENT TO ACCOMMODATE THE CONNECTIONS AND BENDS.
13. YORKSHIRE WATER POLICY IS NOT TO ACCEPT CLASS 120 OR 150mm DIA. MANHOLE RINGS. INSTEAD IT IS PREFERRED THAT YOU USE A TYPE 'B' MANHOLE WITH 1000mm DIA. OR 1000mm DIA. RINGS WITH THE OPENING 800mm OVER THE CHANNEL WHERE DEPTH OF COVER TO PIPE SOFFIT IS 1.1-1.2m.
14. ALL HIGHWAY WORKS AND MATERIAL TO CONFORM WITH HIGHWAYS COUNCIL SPECIFICATION.
15. GULLY COVER AND FRAMES SHALL BE D400 DUCTILE IRON AND COMPLY WITH EUROPEAN STANDARD BS EN 124. THESE SHOWN IN ACCESSWAYS AND NEWS COURTS MUST BE SUITABLE FOR USE IN PEDESTRIAN AREAS.
16. BEDDING AND BACKFILL MATERIAL TO CONFORM TO THE REQUIREMENT OF WATER INDUSTRY SPECIFICATION 4.06-2 (FAS 4.06).
17. PLASTIC CHANNEL SECTIONS IN MANHOLES ARE NOT ACCEPTABLE AND YORKSHIRE WATER WOULD PREFER CLAYWARE CHANNELS IN MANHOLES. YORKSHIRE WATER HAVE FOUND THAT PLASTIC CHANNELS ARE DIFFICULT TO SET IN CONCRETE AS THEY FLOAT AND A SATISFACTORY FINISH CANNOT BE OBTAINED ON BENCHING.
18. WHERE A B125 COVER AND FRAME HAS BEEN APPROVED, THIS MUST NOT BE COATED IN PLASTIC AND MUST HAVE LIFTING EYES SUITABLE TO ACCOMMODATE STANDARD LIFTING KITS. SCREW DOWN COVERS ARE NOT ACCEPTABLE.
19. THERE SHOULD BE SUFFICIENT CLEARANCE TO ACCOMMODATE THE BEDDING FOR BOTH PIPES. APPROX 300mm ± CROSSOVER NEAR THE ROCKER THEN THE CLEARANCE NEEDED MAY BE INCREASED.

ALL PIPEWORK 300mm DIA OR LESS TO BE VITRIFIED CLAY CONFORMING WITH BS 65. MINIMUM CRUSHING STRENGTHS TO BE AS FOLLOWS: 100mm DIA. 40kN/m, 150mm DIA 40kN/m, 225mm DIA 45kN/m, 300mm DIA 72kN/m.
ALL PIPEWORK 375mm DIA OR GREATER TO BE CONCRETE CLASS 120 TO EN 1916 / BS 5911-1:2002.
ADAPTABLE SEWERS TO BE LAID IN CLASS 'S' GRANULAR BED & SURROUND.

Note
All Drainage works and materials to conform with 'Codes for Adoption'.

Chambers
Type C, D, E & F are non preferred chambers. For type 'B' chambers less than 1.2m from top of benching to the underside of the cover slab, shall have the cover fixed in the centre of the slab and the channels intersecting beneath the cover.


Covers
The minimum size for manhole covers is 600mm by 600mm. Manhole covers to be class D400 and have 150mm deep frames where located in the highway.

Step Irons / Ladders
All step irons shall be double rung and complying clause 4.2.3.1. Step irons are required for all manholes, up to 6 metres deep.

Brickwork
All brickwork to be constructed using class B engineering solids.

Rev A Updated to suit YW latest standard details

09.08.21 HH



Haigh Huddleston & Associates

Civil Structural Engineering Consultants

Firth Buildings, 99 - 101 Leeds Rd, Dewsbury, WF12 7BU

T 01924 464342 F 01924 450662

e trevor.haigh@haighhuddleston.co.uk

Client

YORKSHIRE COUNTRY PROPERTIES

Project

STATION ROAD, SKELMANTHORPE

Detail

STANDARD MANHOLE DETAILS

Dwn

Chkd

Date

AUG-21

Scale

NTS@A0

Dwg No.

E1977366/006A