This drawing is copyright. © Beam Consulting Engineers Ltd.

A1

Key

- Existing Surface Water Drainage
- Existing Foul Water Drainage
- Existing Combined Water Drainage
- Proposed Surface Water Drainage
- Proposed Foul Water Drainage
- Existing/Diverted Culvert
- Demolished Culvert
- Proposed Culvert
- G — Proposed Surface Water Gully
- RWP — Proposed Rainwater Pipe

Note:
Outline Drainage Strategy. Subject to approval and detailed design

Note:
Existing drainage information based on 1814 FSK436A Proposed Site Plan by HTC Architects dated August 2021 and D224-001 Utilities survey by Landform Surveys.

El Sub Sta

398a

Track

398

396

400

402

394

NEW HEY ROAD

Existing culvert to be demolished and grubbed out

Proposed 600x400mm concrete box culvert installed to divert existing culvert

Proposed foul connection into existing combined MH. Depth TBC

Proposed surface water connection into existing combined MH. Depth TBC

Existing combined MH on site to be replaced

Attenuation Tank

Flow control MH restricted to 5L/s with 175m³ on site underground storage designed for 1:100 year rainfall plus 30% climate change.

Plan
Scale 1:250

DESCRIPTION	REV	DATE	CHK	APR
Updated to suit revised scheme	A	27/08/2021	TM	KGP

beamconsulting

Beam Consulting
14 Bond Street
Wakefield
WF1 2QP
Tel: 01924 361653
Fax: 01924 364631

PROJECT
New Hey Road
Huddersfield

DRAWING TITLE
Residential Option 2
Outline Design Drainage Strategy

CLIENT
Lidl Great Britain Ltd

STATUS
Information

DRAWN	JD	DATE	06/08/2021
CHECKED	TM	SCALE	AS SHOWN @ A1
APPROVED	KGP		

DRAWING NUMBER	REVISION
09-122-510	A