

Subject: RE: Attached letter from Kirklees Council regarding application number 2021/94280 at location land at, Lady Ann Road, Soothill, Batley, WF17 0PY
Date: 09 December 2021 10:11:41

Please arrange for the inclusion of the following conditions for the above site:

1. Before the development commences a scheme detailing the location and cross sectional information together with the proposed design and construction details for all new retaining walls/ building retaining walls adjacent to the existing/ proposed adoptable highway, shall be submitted to and approved by the Highway Authority in writing. The approved scheme shall be implemented prior to the commencement of the proposed development and thereafter retained during the life of the development.
2. Before the development commences a scheme detailing the proposed design and construction details for the new bridge structure including any wing walls, carrying the new access road over Howley Beck shall be submitted to and approved in writing by the Councils Highways Structural Section before any development commences. The approved bridge design shall be implemented prior to the commencement of the proposed development and thereafter retained during the life of the development.
3. Before the development commences a scheme detailing the location and cross sectional information together with the proposed design and construction details for all new surface water attenuation tanks/pipes/manholes located within the proposed highway footprint or influence zone of highway loading shall be submitted to and approved by the Highway Authority in writing. The approved scheme shall be implemented prior to the commencement of the proposed development and thereafter retained during the life of the development. See <https://www.kirklees.gov.uk/beta/regeneration-and-development/highways-guidance-and-standards.aspx> for further details.

Important Notes:

All new storm water attenuation tanks/pipes/culverts with internal diameter/ spans exceeding 0.9m must be located off the adoptable highway. Any decision to locate these facilities within the adoptable highway footprint must be accompanied with a full risk evaluation report with particular reference to their proposed inspection, structural assessment and maintenance regime in compliance with the CDM Regulations 2015 requirements.

The adopting authority (i.e. Yorkshire Water) will also be required to produce and submit a legally binding agreement to the Highway Authority explicitly stating that they will be fulfilling their obligations in relation to the systematic and cyclical inspection and structural assessment of any attenuation structure located within the highway footprint, in full compliance with CS450- Inspection of Highway structures.

Furthermore, all new precast pipes/ culverts/storage tanks proposed for use within the footprint of an adoptable highway must comply with the Specification for Highway Works (SHW-Series 500 or 2500) and must be accredited with a BBA (The British Board of Agrément Roads and Bridges) or HAPAS (Highway Authority Product Approval

Scheme) or equivalent certificate.

Regards

Farhad Khatibi

Bridges & Structures Manager
Structures Section
Highways and Streetscene
Kirklees Council

Highways Service | Flint Street | Fartown | Huddersfield | HD1 6LG

☎ **External:** 01484 221000 **Internal:** 74199

Mobile: None

✉ **Email:** farhad.khatibi@kirklees.gov.uk



From: Planning ContactCentre <Planning.ContactCentre@kirklees.gov.uk>

Sent: 06 December 2021 14:28

To: Farhad Khatibi <Farhad.Khatibi@kirklees.gov.uk>

Subject: Attached letter from Kirklees Council regarding application number 2021/94280 at location land at, Lady Ann Road, Soothill, Batley, WF17 0PY

Dear Sir/Madam

Please find attached documentation relating to the above application.

Kind regards

Kirklees Planning