Consultation Response from: KC Environmental Health (Pollution & Noise Control)		
2022/90397 Newsome Bowling Green, St John's Avenue, Newsome, Huddersfield, HD4 6JP		
Erection of 10 dwellings and associated works		
Date Responded: 4th May 2022	**Responding Officer:** Rebecca Muff	**Responding Ref:** WK/202214128

The proposed development site is located within Newsome centre, to the rear of the former Newsome Working Men's Club and is surrounded by a mix of residential and commercial buildings. To the north-east of the site is a children's day care nursery. The proposed development is for 10 dwellings comprising of a mix of 4no. three-bedroomed semi-detached houses and 6no. three-bedroomed terraced houses.

We have reviewed the application and supporting information and make the following comments and recommendations.

Contaminated Land
The proposed development is for the erection of 10 dwellings and is therefore classed as a major development. The proposed site is also near to land that is potentially contaminated (our site ref: 42/15). As the development will entail groundworks, it will be necessary for conditions relating to contaminated land.

Noise
The proposed development is near to existing commercial and licensed premises and noise from customers, business operations and external plant is likely to have an adverse impact on future occupiers of the site. Therefore, before construction work commences it will be necessary for a noise impact assessment to be provided which should determine the existing noise climate taking all likely sources into consideration. The assessment should then detail how this will impact the proposed development and it should detail the mitigation measures that will be required to achieve satisfactory sound levels both indoors and at any outdoor amenity areas of the development. A condition is therefore necessary requiring this information.

Loss of amenity caused by the construction of the development
Because of the size of the development and the proximity of residential properties to the site boundary there is a significant potential for loss of amenity to the occupiers of nearby properties from noise, vibration, dust and artificial light from the construction phase of the development. Therefore, it will be necessary for a condition requiring a Construction Environmental Management Plan (CEMP) to be submitted.

Electric Vehicle Charging points (EVCPs)
We note that the proposals include the provision of car parking, therefore in an application of this nature it is expected that facilities for charging electric vehicles and other ultra-low emission vehicles are provided in accordance with the National Planning Policy Framework and *Air Quality & Emissions Technical Planning Guidance* from the West Yorkshire Low Emissions Strategy Group. A condition requiring charging points is therefore necessary.

Recommended Conditions

CLC1 Submission of a Phase 1 Preliminary Risk Assessment Report - Condition
Groundworks shall not commence until actual or potential land contamination at the site has been investigated and a Preliminary Risk Assessment (Phase I Desk Study Report) by a suitably competent person has been submitted to and approved in writing by the Local Planning Authority.
Reason: To ensure the safe occupation of the site in accordance with Policy LP53 of the Kirklees Local Plan and paragraph nos. 178 and 179 of the National Planning Policy Framework

CLC2 Submission of a Phase 2 Intrusive Site Investigation Report - Condition
Where further intrusive investigation is recommended in the Preliminary Risk Assessment approved pursuant to condition (CLC1), groundworks (other than those required for a site investigation report) shall not commence until a Phase II Intrusive Site Investigation Report by a suitably competent person has been submitted to and approved in writing by the Local Planning Authority.
Reason: To ensure the safe occupation of the site in accordance with Policy LP53 of the Kirklees Local Plan and paragraph nos. 178 and 179 of the National Planning Policy Framework

CLC3 Submission of Remediation Strategy - Condition
Where site remediation is recommended in the Phase II Intrusive Site Investigation Report approved pursuant to condition (CLC2) further groundworks shall not commence until a Remediation Strategy by a suitably competent person has been submitted to and approved in writing by the Local Planning Authority. The Remediation Strategy shall include a timetable for the implementation and completion of the approved remediation measures.
Reason: To ensure the safe occupation of the site in accordance with Policy LP53 of the Kirklees Local Plan and paragraph nos. 178 and 179 of the National Planning Policy Framework

CLC4 Implementation of the Remediation Strategy - Condition
Remediation of the site shall be carried out and completed in accordance with the Remediation Strategy approved pursuant to condition (CLC3). In the event that remediation is unable to proceed in accordance with the approved Remediation Strategy or contamination not previously considered in either the Preliminary Risk Assessment or the Phase II Intrusive Site Investigation Report is identified or encountered on site, all groundworks in the affected area (except for site investigation works) shall cease immediately and the Local Planning Authority shall be notified in writing within 2 working days. Works shall not recommence until proposed revisions to the Remediation Strategy have been submitted to and approved in writing by the Local Planning Authority. Remediation of the site shall thereafter be carried out in accordance with the approved revised Remediation Strategy.
Reason: To ensure the safe occupation of the site in accordance with Policy LP53 of the Kirklees Local Plan and paragraph nos. 178 and 179 of the National Planning Policy Framework

CLC5 Submission of Validation Report - Condition
Following completion of any measures identified in the approved Remediation Strategy or any approved revised Remediation Strategy a Validation Report by a suitably competent person

shall be submitted to the Local Planning Authority. No part of the site shall be brought into use until such time as the remediation measures have been completed for the site in accordance with the approved Remediation Strategy or the approved revised Remediation Strategy and a Validation Report in respect of those remediation measures has been approved in writing by the Local Planning Authority. Where validation has been submitted and approved in stages for different areas of the whole site, a Final Validation Summary Report shall be submitted to and approved in writing by the Local Planning Authority.
Reason: To ensure the safe occupation of the site in accordance with Policy LP53 of the Kirklees Local Plan and paragraph nos. 178 and 179 of the National Planning Policy Framework

CLC 7 Contaminated land - Footnote
All contamination reports shall be prepared by a suitably competent person, as defined in Annex 2 of the National Planning Policy Framework 2019. Reports must be prepared in accordance with the following guidance:

- *Land Contamination Risk Management (LCRM)*
- BS 10175:2011+ A2:2017 *Investigation of Potentially Contaminated Sites. Code of Practice*
- *Development on Land Affected by Contamination - Technical Guidance for Developers, Landowners & Consultants - (v11.2) June 2020* by the Yorkshire and Lincolnshire Pollution Advisory Group

NC9 Noise Assessment Report and Mitigation Scheme - Condition
Before construction work commences a report specifying the measures to be taken to protect the development from noise from all significant noise sources that are likely to affect the proposed development (including noise from licensed premises, commercial premises, and external plant) shall be submitted to and approved in writing by the Local Planning Authority. The report shall:

a) Determine the existing noise climate
b) Predict the noise climate in gardens (daytime), bedrooms (night-time) and other habitable rooms of the development
c) Detail the proposed attenuation/design necessary to protect the amenity of the occupants of the new residences (including ventilation if required).

The development shall not be occupied until all works specified in the approved report have been carried out in full and such works shall be thereafter retained.

NF4 Competent Person - Footnote
All noise assessments should be carried out by a competent person. Developers may wish to contact the Association of Noise Consultants http://www.association-of-noise-consultants.co.uk/ (020 8253 4518) or the Institute of Acoustics http://www.ioa.org.uk (0300 999 9675) for a list of members.

CEMPC Construction Environmental Management Plan - Condition
No development shall take place, until a Construction Management Plan has been submitted to, and approved in writing by, the Local Planning Authority. The Construction Management Plan shall provide details of:

a) timetable of all works
b) vehicle sizes and routes, times of vehicle movements, identify the location of any HGV waiting areas and include details of the management of said areas
c) the parking of vehicles of site operatives and visitors
d) details and location of signage
e) loading and unloading of plant and materials
f) storage of plant and materials used in constructing the development
g) measures to be taken to minimise the deposit of mud, grit and dirt on public highways by vehicles travelling to and from the site, including the provision of adequate wheel washing facilities within the site
h) measures to control and monitor the emission of dust and dirt during construction
i) a Site Waste Management Plan, detailing recycling/disposing of waste resulting from demolition and construction works
j) mitigation of noise and vibration arising from all construction related activities to (these details should also include suitable restrictions on the hours of working on the site including times of deliveries)
k) artificial lighting used in connection with all construction related activities and security of the construction site
l) site manager and resident liaison officer contact details (including their remit and responsibilities); and
m) details of engagement with local residents and occupants or their representatives.

The development shall be carried out strictly in accordance with the approved CEMP and no change there from shall take place without the prior written consent of the Local Planning Authority.
Reason: To safeguard the amenities of the occupiers of nearby properties in accordance with part 15 of the NPPF and xxxxx of the Local Plan

CEMPF Construction Environmental Management Plan - Footnote
Noisy construction related activities should not take place outside the hours of:
07.30 to 18.30 hours Mondays to Fridays
08.00 to 13.00 hours, Saturdays
With no noisy activities on Sundays or Public Holidays

Institute of Air Quality Management document *"Guidance on the assessment of dust from demolition and construction"* Version 1.1 2014 provides detailed information regarding dust control.

Kirklees Council has powers under Section 60 of the Control of Pollution Act 1974 to control noise from construction sites and may serve a notice imposing requirements on the way in which construction works are to be carried out. It has additional powers under Sections 80 of the Environmental Protection Act 1990 to prevent statutory nuisance including noise, dust, smoke and artificial light and must serve an abatement notice when it is satisfied that a statutory nuisance exists or is likely to occur or recur. Failure to comply with a notice served using the above-mentioned legislation would be an offence for which the maximum fine on summary conviction is unlimited.

EVC1 Electric Vehicle Charging Points - Condition
Before the electrical system is installed a scheme detailing the dedicated facilities that will be

provided for charging electric vehicles and other ultra-low emission vehicles shall be submitted to and approved in writing by the Local Planning Authority. The scheme shall meet at least the following minimum standard for numbers and power output:

- A Standard Electric Vehicle Charging point providing a continuous supply of at least 16A (3.5kW) for each residential unit that has a dedicated parking space
- One Standard Electric Vehicle Charging Point providing a continuous supply of at least 16A (3.5kW) for at least 10% of residential parking spaces that are not allocated to specific dwellings

Buildings and parking spaces that are to be provided with charging points shall not be brought into use until the charging points are installed and operational. Charging points installed shall be retained thereafter.

Reason: In the interest of supporting and encouraging low emission vehicles, in the interest of air quality enhancement, to comply with the aims and objectives of Policies LP20, LP24 and LP47 of the Kirklees Local Plan and Chapters 2, 9 and 15 of the National Planning Policy Framework.

EVF1 Electric Vehicle Charging Points – Footnote

- A Standard Electric Vehicle Charging Point is one which is capable of providing a continuous supply of at least 16A (3.5kW) and up to 32A (7kW). The higher output is more likely to be futureproof
- Standard charging points for single residential properties that meet the requirements specified in the latest version of *"Minimum technical specification - Electric Vehicle Homecharge Scheme (EVHS)"* by the Office for Low Emission Vehicles will be acceptable. Basically, charging points that provide Mode 3 charging with a continuous output of least 16A (3.5kW) and have Type 2 socket outlet would be acceptable
- For developments where some or all of the parking is likely to be used for shorter stay parking (30mins to 4 hours) then Fast (7-23kW) or Rapid (43kW+) charging points may be more appropriate. If Fast or Rapid charging points are proposed together with restrictions on the times that vehicles are allowed to be parked at these points then a lower number of charging points may be acceptable.
- The electrical supply of the final installation should allow the charging equipment to operate at full rated capacity.
- The installation must comply with all applicable electrical requirements in force at the time of installation.