Subject:	RE: Attached letter from Kirklees Council regarding application number 2022/90602 at location Land at Hart Street, Newsome, Huddersfield, HD4 6LS
Date:	16 March 2022 18:07:19

Further to the provision of additional sectional details by the developer's consultants, it would appear that they have not been able to establish the condition of the mill pond wall supporting Naomi Road and as such when the water in the mill pond is being drained, they will need to provide additional comments on their sectional details to assure us that the condition of wall will be continually monitored and that should any significant defects be detected which could potentially undermine its stability, they will implement all necessary temporary measures to adequately support the wall pending the successful completion of the infilling works.

Furthermore, the fill material, its placement and compaction will all need to comply with DMRB Specification for Highway Works, which will need to be clearly detailed on the revised sectional drawings prior to further consideration be given to discharge of the relevant condition.

Regards

Farhad Khatibi

Bridges & Structures Manager
Structures Section
Highways and Streetscene
Kirklees Council

Highways Service I Flint Street I Fartown I Huddersfield I HD1 6LG

☏ **External:** 01484 221000 **Internal:** 74199
Mobile: None
✉ **Email:** farhad.khatibi@kirklees.gov.uk