ACS Consulting
tree consultants

Our Ref: 4668/TW.22

Cygnet Langdale, 32 and 34 Greenhead Road,
Gledholt, West Yorkshire HD1 4EZ.

Tag No.	Identity	Particular Schedule of Works Required
1	Beech	Crown reduce by up to 1m cutting back to suitable lateral branches creating wounds of no more than 10mm in diameter to leave a canopy of approximately 4m in width.
3	Lime	Retain the tree and repair the wall. Remove dead wood.
G1	Cypress	Fell and remove. (Option 2).
G2	Cypress	Fell and remove.

Notes

Works in accordance with BS3998 – 2010

Not for planning control.

Any defects are to be reported to ACS Consulting – 01565 755422

No deviation from the specification without written consent.

General Risk Assessment and Method Statement to be supplied. Bat risk assessment to be supplied

Crown cleaning i.e. removal of any dead, diseased, broken or rubbing branches that were found.