The use of this data by the recipient acts as an agreement of the following statements. Do not use this data if you do not agree with any of the following statements:-

Ryder Architecture has co-ordinated relevant information received from third parties, but are not responsible for the content of the information received from others.

The controlled version of this drawing should be viewed in DWF or PDF format not DWG or other formats. All prints of this drawing must be made in full colour.

Where this drawing has been based upon Ordnance Survey data, it has been reproduced under the terms of Ryder Licence No. 100000144. Reproduction of this drawing in whole or in part is prohibited without the prior permission of Ordnance Survey.

Do not scale the drawing. Use figured dimensions in all cases. Check all dimensions on site. Report any discrepancies in writing to Ryder before proceeding.

Scale Bar (m)

0 2 4 8 16

N

NOTE
Refer to planting schedule on drawing 7000

HOPE STREET

OLSON STREET

STONEFIELD STREET

74.4m

13 1 2 7 5 3 8 12a 12 14 17 9 11 19 23 24

C02

5 No. Betula pendula 'Fastigiata'

32 No. Blechnum spicant
28 No. Polystichum setiferum
21 No. Buxus sempervirens

26 No. Polystichum setiferum
23 No. Blechnum spicant
23 No. Carex oshimensis 'Evergold'
7 No. Cornus sanguinea 10%
7 No. Corylus avellana 10%
10 No. Prunus spinosa 15%
4 No. Rosa arvensis 5%
7 No. Viburnum opulus 10%
33 No. Crataegus monogyna 50%
20 No. Asplenium scolopendrium
17 No. Buxus sempervirens

8 No. Cornus sanguinea 10%
8 No. Corylus avellana 10%
11 No. Prunus spinosa 15%
4 No. Rosa arvensis 5%
8 No. Viburnum opulus 10%
36 No. Crataegus monogyna 50%

189 No. Panicum virgatum 'Heavy Metal'

251 No. Stipa tenuissima

25 No. Hebe 'Red Edge'
46 No. Panicum virgatum 'Northwind'
25 No. Polystichum setiferum

12 No. Hebe 'Red Edge'

21 No. Hebe 'Red Edge'
34 No. Cornus sanguinea

10 No. Helenium 'Moerheim Beauty'
9 No. Polystichum setiferum

4 No. Prunus 'Sunset Boulevard'

t John's
.odge

Rev	Description	Drawn	Checked	Date
C02	Tree planting number and specification amended to be fastigiate trees set 2m away from external fences, underground ducts and ret wall foundations. 4no trees behind disabled bays on Halifax Rd added. No tree planting behind parking spaces 1 to 11 on Pyrah St. Fence and hedge alignment to stone buttress wall amended. Raised planter added to MSCP entrance. Layout of ornamental planting to Halifax Rd amended to allow for direct access to main door and maintenance path around the Oldroyd building. Tree planting on Pyrah St car park amended to avoid area of japanese knotweed. Carlton Road pedestrian gate next to new 5 storey core amended to open inwards. Halifax Rd pedestrian gate from Oldroyd building amended to be double set of gates fixed to centre of existing pillars to reduce extent of protrusion	AOL	SAY	12/04/23
C01	Site plan updated and planting plan updated to suit revised areas	AOL	AOL	06/12/22
P8	Issued for Stage 4	ZLI	AOL	21/06/21
P7	Planting plan revised in line with revised site layout	AOL	SBL	08/04/21
P6	Planting plan revised to show additional trees and updated planting species	AOL	SBL	29/03/21
P5	Tree planting revised following comments from WYP and WD	AOL	SBL	23/03/21
P4	Area of species rich grassland revised, site plan updated following comments from civil engineers	AOL	SBL	09/03/21
P3	Issued for Stage 3	AHA	AOL	25/02/21
P2	Planting amended following ecologists comments	AHA	AOL	19/02/21
P1	First Issue	AHA	AOL	09/02/21

Suitability
Issued for Stage Approval

Project
6BKD1
Willmott Dixon

Drawing
Planting Plan North

Drawing Number

Project ID	Originator	Zone	Level	Type	Role	Number
6BKD1	- RYD	- ZZ	- XX	- DR	- L	- 70002

Project Number	Scale at A1	Status	Revision
3273-01	1 : 200	S4	C02

info@ryderarchitecture.com
www.ryderarchitecture.com

Ryder