




EXISTING GROUND FLOOR PLAN

1:100@A4

KEY

— SKIRTING

— DOOR SURROUND

— WINDOW SURROUND

ALL SURFACES TO BE CLEANED AND LOOSE MATERIALS TO BE REMOVED. ANY REPAIRS TO WOOD BASED FEATURES, SUCH AS WINDOWS AND DOOR FRAMES, MUST BE COMPLETED IN LINE WITH TRADITIONALLY RESPECTED RESTORATIVE TECHNIQUES, SUCH AS PATCHING, PIECING IN, AND CAREFULLY REINFORCING THE STRUCTURE OF THE WOOD. REPAIRS WILL FIT IN LINE WITH THE EXISTING STYLE AND COLOURS OF THE CURRENT WORK, AS WELL AS BEING PHYSICALLY COMPATIBLE WITH THE MATERIALS ORIGINALLY USED. EXISTING PAINT TO BE REMOVED USING CHEMICAL SURFACE STRIPPERS AND SAND PAPERING METHODS ONLY. SURFACES TO BE REPAINTED WITH 2 COATS OF DULUX WILLOW TREE QUICK DRY SATINWOOD PAINT

KUFIC ARCHITECTS

Suite 24 Batley Business Park,
Technology Drive,
Batley WF17 6ER

Tel: 01924 694 404
info@kufic.co.uk
www.kufic.co.uk

PROJECT:
23-25 BRADFORD ROAD
DEWSBURY
WF13 2DU

TITLE:
CONVERSION OF EXISTING BUILDING
TO APARTMENTS

DESCRIPTION:
JOINERY DETAILS

DATE: 22/05/23
SCALE: 1:100 @ A4

DRAWN: HD
CHECKED: YA

DRAWING REF:
22270-D08-A

REV:

JOINERY DETAILS

23-25 BRADFORD ROAD, DEWSBURY, WF13 2DU


REF: 22270 - A

Office 1

Window surrounds



Skirting



Architrave



Door



Office 2

Window surrounds

