

FirstLite

LM3**Product Features**

The LM3 lens module is part of our budget range of LED's and comes with a three year warranty. LM modules offer excellent illumination for general signage projects. Use in signage with return depths of between 60mm - 150mm. 2835 SMD LED Chip.



PRICE

Product Specifications

COLOUR	<input type="radio"/> WHITE
LED QUANTITY	3
POWER CONSUMPTION	1w
VOLTAGE	12 VOLT DC
AMBIENT TEMPERATURE	-25°C to +60°C
DIMENSIONS (length x width x height)	71mm x 14.5mm x 4.5mm
VIEWING ANGLE	160°
IP RATING	IP 65
MODULE SPACING (centre to centre)	185mm
LED MODULES per METRE	6
MODULES POWERED BY A 30w DRIVER	27
MODULES POWERED BY A 60w DRIVER	54
MOUNTING	3M VHB ADHESIVE TAPE & MECHANICAL
MAXIMUM AMOUNT OF MODULES IN ONE RUN	25
LUMENS per MODULE	<input type="radio"/> 100
SYSTEM CERTIFICATIONS	RoHS
COLOUR TEMPERATURE	<input type="radio"/> 5000K

