

ARBORICULTURAL REPORT
to BS 5837:2012
at
Primrose Lane
Liversedge
West Yorkshire

Client:

Jones Homes
(Yorkshire) Limited

Client Address:

Green Bank House
Green Bank
Cleckheaton
West Yorkshire
BD19 5LQ

Client Telephone:

01274 852700

JCA Ref:

21600/AJB

JCA Limited

Arboricultural & Ecological Consultants

Contents

1. Introduction 3

1.1 Purpose of the Report..... 3

1.2 Terms of Reference 3

1.3 Scope of the Report..... 3

1.4 Survey Details..... 4

2. Site Description 4

2.1 Topography and Land Use 4

2.2 Treescape and Visual Amenity Value 4

2.3 Age Class Mix 4

2.4 Species Diversity 4

3. Status of the Trees..... 5

4. Tree Descriptions and Recommendations..... 5

5. Discussion Relating to the Existing Treescape..... 6

5.1 Tree Condition & Recommended Works 6

5.2 General Design Advice 6

6. Conclusions 8

Appendix 1: Tree Descriptions and Recommendations 10

Appendix 2: Explanation of Tree Descriptions 11

Appendix 3: General Guidelines 13

Appendix 4: Glossary of Terms & Abbreviations 14

Appendix 5: Author Qualifications..... 15

Appendix 6: Tree Constraints Plan..... 16

1. Introduction

1.1 Purpose of the Report

- 1.1.1 This report is required at **Primrose Lane, Liversedge**, to provide detailed, independent, arboricultural advice on the trees present, in the context of potential development.
- 1.1.2 The purpose of this report is to summarise the findings of an arboricultural assessment of the existing vegetation at the above site; conducted in accordance with the guidelines contained within BS5837: 2012 'Trees in relation to design, demolition and construction – Recommendations'.
- 1.1.3 Where necessary, this report will outline any tree works which are required within the current context of the site. It will also grade the trees in accordance with the British Standard; which will guide the design in terms of which trees should be retained and which trees could be removed.

1.2 Terms of Reference

- 1.2.1 JCA Ltd has been instructed by **Jones Homes (Yorkshire) Limited** to survey the site and prepare the findings in a report.
- 1.2.2 For this purpose, a topographical survey has been supplied (**Drawing Ref. Liversedge-survey-new boundary added**), which forms the basis for the Tree Constraints Plan at **Appendix 6**. The topographical survey, along with all other documents supplied to JCA, is assumed to be correct. No checking of such documents will be undertaken and JCA cannot be held responsible for incorrect data supplied by other parties.

1.3 Scope of the Report

- 1.3.1 This report is compiled in accordance with *BS 5837:2012 'Trees in relation to design, demolition and construction – Recommendations'* and is based on an independent and objective assessment of the existing vegetation.
- 1.3.2 All trees within the site boundary with a stem diameter above 75mm are included.
- 1.3.3 Where applicable trees outside the site boundary, but close enough to be affected by the proposed development, are included.
- 1.3.4 The specific designs of the proposed development are not generally taken into account at this stage or detailed within this report. This is to be detailed in an Arboricultural Impact Assessment.

1.4 Survey Details

- 1.4.1 The survey took place during December 2023 and was conducted by **Andrew Bussey** *LANTRA Accredited PTI*.
- 1.4.2 During this survey, all trees were inspected from ground level. Further investigations, such as a climbed inspection or a decay detection survey, have not been undertaken.
- 1.4.3 Measurements were obtained using clinometers, specialist tapes or electronic distometers. Where this was not possible, measurements were estimated to the best ability of the surveyor. JCA endeavour to provide accurate information and will always take measurements unless inhibited by restricted access or other mitigating circumstances. Where measurements have been estimated, they are clearly highlighted at **Appendix 1**.

2. Site Description

2.1 Topography and Land Use

- 2.1.1 The site, which slopes from the south down towards the northern boundary, is occupied by open field which are used as horse paddocks.

2.2 Treescape and Visual Amenity Value

- 2.2.1 Collectively, those trees which fall into retention category 'B' and 'A' within this report provide a good addition to the local; treescape and visual amenity value of the area.

2.3 Age Class Mix

- 2.3.1 The trees surveyed ranged in age from young to mature.

2.4 Species Diversity

- 2.4.1 Species surveyed include Hawthorn, Elder, Sycamore, Goat Willow, Common Alder and Pine.

3. Status of the Trees

- 3.1 A check was made on 11th January 2024 with **Kirklees Metropolitan Council**.
- 3.2 We are informed that there is no Tree Preservation Order (TPO) in force and that the site is not within a Conservation Area.
- 3.3 Due to the large potential penalties for illegally carrying out work to protected trees, JCA recommend that a further check is carried out prior to any works being undertaken. This is especially relevant as the Local Authority is able to serve a TPO at any time.

4. Tree Descriptions and Recommendations

- 4.1 Full details of all individual trees surveyed are recorded in the tables at **Appendix 1**. A full explanation of the tables can be found at **Appendix 2**. Please refer also to the Tree Constraints Plan at **Appendix 6** for tree locations.

5. Discussion Relating to the Existing Treescape

5.1 Tree Condition & Recommended Works

- 5.1.1 The tree survey revealed a total of **9** items of vegetation (**7** individual trees, **1** hedge and **1** woodland). Of these, **1** woodland was identified as retention category 'A', **4** trees and **1** hedge were identified as retention category 'B' and **3** trees were identified as retention category 'C'. Please refer to **Appendix 2** for retention category and definition criteria.
- 5.1.2 The trees were generally found to be in a good condition, as such, no tree works are required under the current context of the site.
- 5.1.3 All trees which are to be retained within the proposed development should be inspected on a regular basis in the interests of risk management.

5.2 General Design Advice

- 5.2.1 The following is an overview of the general design considerations relating to tree cover.
- 5.2.2 The precise details of a proposed development are not known at present. The specific implications of a proposed design should be assessed within an Arboricultural Implications Assessment (AIA).
- 5.2.3 The retention categories of the trees surveyed are an indication of their overall values. The category of each item is listed at **Appendix 1** and an explanation of the retention categories is included at **Appendix 2**. As a general rule, those trees listed as retention category 'A' or 'B' are the most valuable items and as such the removal of these is likely to be met with resistance by the Local Planning Authority (LPA). Those items listed as retention category 'C' are of lesser value and the removal of these is less likely to be met with resistance by the LPA. The above information should guide the design in terms of which trees are to be removed and which are to be retained. However, it should be noted that the retention of trees is just one consideration in the design process and each development will be taken for its merits.
- 5.2.4 The location of each tree is plotted on the associated Tree Constraints Plan at **Appendix 6**. This plan identifies the retention category of each tree (Retention A: green canopy, Retention B: blue canopy, Retention C: grey canopy, Retention U: red canopy), the crown spread, and also the associated rooting zone (Root Protection Area or RPA shown in gold). In order to enable the survival of trees shown to be retained within any proposals, both the canopy of the tree and its RPA must be completely avoided wherever possible. This relates to not just the location of new buildings, but also to the location of new areas of hard standing, proposed utility routes and any ground level changes (both excavations and soil piling). Where this is not possible, specialist construction methods and materials will need to be used.

- 5.2.5 Where information is available, the water demand of each tree is provided at **Appendix 1**, in accordance with NHBC Standards 2014 chapter 4.2. 'Building near trees'. The water demand of trees can affect adjacent structures and this is therefore included to inform foundation design, depth and the proximity of proposed structures to trees.
- 5.2.6 Retained trees will require adequate protective measures during development. Such measures typically entail temporary protective fencing, installed to the full extent of the RPA. Where this is not entirely possible, ground protection may also comprise part of the protective measures. This includes a compaction reducing construction detail which enables a degree of construction traffic over/within the RPA.
- 5.2.7 As the RPAs of the trees will require fencing off as a protection measure, this should be brought into consideration when planning such things as access routes and material storage during development. It is accepted that in some cases it is not entirely possible to completely avoid the RPA or canopy lines within a new development. The consulting arboriculturalist should therefore be made aware of any such incursions to make comment and, where possible, advise on mitigation actions. Such details should be contained within an Arboricultural Implications Assessment (AIA).
- 5.2.8 No material storage is permitted within the RPA of retained trees unless confirmed to be acceptable by the consulting arboriculturalist. The exact details and location of protective measures should be included within an Arboricultural Method Statement (AMS).
- 5.2.9 The position of the site compound is a major consideration. It is recommended that this, which typically includes the site office, facilities, toilets, storage of materials and parking, is located away from trees and outside the RPA.
- 5.2.10 Many development sites contain areas of nature conservation interest. Trees and hedgerows, in particular, can provide an important habitat for birds, bats, invertebrates and fungi and appropriate attention needs to be paid to preserving habitats throughout the development process. JCA can provide Ecological Surveys and Bat Surveys where required.
- 5.2.11 If a landscape planting scheme is proposed, consideration must be made at the planning stage as to where this is to be implemented on site. Such locations should be protected in order to prevent soil compaction and/or contamination and should therefore form part of the Construction Exclusion Zone. JCA can provide Tree Planting Schemes where required.

6. Conclusions

- 6.1 The trees surveyed were generally found to be in a good condition.
- 6.2 The trees are not protected by a Tree Preservation Order or by virtue of them being in a Conservation Area.
- 6.3 No tree works are required under the current context of the site.
- 6.4 General design advice has been provided in **Section 5.2**.
- 6.5 Upon provision of specific proposals, site-specific advice can be given with regards to the impact on trees. In accordance with **Section 5.4** of **BS 5837: 2012**, the next stage on this site should be the preparation of an **Arboricultural Impact Assessment (AIA)**, which will illustrate and discuss the impact of the proposals on the trees and vice versa, to help to inform good design.
- 6.6 The data gained during the survey provides an indication of the health of the trees. However, it does not enable a comprehensive assessment of their condition over time. Trees are living organisms which are affected by many factors including weather conditions, diseases/disorders, light levels and human activities. Because of this, this report is only valid for a period of 1 year from the date of issuing. Should an update or revision of this report be required outside of this time period, JCA may require a further site visit to ensure that the condition of the trees has not significantly changed. It is advised that the trees are inspected regularly, in the interests of risk management.

Appendices

Tree Ref.	Age Common Name <i>Botanical Name</i>	Height (m)	Crown Height (m)	Height (m) and Direction of the Lowest Branch	Diameter (cm)	Crown Spread N W E S	Observations	Recommendations Priority	Physiological Condition	Structural Condition	Amenity Value	NHBC Water Demand	Life Expectancy (yrs)	Retention Category
H 1	Early-mature Hawthorn <i>Crataegus monogyna</i>	Tom 3	0+	0+ n/a	To 10	See plan	Maintained hedgerows, occasional Elder noted.	No action required. n/a	GOOD	GOOD	MOD	LOW TO HIGH	40+	B 2
T 2	Early-mature Sycamore <i>Acer pseudoplatanus</i>	11	2	2 n/a	40#	4 4 4	Twin-stemmed at 2m with a balanced crown. Not fully inspected due to H1 .	No action required. n/a	GOOD	GOOD	MOD	MOD	40+	B 1
T 3	Early-mature Sycamore <i>Acer pseudoplatanus</i>	12	2	2 n/a	48#	4.5 4.5 4.5	Single-stemmed and vertical with a balanced crown. Not fully inspected due to H1 .	No action required. n/a	GOOD	GOOD	MOD	MOD	40+	B 1
T 4	Early-mature Hawthorn <i>Crataegus monogyna</i>	5	1	0 n/a	12 x 7 Avg.	3 3 3	Multi-stemmed at ground level with a balanced crown. Elder noted growing within.	No action required. n/a	GOOD	GOOD	LOW	LOW TO HIGH	40+	C 1
T 5	Mature Goat Willow <i>Salix caprea</i>	7	0	1 n/a	75#	5.5# 5.5# 5.5#	Multi-stemmed at 1.5m with a balanced crown. Not fully inspected due to vegetation.	No action required. n/a	GOOD	GOOD	MOD	HIGH	40+	B 1
T 6	Mature Sycamore <i>Acer pseudoplatanus</i>	14	0	0.5 n/a	35 x 7 Avg.	6 6 6	Multi-stemmed at ground level with a balanced crown. Not fully inspected due to a fence and vegetation.	No action required. n/a	GOOD	GOOD	MOD	MOD	40+	B 1
W 7	Young to mature Mixed species <i>Details in observations</i>	To 16	0+	0+ n/a	To 75#	See plan	Situated on adjacent land. A woodland consisting of Sycamore, Hawthorn, Common Alder and Pine. Not fully inspected under the remit of this report. Not all tree stems within the woodland within influencing distance of the proposed development were shown on the topographical plan provided.	No action required. n/a	GOOD	GOOD	HIGH	MOD TO HIGH	40+	1 A 2
T 8	Early-mature Sycamore <i>Acer pseudoplatanus</i>	13	2	2 n/a	43	3.5 3 3	Twin-stemmed at 1.5m with a balanced crown. Included bark present at the stem junction.	No action required due to low public land use. n/a	GOOD	GOOD	LOW	MOD	10+	C 1
T 9	Early-mature Sycamore <i>Acer pseudoplatanus</i>	14	2.5	2.5 n/a	49	3.5 4.5 4.5	Multi-stemmed at 3m with a balanced crown. Multiple pruning wounds, many leaving stubs. Exposed roots noted. A small cavity is present on the stem at 0.5m.	No action required due to low public land use. n/a	GOOD	GOOD	LOW	MOD	20+	C 1

Appendix 2: Explanation of Tree Descriptions

A2.1 Measurements/ Reference Information

- A2.1.1 *REF NUMBER*. All items surveyed are allocated a reference number preceded with a letter, identifying the type of vegetation surveyed: T = an individual tree, G = a group of trees or an area of vegetation, W = woodland, H = a hedgerow.
- A2.1.2 *SPECIES: COMMON AND BOTANICAL NAME*. The common and botanical names of the species present are noted. If the species is not clear or identifiable, then a general common name and genus will be noted.
- A2.1.3 *AGE CLASS* of the tree is described as young, semi-mature, early-mature, mature, over-mature, veteran or dead.
- A2.1.4 *HEIGHT* of the tree is measured in metres from the stem base to the top of the crown.
- A2.1.5 *CROWN HEIGHT* is an indication of the height above ground level at which the crown begins.
- A2.1.6 *STEM DIAMETER* is measured at 1.5 metres above (higher) ground level. Where the tree is multi-stemmed at this point; diameter measurements are taken for each stem. If more than five stems are present, an average stem diameter is taken. If for whatever reason it is not practical to measure multiple-stemmed trees in this way, the diameter is measured close to ground level, just above the root buttress.
- A2.1.7 *CROWN SPREAD* is measured from the centre of the stem base to the tips of the branches to all four cardinal points.
- A2.1.8 *HEIGHT AND DIRECTION OF LOWEST BRANCH*. The height and direction of the lowest significant branch is noted because of potential issues relating to clearances and the need for tree pruning.
- A2.1.9 *NHBC WATER DEMAND*. The water demand of each tree, as listed in NHBC Standards 2010 Chapter 4.2 'Building near trees'. This is included to aid structural engineers, architects and other members of the design team as it determines foundation depth and other considerations with regard to trees.

A2.2 Evaluations

- A2.2.1 *PHYSIOLOGICAL CONDITION* is classed as good, fair, poor, or dead. This is an indication of the health and vitality of the tree and takes into account vigour, presence of disease and dieback.
- A2.2.2 *STRUCTURAL CONDITION* is classed as good, fair or poor. This is an indication of the structural integrity of the tree and takes into account significant wounds, decay and quality of branch junctions.
- A2.2.3 *LIFE EXPECTANCY* is classed as; Dead, less than 10 years, 10+ years, 20+ years, or 40 + years. This is an indication of the minimum number of years before removal of the tree is likely to be required.
- A2.2.4 *AMENITY VALUE*. A general indication is given in respect to the amenity/landscape value of the tree/group within the surrounding area.
- A2.2.5 *PRIORITIES*. A priority rating is given concerning the time periods in which the recommended works should be undertaken. LOW priority works should be undertaken within 12 months of the survey, MOD (moderate) priority works should be undertaken within 6 months and HIGH priority works should be completed as soon as practically possible. If no works are recommended, N/A (not applicable) will be used.

A2.3 Retention Categories

- A2.3.1 *A (marked green on the Tree Constraints Plan) = Trees of high quality.*
- These trees are of high quality and value with a good life expectancy (usually with an estimated remaining life expectancy of 40 years).
- A2.3.2 *B (marked in blue on the Tree Constraints Plan) = Trees of moderate quality.*
- These trees are of moderate quality and value with a reasonable life expectancy (usually with an estimated life expectancy of at least 20 years).
- A2.3.3 *C (marked in grey on the Tree Constraints Plan) = Trees of low quality.*
- These trees are of low quality and value but which are in adequate condition to remain or are young trees with a stem diameter below 15cm (usually with an estimated life expectancy of at least 10 years).
- A2.3.4 Trees categorised as retention category 'A', 'B' or 'C' are then justified by being further divided into 3 subcategories:
- 1 = Mainly arboricultural qualities.
 - 2 = Mainly landscape qualities.
 - 3 = Mainly cultural values, including conservation value.

Appendix 3: General Guidelines

- A3.1 All tree work should be undertaken to BS 3998: 2010 '*Recommendations for tree work*' or other recognised industry practice.
- A3.2 Staff carrying out the work must be qualified, experienced and ideally be Arboricultural Association approved contractors. They should be covered by adequate public liability insurance.
- A3.3 This report is based upon a visual inspection. The consultant shall not be responsible for events which happen after this time due to factors which were not apparent at the time, and the acceptance of this report constitutes an agreement with the guidelines and the terms listed therein.
- A3.4 Any defects seen by a contractor or the employer that were not apparent to the consultant must be brought to the consultant's attention immediately.
- A3.5 No liability can be accepted by JCA in respect of the trees unless the recommendations of this report are carried out under the supervision of JCA and within JCA's timescale.
- A3.6 It is advisable to have trees inspected by an arboricultural consultant on a regular basis.

Appendix 4: Glossary of Terms & Abbreviations

Arboriculture	The cultivation of trees in order to produce individual specimens of the greatest ornament, for shelter or any primary purpose other than the production of timber or fruit.
Canker	Disease damaged area of a tree, usually caused by fungus or bacteria affecting the bark.
Co-dominant stem	A stem which has grown in direct competition to the main stem and which has formed a substantial size influencing the appearance of the tree.
Crown lift	The removal of the lowest branches, usually to a given height. It allows more residual light and greater clearance underneath for vehicles etc.
Crown reduction	The reduction of a tree's height and spread while preserving its natural shape.
Crown thin	The removal of some of the density of a tree's crown, usually 5-15% allowing more light through its canopy and reducing wind resistance.
Deadwood	Either dead branches, or a procedure involving the removal of dead, dying and diseased branches.
Dieback	Where branches are beginning to show signs of death usually at the tips in the crown.
Epicormic shoots	Small branches that grow in clusters around the base of the stem of a tree or within the crown. This is usually as a result of bad pruning or some other stress factor, although can be a natural growth pattern for some species of tree (eg Lime species).
Included bark	Where the bark on two adjoining branches or stems is growing tight together, forming a joint with limited physical strength.
Pollarding	A method of tree management in which the main trunk and principle branches of the tree are cut to the same height, and the resulting branches are then cropped on a regular basis.
Remedial pruning	The removal of old stubs, deadwood, epicormic growth, rubbing or crossing branches and other unwanted items from the tree's crown. Sometimes referred to as crown cleaning.
RPA	Root Protection Area – Theoretical rooting area of a tree as defined in BS 5837:2012 ' <i>Trees in relation to design, demolition and construction – Recommendations</i> '.
Topping	Topping is a form of pruning that removes terminal growth leaving a 'stub' cut end. Topping can cause serious health problems to a tree.

Appendix 5: Author Qualifications

Principal Consultant and Managing Director

Jonathan Cocking *F.R.E.S., Tech. Cert. (Arbor.A), PDipArb (RFS) FArborA CBiol MSB. MICFor.* Jonathan is a Registered Consultant and Fellow of the Arboricultural Association and sits on its Professional Committee. He has 31 years' experience in the Arboricultural profession and served for eight years as Senior Arboriculturist with a large local authority before establishing JCA in 1997. Jonathan has since developed JCA's portfolio of services and its extensive client base. He is a Chartered Biologist, a Chartered Arboriculturalist and an Expert Witness with much experience of litigation work.

Technical Director

Toby Thwaites *BSc (Hons), HND (Arboriculture), MArborA.* Toby joined JCA in 1998 after graduating in Ecology at the University of Huddersfield and has since graduated in Arboriculture at the University of Central Lancashire. A former JCA team leader and Consulting Arboriculturist, Toby is now Technical Director and oversees all office and on-site activities at JCA and is on hand to offer technical support and advice.

Operations Director

Charles Cocking *FdSc (Arboriculture), MArborA.* Charles joined JCA in January 2014 having previously worked for the company on a part time basis during 2013. Charles obtained his Foundation Degree in Arboriculture at Askham Bryan College, York, and is a Professional Member of the Arboricultural Association. Charles now oversees all internal operations for the company.

Consulting Staff: Arboriculture

Andrew Bussey. Andrew started working in consultancy at JCA in 2006 having spent 12 years working as an arborist for various private companies before joining a Local Authority forestry team. He has various NPTC qualifications, is QTRA qualified and is a LANTRA Accredited Professional Tree Inspector.

Emily Wilde *FdSc (Arboriculture).* Emily joined JCA having previously worked for various private tree surgery and consultancy companies over the past 8 years. She initially obtained a ND in Forestry & Arboriculture, followed by a FdSc in Arboriculture at Askham Bryan College, York. Emily has various NPTC certificates and is QTRA qualified.

Mick Eltringham *ND (Forestry).* Mick joined JCA after spending 12 years working in the industry for various private companies in the north and south of England. He has also spent the last five years working as a consultant for two canopy research projects in the Amazon Rainforest, working with Oxford University and the University of Arizona. He has various NPTC Qualifications.

Dan Kemp *FdSc (Arboriculture), BTEC National Diploma(Arboriculture), National Certificate In Horticulture, City & Guilds In Horticulture.* Dan joined JCA in February 2019 with nearly 30 years' experience in arboriculture with extensive Botanical and Mycological expertise. He worked as a London Tree Officer for 12 years and in several arboricultural and horticultural management posts, specialising particularly in tree risk assessments and tree related subsidence.


Luke Wickham *FdSc (Arboriculture and Urban Forestry), TechArborA.* Luke joined JCA in 2021 after obtaining his Foundation Degree in Arboriculture and Urban Forestry at Askham Bryan College. Having previously worked within the industry for the past 4 years, running his own small business and sub-contracting for local firms, Luke brings a sound knowledge and understanding of the practical and academic sides of the industry.

Andrew McPhaden *BSc (Hons), TechArborA.* Andrew joined JCA in 2022 having spent 5 years working as an Arborist for various private companies in both the UK and Germany. During his time abroad he obtained the European Tree Worker Certification along with a tree inspector certification from the Forschungsgesellschaft Landschaftsentwicklung Landschaftsbau. He brings a strong understanding of the practical sides of the industry and holds various NPTC qualifications.

Administrative Staff

Catherine Cocking Accounts Manager.
Kelly Saunders Accounts Assistant.

Lorraine Spink Administrative Assistant.
Adie Gray I.T. Officer.




THIS PLAN IS TO BE PRINTED IN COLOUR
AND READ IN CONJUNCTION WITH THE
JCA ARBORICULTURAL REPORT
(JCA REF: 21600/AJB)

Root Protection Area: RPA

THE ROOT PROTECTION AREA SHOULD IDEALLY REMAIN
UNDISTURBED IF THE TREE IS TO BE RETAINED.

THE DEVELOPMENT PROPOSALS SHOULD THEREFORE BE
DESIGNED TO AVOID THE RPA OF ANY TREE WHICH IS TO
BE RETAINED.

IF IT IS NECESSARY FOR THE DEVELOPMENT TO ENCROACH
INTO THE RPA OF A TREE WHICH IS TO BE RETAINED THEN
SPECIALIST CONSTRUCTION TECHNIQUES AND MATERIALS
MUST BE CONSIDERED.



Appendix 6: Tree Constraints Plan

ADDRESS: Primrose Lane, Liversedge,
West Yorkshire.
JCA REF: 21600/AJB

SCALE : 1:1000 PAPER SIZE : A3
SURVEYED BY: AJB DRAWN BY: AJB APPROVED BY: TT

BRITISH STANDARD 5837:2012: 4.5 RETENTION CATEGORIES	
Detailed definitions of these categories are at Appendix 2 of our report. N.B. These categories do not necessarily represent or correspond to recommendations for action made in this report.	
	CATEGORY A: 'RETENTION MOST DESIRABLE'
	CATEGORY B: 'RETENTION DESIRABLE'
	CATEGORY C: 'TREE WHICH COULD BE RETAINED'
	CATEGORY U: 'TREE FOR REMOVAL'
	STEM OF TREE TO BE RETAINED
	STEM OF TREE TO BE REMOVED
	ROOT PROTECTION AREA



I hope that this report provides all the necessary information, but should any further advice be needed please do not hesitate to contact the author.

Signed



.....

Andrew Bussey *LANTRA Accredited PTI.*

11th January 2024

For and on behalf of **JCA Ltd**

Registered Office

**Unit 80
Bowers Mill
Branch Road
Barkisland
Halifax
HX4 0AD**

Tel: 01422 376335

Fax: 01422 376232

Email: info@jcaac.com

www.jcaac.com

Report printed on recycled paper

JCA Ltd. Arboricultural and Ecological Consultants

Professional Tree and Ecology Advice nationwide

ARBORICULTURAL SERVICES

Guidance for Architects and Developers

- British Standard 5837 Tree Surveys
- Arboricultural Implication Assessments (AIA)
- Arboricultural Method Statements (AMS)

Tree Advice for the Legal Profession

- Subsidence Litigation
- Personal Injury and Accident Investigation
- Expert Witness, Planning Inquiries and Appeals

Advice for Engineers, Loss Adjusters and Insurers

- Tree Surveys for Subsidence
- Heave Assessment
- Tree Root Identification

Veteran Tree Management

- Ancient Woodland Management
- Veteran Tree Management

Advice for Local Authorities and Social Housing

- Tree Safety Surveys
- Specialist Decay Detection
- Landscape and Orchard Design

Tree Health and Pest and Disease Management

- Pest and Disease Surveys
- Tree Health Checks
- Disease Mitigation and Control

ECOLOGICAL SERVICES

Ecological Pre-Planning Services

- Phase 1 Habitat Surveys
- Great Crested Newt eDNA Sampling
- Protected Species: Bat, Wintering and Nesting Bird, Badger, Amphibian, Otter, Water Vole, White-Clawed Crayfish, Dormice and Reptile Surveys,
- Preparation for Environmental Impact Assessment (EIA)
- Invasive Species Surveys
- Code for Sustainable Homes

Ecological Post-Planning Services

- Biodiversity Enhancement Plans
- Protected Species Mitigation
- Ecological Management (Bat and Bird box installation and inspection)

HEAD QUARTERS:

Unit 80 Bowers Mill,
Branch Road,
Barkisland,
Halifax, HX4 0AD.

Tel: 01422 376335
Mobile: 07778 391986
Email: jon@jcaac.com
Website: www.jcaac.com

