

Our Ref: 22007

Via Email: Farzana.Tabasum@kirklees.gov.uk

7th December 2023

Dear Farzana

BROMLEY FARM EXTENSION PLANNING – ADDITIONAL INFORMATION

Please find detailed below the additional information requested in your email of the 29th November 2023.

1) Details of the proposed bund materials & phasing of when this will be created and removed.

The screening bund adjacent to the site access will be constructed using topsoils beneath the bund location and also topsoils and subsoils from the creation of the site access down to the top of rockhead. All topsoils will be stored separately from subsoil.

The bund will be created before mineral extraction is undertaken and will remain until the site is fully restored.

2) Details of fence

Fencing will consist of post and wire, with top two levels being barbed wire as shown below. 1.2m in height.



3) Details of trees to be planted along this part of the access road (species, nos. heights etc)

Species mix will consist of native, faster growing trees, two rows staggered at 2m centres. 146 trees in total. The species mix and numbers are:

Species	Specification	% to be planted	No of Trees
Silver Birch	60-90 cm Bare rooted	40	58
Rowan	60-90 cm Bare rooted	40	58

Hazel	45-60 cm Bare rooted	20	30
-------	----------------------	----	----

Planting will take place during the first available planting season between October to March

4) *Access road surface details, beyond the point shown on drawing 2074 -10*

Beyond the 50m of concrete the internal roadway will be a combination of compacted crushed inert material such as sandstone or soft fired product such as pipe or brick waste.

5) *HGV Routing Plan*

A HGV Routing plan, Ref 22007/517 is attached as requested.

If you have any further queries please don't hesitate to contact me.

Yours sincerely,

P Sharland

Phil Sharland
Senior Planning Consultant
Silkstone Environmental Ltd