

Fix any and all steelwork fully in accordance with the Structural Engineer's design drawings, specification and calculations. Allow for all concrete padstones to Engineer's specification, shims, temporary supports etc. associated with this work.

All steelwork to maintain 150mm bearing capacity,
clad with 15mm fire line plasterboard & skim to give
30 minutes fire resistance.



REV	
-----	--

