



- ### Private Drainage
- This drawing is to be read in conjunction with and checked against all other drawings, Engineering Details, specification and any structural, geotechnical or other specialist document provided.
 - All connections for house drainage shall be 100mm unless stated otherwise and must extend a minimum of 500mm behind the back of the footpath.
 - All pipes to be vitrified clay or UPVC and shall be 100mmØ laid to a fall of 1:80 unless noted otherwise or indicated by size and invert levels. All connections when laid shall be plugged, protected as necessary and marked with a stake for future use.
 - Building drainage shall comply with BS 8301 1985, BS EN 752 and Building Regulations PART H. Inspection chambers located within garages to have double seal bolt down covers.
 - Gully Tops and Manhole cover specification to be in accordance with BS EN 124, and located in accordance with BS EN 124 groups 1-6 and applicable to loading application.
 - This drawing is schematic for clarity only, positions of pipe runs and manholes may vary on site due to site conditions.
 - Cover and invert levels are indicative and may vary on site. In any case the following minimum cover to depth of cover to the crown of pipes without protection shall be as follows:
 - Domestic chambers and pathways without any possibility of vehicular access - 0.35m
 - Domestic driveways, parking areas and yards with height restrictions to prevent entry by vehicles with a gross weight in excess of 7.5 tonnes - 0.5m
 - Domestic driveways, parking areas and narrow streets without footways (e.g. Mews developments) with limited access for vehicles with a gross weight in excess of 7.5 tonnes - 0.9m
 - Agricultural land and public open space - 0.9m
 - Other highways and parking areas with unrestricted access to vehicles with a gross weight in excess of 7.5 tonnes - 1.2m
 Note: any protection required where drainage does not comply with a-e above shall be as follows:
 - Vitrified clay pipes - provide a 100mm min. thick concrete bed and surround (instead of class 'S' bedding) and a 13mm thick compressible filler at each joint.
 - UPVC pipes - provide a concrete bridging (in addition to class 'S' bedding) in accordance with appendix A15, Building Regulations part H.
 Note: in-situ concrete used in connection with a) and b) above shall be standard mix GEN3 in accordance with BS 5328.
 - Drainage runs should be laid at a minimum of 5.0 metres from the rear of properties where practicable to allow for future extensions.
 - Where pipes pass under buildings, unless beam & block floors are used, they are to be surrounded in concrete.
 - All branch drains, or connections, are to discharge to the collectors obliquely, and in the direction of the main flow.
 - House levels are Finished Floor Levels (FFLs), assumed to be typically a minimum of 150mm above finished ground level outside. refer to architect drawing for details.
 - All low spots on hardstanding areas to have gullies.
 - Prior to topsoiling of rear gardens, the gardens should be reworked, rotated or decompacted to a depth of 600mm. Once this is carried **NO PLANT** to access these areas, any further consolidation of subsoil to be reworked as necessary. Before reworking or rotating the Contractor is to mark all drain runs in the area.
 - Deep Flow guttering to all units to be utilised. To be taken into account when positioning RWIP's, refer to Architect's drawings.
 - Pipe bedding to be class 'S' bedding (100mm granular bed and surround).
 - Excavations for manholes, pipe runs etc located within a 45 degree load distribution splay from any adjoining existing foundations, are to be adequately supported for the duration of the works and building drainage protected.
 - Foundations adjacent to pipe runs or manholes are to have their formation level set above the invert level no higher than the equivalent of the horizontal distance between the pipe/excavation trench and the foundation, minus 500 mm.
 - Where excavations for pipe runs are parallel and in close proximity to each other and/or other service trenches. The contractor shall ensure that adequate safety measures, including temporary shoring, are provided in line with current health & safety legislation and good practice. Particular attention is to be paid to adjacent trenches of differing invert levels.
 - All existing drainage found on site during the works shall be investigated, its operational status confirmed, and the following applied:
 - Inoperative drainage shall be cut back and pipe runs filled with concrete grout.
 - 'Live' drainage shall be temporarily re-routed to allow the new drainage to be constructed.
 - Where existing drainage is to be re-used including road, building and external drainage systems, the contractor shall ensure that all chambers and drainage runs are cleaned, de-silted and made good.
 - Covers to existing chambers to be re-used shall be replaced where necessary to suit proposed development loading class, see note 5. Chamber covers shall also be adjusted to suit final ground levels as necessary.
 - Where necessary, existing chambers shall be re-benched to suit new pipework arrangement.

| KEY | |
|--|--|
| PG | Private Gully |
| G | Highway Gully to be adopted by Local Highway Authority |
| SW Manhole and Sewer to be Adopted by Yorkshire Water | |
| 1500/100 | SW Demarcation Chamber and Lateral Drain to be Adopted by Yorkshire Water |
| CL: 208.200 IL: 207.850 | Private Surface Water Manhole and Drain |
| CL: 207.168 IL: 206.515 | Private Foul Water Manhole and Drain |
| Acc channel | Acc Drainage channel at extent of private drive to prohibit SW run off onto public highway |
| Private Foul Water Rising Main | |
| Foul Water Soil Vent Pipe | |
| Surface Water Rain Water Pipe | |
| Site Boundary | |
| Extent of highway to be offered for adoption under S38 agreement | |
| CL | Manhole Cover Level |
| IL | MH Outlet Pipe Invert Level |

THE HOUSING LAYOUT SHOWN ON THIS PLAN IS TAKEN FROM ACUMEN DESIGNERS AND ARCHITECTS SITE LAYOUT REFERENCED 2492-PH4-100 DATED AUGUST 2018.

THE TOPOGRAPHICAL SURVEY SHOWN ON THIS PLAN IS TAKEN FROM ELLAM LAND SURVEYS PLAN 7538-2D/1 DATED JULY 2017.

THE COORDINATE SYSTEM USED FOR THE PRIMARY CONTROL IS OSGB36 (15)

PHASE 1 OF THE DEVELOPMENT ALREADY APPROVED AND SEWERS TO BE CONSTRUCTED UNDER YORKSHIRE WATER SECTION 104 AGREEMENT REFERENCE H-3-264-249