

REV	DATE	DESCRIPTION	DRW	CHK
P01	06.03.23	FOR PLANNING	RD	AG
P02	21.06.23	GENERAL NOTES ADDED	RD	AG
P03	07.09.23	GENERAL NOTES UPDATED	RD	AG

GENERAL NOTES

1. K FITTINGS TO THE REAR OF THE STORE ARE TO HAVE UPWARD LIGHT OMITTED
2. PLANT AREA LIGHTING IS TO BE PROGRAMMED TO ONLY BE ILLUMINATED DURING PLANT MAINTENANCE
3. CAR PARK LIGHTING & SIGNAGE SET TO ACTIVATE 07.00-23.00 MONDAY TO SATURDAY AND 08.30-17.00 SUNDAY. THE PHOTOCELL SHALL INHIBIT THE ON COMMAND.
4. BUILDING MOUNTED LIGHTING CONTROLLED VIA PHOTOCELL ONLY THEREFORE ON IN ALL HOURS OF DARKNESS.
5. CAR PARK LIGHTING & SIGNAGE DEACTIVATED BY EXTERNAL LUX SENSOR WHEN OUTSIDE LIGHT LEVEL RISES ABOVE 1400 LUX.
6. ONCE FITTINGS HAVE BEEN INSTALLED AND COMMISSIONED LIGHTING LEVELS AROUND THE BOUNDARY ARE TO BE MONITORED AND IF CONCERNS ARISE FROM LIGHT SPILL BACK LIGHT SHIELDS SHOULD BE INSTALLED TO MINIMIZE THE EFFECT



Car Park	20.2 lux	5.6 lux	0.28
Trolley Canopy	84 lux	41 lux	0.49
Plant	26 lux	12.9 lux	0.50

Symbol	Article number	Article name
EX1	CTRB4600NWG	CITY RLB T4
EX2	2 x CTR4860NWG	CITY RL T4
K	CBU200WNWG	CITY BEAM
H	SML 250	SML 250
C	CYP5430NW	CYCLONE

Client
ALDI - Aldi Stores Ltd.

Project Title
Aldi HUDDERSFIELD

Project Address
MIRFIELD ROAD HUDDERSFIELD



ELECTRICAL ENGINEERING SERVICES EXTERNAL LIGHTING

Job No. 79-E0000 WGC Originator XX Zone XX Level DR Type E

System Classification Ss_70_80_25-0001 Drawing No. S01 Suitability P03 Revision

Drawn RD Checked AG Date 06.03.23 Scale 1:250 Size A1

