


**Site Address:** Upper Quarry Road, Bradley, Huddersfield HD2 1XD

**Arboricultural Impact Assessment:**


The proposal aims to demolish the garages to the north and potentially retain the single garage to the south close to T1. If the single garage is to be removed, this should be completed inboard to protect the tree. Ground protection should be placed to the north of T1 to deter from compaction during the phases of the development.

The new building is well placed outside the RPA of T3 which will require some ground protection within the exposed RPA to deter from compaction.

T3 may require some sympathetic pruning to allow clearance for the development which should be completed in line with BS3998:2010 and facilitate a clearance of 2m limiting the wound size to 50mm.



© Barnes Associates Ltd. This plan should be viewed in... please do not scale from this drawing, all dimensions should be checked on site, any errors or divergences should be brought to the attention of Barnes Associates Ltd. All rights reserved in Chapter IV of the Copyright, Design & Patents Act 1988 have been generally asserted and copyright of this plan remains with Barnes Associates Ltd until all fees are paid in full.



**Tree Management Requirements**

Trees to be retained within the scheme and protected in line with the guidelines set out in BS5837.

Zone of Infringement- (ZOI) Indicated by Magenta shading. Areas of conflict within RPA's of retained trees.

Trees to be retained and protected in line with BS5837 though requiring facilitation pruning. Pruning to be in line with BS3998.

Notes:  
Plan is based upon the supplied topographical Survey Plan. Copies of this plan are available in CAD Formats .dwg & .dxf upon request.

Revision	Description
12/07/2023	Preliminary Issue

A

Client: Hemingway Design House

Project: Upper Quarry Road


Title: Arboricultural Impact Assessment

Drawing No: BA23077AIA Status: P

Scale: 1:100 @ A1

Date: 12/07/2023

Drawn By: MM Checked: SB Approved: SB



**BARNES associates**  
SURVEY MANAGE IMPROVE

Unit 1 Foundry Yard, New Row  
Boroughbridge YO51 9AX  
T 01423 322 371  
E info@barnesassociates.co.uk  
W barnesassociates.co.uk

Company Number 10438116  
Registered in England and Wales