

Summary of Critical Results by Maximum Level (Rank 1) for PRELIM DESIGN  
2.SWS

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m <sup>3</sup> /ha Storage	0.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	2
Number of Online Controls	2	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Ratio R	0.326
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales		Cv (Winter) 0.840
M5-60 (mm)	19.000		

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep	2.5 Second Increment (Extended)
DTS Status	ON
DVD Status	ON
Inertia Status	ON

Profile(s)	Winter
Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 480, 600, 720
Sensitivity flows(s) (%)	0, +30

PN	US/MH Name	Storm	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
S1.000	S1	15	Winter	+30%				183.726
S1.001	S2	15	Winter	+30%				181.723
S2.000	S18	15	Winter	+30%	+30%/15	Winter		181.386
S1.002	S3	15	Winter	+30%	+30%/15	Winter		181.123
S1.003	S4	15	Winter	+30%				179.320
S1.004	S5	15	Winter	+30%	+30%/15	Winter		177.761
S1.005	S6	360	Winter	+30%	+0%/15	Winter		177.209
S1.006	S7	15	Winter	+30%				175.367
S1.007	S8	15	Winter	+30%				174.765
S1.008	S9	15	Winter	+30%				174.273
S3.000	S19	15	Winter	+30%				175.499
S3.001	S20	15	Winter	+30%				174.594
S1.009	S10	15	Winter	+30%				173.717
S1.010	S11	15	Winter	+30%				172.952
S4.000	S21	15	Winter	+30%	+30%/15	Winter		172.639
S1.011	S12	15	Winter	+30%	+30%/15	Winter		172.523
S1.012	S13	15	Winter	+30%	+30%/15	Winter		171.511
S5.000	S22	15	Winter	+30%	+30%/15	Winter		175.053
S5.001	S23	15	Winter	+30%	+30%/15	Winter		173.837

Summary of Critical Results by Maximum Level (Rank 1) for PRELIM DESIGN  
2.SWS

PN	US/MH Name	Surcharged Flooded			Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
		Depth (m)	Volume (m <sup>3</sup> )	Flow / Overflow Cap. (l/s)				
S1.000	S1	-0.099	0.000	0.60		68.1	OK	
S1.001	S2	-0.097	0.000	0.62		72.4	OK	
S2.000	S18	0.386	0.000	1.03		53.7	SURCHARGED	
S1.002	S3	0.354	0.000	1.12		136.4	SURCHARGED	
S1.003	S4	-0.093	0.000	0.79		194.4	OK	
S1.004	S5	0.007	0.000	1.00		243.7	SURCHARGED	
S1.005	S6	1.416	0.000	0.09		4.5	FLOOD RISK	
S1.006	S7	-0.175	0.000	0.36		60.7	OK	
S1.007	S8	-0.177	0.000	0.35		60.7	OK	
S1.008	S9	-0.140	0.000	0.56		96.7	OK	
S3.000	S19	-0.151	0.000	0.24		27.8	OK	
S3.001	S20	-0.110	0.000	0.52		56.1	OK	
S1.009	S10	-0.115	0.000	0.69		152.8	OK	
S1.010	S11	-0.103	0.000	0.76		167.2	OK	
S4.000	S21	0.145	0.000	0.77		64.3	SURCHARGED	
S1.011	S12	0.250	0.000	0.91		226.6	SURCHARGED	
S1.012	S13	0.515	0.000	1.09		291.3	SURCHARGED	
S5.000	S22	0.088	0.000	0.82		87.0	SURCHARGED	
S5.001	S23	0.866	0.000	0.98		125.6	SURCHARGED	

Haigh Huddleston & Associates		Page 2
Firth Buildings 99-101 Leeds Road Dewsbury WF12 7BU		
Date 01/01/0001 File PRELIM DESIGN 4 FULL SI...	Designed by j.mcbride Checked by	
Micro Drainage	Network 2020.1	

Summary of Critical Results by Maximum Level (Rank 1) for PRELIM DESIGN 2.SWS

PN	US/MH Name	Storm	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
S5.002	S24	15	Winter +30%	+0%/15	Winter			171.316
S5.003	S25	15	Winter +30%	+0%/15	Winter			169.578
S6.000	S26	360	Winter +30%	+0%/120	Winter			169.554
S1.013	S14	360	Winter +30%	+0%/15	Winter			169.564
S1.014	S15	600	Winter +30%					167.165
S1.015	S16	720	Winter +30%					166.938

PN	US/MH Name	Surcharged Flooded			Half Drain Pipe		Status	Level Exceeded
		Depth (m)	Volume (m <sup>3</sup> )	Flow / Overflow Cap. (l/s)	Time (mins)	Flow (l/s)		
S5.002	S24	0.958	0.000	1.34		158.4	FLOOD RISK	
S5.003	S25	0.181	0.000	1.39		157.7	SURCHARGED	
S6.000	S26	0.866	0.000	0.01		13.2	SURCHARGED	
S1.013	S14	1.939	0.000	0.38		14.6	SURCHARGED	
S1.014	S15	-0.385	0.000	0.05		14.6	OK	
S1.015	S16	-0.362	0.000	0.09		14.6	OK	