

SPECIES LIST

ID	Qty	Species	Density	Size
A.j.Ro	8	Aucuba japonica 'Rozannie'	4	3L pot, 60-80cm
B.c.S	22	Bergenia cordifolia 'Silberlicht'	8	3L cover pot
C.a.I	12	Cornus alba 'Ivory Halo'	5	3L pot, 60-80cm
C.L	26	Crococsmia 'Lucifer'	6	2L cover pot
E.G.R	11	Euonymus 'Green Rocket'	6	2L pot, 30-40 cm
E.F.E	119	Euonymus fortunei 'Emerald Gaiety'	4	5L pot 30-40 cm
G.J.B	135	Geranium 'Johnsons Blue'	8	3L cover pot
H.R.E	18	Hebe 'Red Edge'	5	5L pot
H.P.P	11	Heuchera 'Palace Purple'	6	3L cover pot
H.a.A	9	Hydrangea arborescens 'Annabelle'	4	3L cover pot
I.a.	44	Ilex aquifolium	1	3L, 60-80cm ht
L.a.H	75	Lavandula angustifolia 'Hidcote'	6	5L pot, 15-20cm
L.n.M.G	75	Lonicera nitida 'May Green'	6	3L cover pot 30-40 cm
P.B.B	11	Phormium 'Bronze Baby'	4	3L pot min. 7 leaves
P.f.A	34	Potentilla fruticosa 'Abbotswood'	4	3L pot, 20-30cm
P.O.G.	44	Pyracantha 'Orange Glow'	1	3L, 60-80 cm ht
R.K	11	Rosa 'Kent'	4	5L pot
S.j.R	8	Skimmia japonica 'Rubella'	4	5L min pot, 40-60cm
V.b	11	Verbena bonariensis	4	3L pot
V.m.A	11	Vinca minor 'Alba'	6	3L cover pot

ID	Qty	Species	Size
SPECIMEN 2	2	Amelanchier lamarckii	10L pot 1m ht
SPECIMEN 1	1	Viburnum x bodnantense 'Dawn'	25L, branched, 6 breaks

ID	Qty	Species	Size
H.h	5	Hedera helix	2L, 40-60cm, Caned, several shoots, 5 breaks
P.h	2	Parthenocissus henryana	2L, 60-80cm, Caned, several shoots, 2 breaks

ID	Qty	Species	Size
C.L	2	Cornus alba 'Ivory Halo'	3L pot, 60-80cm
H.h	5	Hedera helix	2L, 40-60cm, Caned, several shoots, 5 breaks
P.h	2	Parthenocissus henryana	2L, 60-80cm, Caned, several shoots, 2 breaks

ID	Qty	Species	Size (girth and height)
M.d.C	8	Malus domestica 'Cox's Orange Pippin'	125-150cm ht; B; Espallier MMIO6; central leader; 3 tiers

ID	Qty	Species	Size (girth and height)
Ma.sy	7	Malus sylvestris	14-16cm, 425-600cm ht, min 200cm cs
Pa	3	Prunus avium	14-16cm, 425-600cm ht, min 200cm cs

ID	Qty	Species	Size (girth and height)
B.p	3	Betula pendula	12-14cm, 350-425cm ht, min 200cm cs
C.b.F	1	Carpinus betulus 'Frans Fontaine'	12-14, 350-425cm ht, min 175-200cm cs
Pr.Sp	3	Prunus 'Spire'	10-12cm, 300-350cm ht, min 200cm cs
P.SB	3	Prunus 'Sunset Boulevard'	12-14cm, 350-425cm ht, min 175-200cm cs
S.a.M	4	Sorbus aria 'Majestica'	12-14cm, 350-425cm ht, min 175-200cm cs
S.a.S	5	Sorbus aucuparia 'Streetwise'	12-14cm, 350-425cm ht, min 175-200cm cs

ID	Qty	Species	%	Density / sq m
C.v	119	Calluna vulgaris	50	1.7
V.m.	119	Vaccinium Myrtillus	50	1.7

ID	Qty	Species	Size (girth and height)	%
C.av	129	Corylus avellana	B; 40-60cm ht; 1+1	30
E.e	43	Euonymus europaeus	B; 40-60cm ht, 1+1, transplant, 3 breaks, 10	10
I.aq	86	Ilex aquifolium	3L pot; 40-60cm ht; bushy; 3 breaks	20
P.sp	86	Prunus spinosa	B; 40-60cm ht; 1+1	20
R.c	43	Rosa canina	B; 30-40cm ht, 1+0	10
V.o	43	Viburnum opulus	B; 40-60cm ht, 1+1, transplant, 2 breaks, 10	10

ID	Qty	Species	Size
C.bet	112	Carpinus betulus	5L pot; 80-100cm, 1+1, 5 breaks
C.t	87	Choisya ternata	5L pot, 40-60cm ht
E.D.S	119	Escallonia 'Donard Seedling'	3L pot; 40-60cm ht; 4 breaks
H.p.S	200	Hebe pinguifolia 'Sutherlandii'	3L pot; 20-30cm; 5 breaks
I.c.r	227	Ilex crenata	5L pot, 30-40cm ht 7 brks, bushy

ID	Qty	Species	Density (/m2)	Size (bulb grade)
C.bi	307	Crocus bicolor mix	20	5-6
G.n	307	Galanthus nivalis	20	5-6
H.y.s	574	Hyacinthoides non-scripta	20	6+
N.p	307	Narcissus pseudonarcissus	20	7+
T.s	307	Tulipa sylvestris	20	6+

Environmental + ecological enhancements:
 - All properties to receive a biodiversity tool kit to include, compost bin, hedgehog house and water butt.
 - Refer to Middlelm Bell Ecological Design strategy for details of the bat box, bird box and hedgehog hole locations.



KEY

EXISTING

- Site boundary
- Existing trees/vegetation

PROPOSED

- Specimen shrubs
- Espallier fruit trees against wall
- Trees
- Bulb planting
- Wildflower meadow grass (10% native wildflower, 90% grass)- EMI Basic General Purpose Meadow mixture by Emorsgate or similar approved
- Mown wildflower meadow grass (10% native wildflower, 90% grass)- EMI Basic General Purpose Meadow mixture by Emorsgate or similar approved
- Front gardens: Medallion turf by Rolawn or similar approved
- Rear gardens: Grass seed
- Diverse groundfloor. Grass Mixture (EG9 by Emorsgate or similar approved) under the proposed native hedgerow.
- Ornamental planting
- Single species hedge
- Native mixed hedge
- Ornamental gravel TBC
- Breedon Gravel footpath or similar TBC
- Dry stone wall - Entrance feature
- Indicative Steps and Handrail TBC
- SEAT
- Seat - Hatton 4 slat timber seat with backrest. Supplied by Broxap or similar approved TBC
- Trim trail equipment by Jupiter Play or similar and approved
- Margin retained and maintained by Management Company [1m along main road]
- Extended 1m depth excavation to form tree pit + root barrier adjacent to highway
- Root barrier to be supplied by Urban Green Blue or similar and approved
- Indicative drainage easement related to proposed drainage tank. Specified by engineers
- Zone allowed for timber crib wall
- +000.00 Indicative proposed levels TBC

Planting notes refer to sheet 2



Revisions:

Rev	Date	By	Note
G	23.08.23	KA	Minor amendments
F	20.06.23	KA	Minor amendments
E	13.06.23	KA	Layout updates
D	16.05.23	KA	Minor amendments
C	07.03.23	KA	Minor amendments
B	06.03.23	KA	Minor amendments
A	03.03.23	KA	Minor amendments

Detailed Landscape Proposal
Sheet 1 of 2
 Land at Wesley Avenue, Netherthong

Client: Heywood Developments
 DRWG No: P22-2837_EN_0002_01 REV: G
 Drawn by: KG
 Date: 27/02/23
 Scale: 1:200 @ A1

Approved by: KC
PEGASUS GROUP

© Pegasus Planning Group Limited. © Crown copyright and database rights OS 100042093. Promap. Licence number 100020449. EmagSite. Licence number 0100031673. Terms & Conditions @ pegasusgroup.co.uk