

The canopy would be of stainless steel construction manufactured to DW172 specification, consisting of: 12 No 500 x 500 stainless steel baffle type grease filters & 6 No grease clean out drawers.

The extract system would consist of an ESP7500 unit & 10 No tri carb panels housed in a purpose made box

This system would remove the odours & grease from the proposed cooking equipment to be used

We have proposed a MUBT500 fan to be fitted as this is an insulated acoustic fan, as such it is one of the quietest fans on the market

The proposed extract system would all be housed internal to the building reducing any disturbance noise to the surrounding area

Nick Booth

Catering Equipment and Hospitality Specialists

walfonsandcompany.com

T: 01274 686 186

E: nick@walfonsandcompany.com

1 Merrydale Road, Euroway Trading Estate,
Bradford BD4 6SD

Let's Be Social