

Should groundwater be encountered within the temporary works, a land drain should be installed and connected into the land drainage system. The known spring to the front of plot 37 is to be investigated further and diverted through the land drainage system on site.

Engineer from HHA to inspect temporary works at regular intervals. Should instability be encountered excavation to cease and engineer from HHA to be contacted immediately.



PROPOSED GROUND LEVEL	198.811	198.867	195.867	192.683	190.976	189.694	189.239
EXISTING GROUND LEVEL	198.788	198.867	195.867	192.683	190.976	189.694	189.239
CHAINAGE	0.000	10.000	20.000	30.000	40.000	42.944	

