

Should groundwater be encountered within the temporary works, a land drain should be installed and connected into the land drainage system. The known spring to the front of plot 37 is to be investigated further and diverted through the land drainage system on site.

Engineer from HHA to inspect temporary works at regular intervals. Should instability be encountered excavation to cease and engineer from HHA to be contacted immediately.



PROPOSED GROUND LEVEL	194.863	194.913	193.730	193.300	190.600	190.600	187.900	187.579	
EXISTING GROUND LEVEL	194.950		191.894		188.923		186.598		185.078
CHAINAGE	0.000		10.000		20.000		30.000		40.000

