

## The Biodiversity Metric 4.0 -Technical Annex 1: Condition Assessment Sheets and Methodology

March 2023

Natural England Joint Publication JP039

ISBN 978-1-7393362-2-6

### Instructions

The method for assessing habitat condition is split into three main steps, all of which are outlined in detail below:

**STEP 1: Considerations before assessing condition**

**STEP 2: Choosing the right condition sheet**

**STEP 3: Using condition sheets**

#### Step 1: Considerations before assessing condition

The following points must be considered **before** undertaking a condition assessment:

- Condition assessments must be undertaken by a competent person, as defined in the Biodiversity Metric 4.0 User Guide.
- Assessors must have access to condition sheets (see **Tabs 1-25**) and the survey cover sheet during the survey (see **SURVEY COVER SHEET** tab). These may be either digital or hard copies.
- The habitat type of the parcel(s) to be assessed must be determined before consideration can be given to its condition as this enables the assessor to select the correct condition sheet (see **HABITAT DEFINITIONS** tab). Most (but not all) metric terrestrial habitat types are equivalent to Level 4 in UKHab, therefore some metric habitats encompass UKHab Level 5 sub-divisions. When classifying a habitat, the assessor should classify and record it to the most accurate and appropriate level. Although a Level 5, or equivalent habitat may need converting to a metric habitat type when using the metric, when assessing
- The location and extent of the habitat parcel(s) to be assessed must be mapped, either on digital or paper maps. Following condition assessment, mapped habitat parcels should be split according to their condition.
- Each habitat parcel to be assessed must be assigned a unique reference ID.

#### Step 2: Choosing the right condition sheet

See **SELECTING CONDITION SHEET** tab which lists the habitat types found in the metric and indicates which condition sheet should be used for each habitat type. Some condition sheets are unique to a single habitat type; others cover a range of habitat types within the same broad habitat category.

**How to use:** locate the relevant habitat type in the first column (Habitat Type), then refer to the second column (Condition Sheet) to determine which habitat condition sheet should be used to assess that particular habitat type. The third and fourth columns (Link to sheet) contain links which can be clicked on to navigate directly to the required condition sheet, for ease of

- Some habitats are allocated a fixed condition score in the metric and do not require a condition assessment for the metric to be completed. For certain low and medium distinctiveness habitats there is a fixed option in the metric - '*Condition*'
- Habitats descriptions in **bold** are Priority Habitats.

#### Step 3: Using condition sheets (Tabs 1-25)

The following instructions and points of clarification apply to most condition assessment sheets:

- Only choose one condition sheet per habitat type. Once the condition sheet has been chosen, the condition assessment can be carried out on relevant sheets A or B, which are the same except that for A - information for one habitat parcel can be recorded, whereas for B - information for up to 10 habitat parcels can be recorded. Each condition sheet is set to print at A4 and can be used as a paper form.
- Assess the habitat parcel against each condition assessment criterion, recording a 'pass' or 'fail' for each criterion assessed, unless otherwise directed by categories available on the sheet.
- If a habitat parcel is failing all criteria, it may be that the habitat type has been recorded incorrectly and the wrong condition sheet is being used. Assessors should refer to the habitat description links at the top of the condition sheet to ensure that the habitat type is correctly identified.
- If condition varies within a parcel during the assessment then start a new condition assessment. Split the original parcel to ensure that each individual parcel comprises an area of habitat of a consistent type and condition.
- Some condition assessment sheets have 'essential' criteria. Essential criteria must be passed to achieve a particular condition state.
- Some condition assessment sheets list species that are indicative of sub-optimal condition status. These lists are not exhaustive. An assessor may exercise professional judgement and consider additional species within this category, such as [GB non-native species secretariat](#)
- Any relevant evidence for passing or failing criteria, or for a particular score, should be captured within the habitat survey target notes and or by taking photographs. Photographs and target notes should be referenced on the condition sheet.

- h) Record any survey limitations on the condition sheet, such as access restrictions or timing restrictions. If survey limitations prevent any criteria from being confidently and accurately assessed, adopt a precautionary approach when passing or failing
- i. If a definitive pass or fail cannot be assigned through baseline survey, assume the criterion is passed.
  - ii. When monitoring post-intervention habitat, fail criteria which cannot be assessed due to survey limitations.

- i) Once all applicable condition criteria have been assessed, assign a result of Good, Moderate or Poor condition following
- i. The 'Fairly Good' or 'Fairly Poor' condition categories are intermediate categories for site-specific features of condition not captured in the standard condition assessment. They should only be applied through application of professional judgement, and sound ecological evidence must be provided to justify the use of these categories. If used, these categories can only be used to adjust the results of a standard metric condition assessment one condition category above or below its result. For example, you cannot go from a standard outcome of 'Poor' to an adjustment to 'Fairly Good' (nor from 'Good' to

The condition assessment survey is a good opportunity to identify any potential opportunities for habitat restoration or enhancement. Note potential opportunities for these within the condition sheet.

The **CA SUMMARY SHEET** can be filled out after the survey to summarise information about the condition assessments, including:

- The site or location of the condition assessment survey
- The number of condition sheets used

### **Notes on Using Condition Sheets**

Additional habitat-specific instructions for non-standard condition assessment sheets are provided below:

#### Using the 'Woodland' condition sheet

The Woodland condition sheet has been adapted from the 'Woodland Condition Survey' developed by the England Woodland Biodiversity Group (EWBG). All supplementary information needed to complete a Woodland condition assessment for the purpose of the metric is provided within the Woodland condition sheet.

Instead of allocating a pass or fail to each criterion, each of the criteria within the woodland condition sheets are allocated a score. These scores are summed, and the total sum is used to assign a final condition score.

#### Using the 'Lakes' condition sheet

The Freshwater Biological Association's 'Habitat Naturalness Assessment' (HNA) is used to assess the condition of a lake. All supplementary information needed to complete a HNA is provided within the Lake condition sheet.

The average of the HNA scores is used to assign a final condition score.

#### Using the 'Coastal' and 'Intertidal' habitat condition sheets

For most coastal and intertidal habitats, instead of allocating a 'pass' or 'fail' to each criterion, each of the criteria within the condition sheets are allocated a score. These scores are summed, and the total sum is used to assign a final condition score.

#### Using the 'Hedgerow' condition sheet

The condition sheet for hedgerows has been adapted from the Defra Hedgerow Survey Handbook. All supplementary information needed to complete a hedgerow condition assessment is provided within the Hedgerow condition sheet.

Each condition criterion is assigned to one of five functional groups. The condition of a hedgerow is assessed according to the number of criteria passed within these functional groups.

Biodiversity Metric 4.0 broad habitat	Biodiversity Metric 4.0 habitat	Classification where definition derived	Habitat name in source classification	Other definition or notes	
Cropland	<i>Arable field margins cultivated annually</i>	UKHab	Arable field margins cultivated annually with an annual flora	The metric habitat type differs from the UKHab name.	
	<i>Arable field margins game bird mix</i>	UKHab	Game bird mix strips and corners; Game bird mix fields	The metric habitat type differs from the UKHab name.	
	Arable field margins pollen and nectar	UKHab	Arable field margins pollen and nectar		
	<i>Arable field margins tussocky</i>	UKHab	Arable field margins sown with tussocky grasses	The metric habitat type differs from the UKHab name.	
	Cereal crops	UKHab	Cereal crops		
	Winter stubble	UKHab	Winter stubble		
	Horticulture	UKHab	Horticulture		
	Intensive orchards	UKHab	Intensive orchards		
	Non-cereal crops	UKHab	Non-cereal crops		
	Temporary grass and clover leys	UKHab	Temporary grass and clover leys		
Grassland	Traditional orchards	UKHab	Traditional orchards		
	Bracken	UKHab	Bracken		
	<b>Floodplain wetland mosaic and CFGM</b>	Floodplain Wetland Mosaic: Metric-specific, see notes	N/A		See User Guide.
		CFGM - Definition based on Priority Habitat Inventory maps	CFGM - Coastal and floodplain grazing marsh		N/A
	Lowland calcareous grassland	UKHab	Lowland calcareous grassland		
	Lowland dry acid grassland	UKHab	Lowland dry acid grassland		
	Lowland meadows	UKHab	Lowland meadows		
	Modified grassland	UKHab	Modified grassland		
	Other lowland acid grassland	UKHab	Other lowland acid grassland		
Other neutral grassland	UKHab	Other neutral grassland			

Biodiversity Metric 4.0 broad habitat	Biodiversity Metric 4.0 habitat	Classification where definition derived	Habitat name in source classification	Other definition or notes
	Tall herb communities (H6430)	Use Habitats Directive Annex 1 definition	Tall herb communities (H6430)	All Tall herb not meeting this definition should be recorded as Other neutral grassland with the relevant secondary code according to UKHab.
	Upland acid grassland	UKHab	Upland acid grassland	
	Upland calcareous grassland	UKHab	Upland calcareous grassland	
	Upland hay meadows	UKHab	Upland hay meadows	
Heathland and shrub	Blackthorn scrub	UKHab	Blackthorn scrub	
	Bramble scrub	UKHab	Bramble scrub	
	Gorse scrub	UKHab	Gorse scrub	
	Hawthorn scrub	UKHab	Hawthorn scrub	
	Hazel scrub	UKHab	Hazel scrub	
	Lowland heathland	UKHab	Lowland heathland	
	Mixed scrub	UKHab	Mixed scrub	
	Mountain heaths and willow scrub	UKHab	Mountain heaths and willow scrub	
	Rhododendron scrub	UKHab	Rhododendron scrub	
	Willow scrub	UKHab	Willow scrub	
	Dunes with sea buckthorn (H2160)	Habitats Directive Annex 1	Dunes with sea buckthorn (H2160)	All other sea buckthorn scrub should be recorded as 'Other sea buckthorn scrub'
	Other sea buckthorn scrub	UKHab	Other sea buckthorn scrub	
Upland heathland	UKHab	Upland heathland		
Individual tree	<b>Rural tree</b>	Metric-specific – see User Guide	N/A	See User Guide
	<b>Urban tree</b>	Metric-specific – see User Guide	N/A	See User Guide
Lakes	Aquifer fed naturally fluctuating water bodies	UKHab	Aquifer fed naturally fluctuating water bodies	
	<i>Ornamental lake or pond</i>	UKHab	Artificial lake or pond	The metric habitat type differs from the UKHab name. ≤ 2ha

Biodiversity Metric 4.0 broad habitat	Biodiversity Metric 4.0 habitat	Classification where definition derived	Habitat name in source classification	Other definition or notes
	High alkalinity lakes	Water Framework Directive (WFD) Lakes typology	N/A	≥ 2ha
	Low alkalinity lakes	WFD Lakes typology	N/A	≥ 2ha
	Marl lakes	WFD Lakes typology	N/A	≥ 2ha
	Moderate alkalinity lakes	WFD Lakes typology	N/A	≥ 2ha
	Peat lakes	WFD Lakes typology	N/A	≥ 2ha
	Ponds (priority habitat)	UKHab	Ponds (priority habitat)	≤ 2ha
	<b>Ponds (non-priority habitat)</b>	UKHab*	N/A	*Ponds which do not meet either the definition of (i) priority habitat ponds or (ii) ornamental ponds.
	Reservoirs	UKHab/WFD Lakes typology*	Reservoir	*Some larger reservoirs are covered by the WFD Lakes typology.
	<i>Temporary lakes ponds and pools (H3170)</i>	UKHab*	Mediterranean temporary ponds (H3170)	The metric habitat type differs from the UKHab name. *All temporary water bodies not meeting this definition should be recorded as the appropriate pond or lake habitat type.
Sparsely vegetated land	Calaminarian grasslands	UKHab	Calaminarian grasslands	
	Coastal sand dunes	UKHab	Coastal sand dunes	
	Coastal vegetated shingle	UKHab	Coastal vegetated shingle	
	Ruderal/Ephemeral	UKHab	Ruderal/ Ephemeral	
	Tall forbs	UKHab	Tall forbs	
	Inland rock outcrop and scree habitats	UKHab	Inland rock outcrop and scree habitats	
	Limestone pavement	UKHab	Limestone pavement	
	Maritime cliff and slopes	UKHab	Maritime cliff and slopes	
	Other inland rock and scree	UKHab	Other inland rock and scree	

Biodiversity Metric 4.0 broad habitat	Biodiversity Metric 4.0 habitat	Classification where definition derived	Habitat name in source classification	Other definition or notes
Urban	Allotments	UKHab	Allotments	
	Artificial unvegetated, unsealed surface	UKHab	Artificial unvegetated, unsealed surface	
	Bioswale	UKHab	Bioswale	
	Biodiverse green roof	UKHab	Biodiverse green roof	
	Built linear features	UKHab	Built linear features	
	<i>Cemeteries and churchyards</i>	UKHab	Cemetery	
	Developed land; sealed surface	UKHab	Developed land; sealed surface	
	Extensive green roof	UKHab	Extensive green roof	
	Facade-bound green wall	UKHab	Facade-bound green wall	
	Ground based green wall	UKHab	Ground based green wall	
	Ground level planters	UKHab	Ground level planters	
	Intensive green roof	UKHab	Intensive green roof	
	Introduced shrub	UKHab	Introduced shrub	
	Open mosaic habitats on previously developed land	UKHab	Open mosaic habitats on previously developed land	
	Other green roof	UKHab	Other green roof	
	Rain garden	UKHab	Rain garden	
	<i>Actively worked sand pit quarry or open cast mine</i>	UKHab	Sand pit quarry or open cast mine	The metric habitat type differs from the UKHab name.  This classification relates to non-vegetated working areas only.
	Sustainable drainage system (SuDS)	UKHab*	Sustainable urban drainage feature	* In the metric, this should only be used for open SuDS with vegetation and/or open water.
	Unvegetated garden	UKHab	Unvegetated garden	The metric habitat type differs from the UKHab name.
	Vacant or derelict land	UKHab	Vacant or derelict land	
Bare ground	UKHab	Bare ground		
Vegetated garden	UKHab	Vegetated garden	The metric habitat type differs from the UKHab name.	

Biodiversity Metric 4.0 broad habitat	Biodiversity Metric 4.0 habitat	Classification where definition derived	Habitat name in source classification	Other definition or notes
Wetland	Blanket bog	UKHab	Blanket bog	
	Depressions on peat substrates (H7150)	UKHab	Depressions on peat substrates (H7150)	
	<i>Fens (upland and lowland)</i>	UKHab	Lowland fens; Upland flushes fens and swamps; Other swamps	The metric habitat type differs from the UKHab name.
	Lowland raised bog	UKHab	Lowland raised bog	
	<i>Wetland – Oceanic valley mire [1] (D2.1)</i>	EUNIS	Oceanic valley bog	The metric habitat type differs from the UKHab name.
	Purple moor grass and rush pastures	UKHab	Purple moor grass and rush pastures	
	Reedbeds	UKHab	Reedbeds	
	<i>Transition mires and quaking bogs (H7140)</i>	UKHab	Transition mires and quaking bogs; lowland (H7140)	The metric habitat type differs from the UKHab name.
Woodland and forest	Felled	UKHab	Felled	See User Guide
	Lowland beech and yew woodland	UKHab	Lowland beech and yew woodland	
	Lowland mixed deciduous woodland	UKHab	Lowland mixed deciduous woodland	
	Native pine woodlands	UKHab	Native pine woodlands	
	Other coniferous woodland	UKHab	Other coniferous woodland	
	Other Scot's pine woodland	UKHab	Other Scot's pine woodland	
	Other woodland; broadleaved	UKHab	Other woodland; broadleaved	
	Other woodland; mixed	UKHab	Other woodland; mixed	
	Upland birchwoods	UKHab	Upland birchwoods	
	Upland mixed ashwoods	UKHab	Upland mixed ashwoods	
	Upland oakwood	UKHab	Upland oakwood	
	Wet woodland	UKHab	Wet woodland	
	Wood-pasture and parkland	UKHab	Wood-pasture and parkland	
	Coastal lagoons	<i>Coastal lagoons</i>	EUNIS	Saline coastal lagoons
Coastal saltmarsh	<i>Saltmarshes and saline reedbeds</i>	EUNIS	Coastal saltmarshes and saline reedbeds	
	<i>Artificial saltmarshes and saline reedbeds</i>	Adapted from EUNIS		
Rocky shore	High energy littoral rock	EUNIS	High energy littoral rock	

Biodiversity Metric 4.0 broad habitat	Biodiversity Metric 4.0 habitat	Classification where definition derived	Habitat name in source classification	Other definition or notes
	<i>High energy littoral rock - on peat, clay or chalk</i>	Subset of EUNIS habitat based on substrate	High energy littoral rock	
	Moderate energy littoral rock	EUNIS	Moderate energy littoral rock	
	<i>Moderate energy littoral rock - on peat, clay or chalk</i>	Subset of EUNIS habitat based on substrate	Moderate energy littoral rock	
	Low energy littoral rock	EUNIS	Low energy littoral rock	
	<i>Low energy littoral rock - on peat, clay or chalk</i>	Subset of EUNIS habitat based on substrate	Low energy littoral rock	
	Features of littoral rock	EUNIS	Features of littoral rock	
	<i>Features of littoral rock - on peat, clay or chalk</i>	Subset of EUNIS habitat based on substrate	Features of littoral rock	
Intertidal sediment	Littoral coarse sediment	EUNIS	Littoral coarse sediment	
	<i>Littoral sand</i>	EUNIS	Littoral sand and muddy sand	
	<i>Littoral muddy sand</i>	EUNIS	Littoral sand and muddy sand	
	Littoral mud	EUNIS	Littoral mud	
	Littoral mixed sediments	EUNIS	Littoral mixed sediments	
	<i>Littoral seagrass</i>	EUNIS	Littoral sediments dominated by aquatic angiosperms	
	<i>Littoral seagrass on peat, clay or chalk</i>	Subset of EUNIS habitat based on substrate	Littoral sediments dominated by aquatic angiosperms	
	<i>Littoral biogenic reefs - Mussels</i>	Subset of EUNIS habitat based on reef forming species	Littoral biogenic reefs	
	<i>Littoral biogenic reefs - Sabellaria</i>	Subset of EUNIS habitat based on reef forming species	Littoral biogenic reefs	
	Features of littoral sediment	EUNIS	Features of littoral sediment	

<b>Biodiversity Metric 4.0 broad habitat</b>	<b>Biodiversity Metric 4.0 habitat</b>	<b>Classification where definition derived</b>	<b>Habitat name in source classification</b>	<b>Other definition or notes</b>
	<i>Artificial littoral coarse sediment</i>	Adapted from EUNIS - see Technical Annex 2		
	<i>Artificial littoral muddy sand</i>	Adapted from EUNIS - see Technical Annex 2		
	<i>Artificial littoral mud</i>	Adapted from EUNIS - see Technical Annex 2		
	<i>Artificial littoral sand</i>	Adapted from EUNIS - see Technical Annex 2		
	<i>Artificial littoral mixed sediments</i>	Adapted from EUNIS - see Technical Annex 2		
	<i>Artificial littoral seagrass</i>	Adapted from EUNIS - see Technical Annex 2		
	<i>Artificial littoral biogenic reefs</i>	Adapted from EUNIS - see Technical Annex 2		
Intertidal Hard Structures	<i>Artificial hard structures</i>	Adapted from EUNIS - see Technical Annex 2		
	<i>Artificial features of hard structures</i>	Adapted from EUNIS - see Technical Annex 2		
	<i>Artificial hard structures with integrated greening of grey infrastructure (IGGI)</i>	Adapted from EUNIS - see Technical Annex 2		
Hedgerows and Lines of trees	<i>Species-rich native hedgerow with trees - associated with bank or ditch</i>	UKHab	Species-rich native hedgerow	The definition does not match exactly as UKHab uses additional secondary codes.
	<i>Species-rich native hedgerow with trees</i>	UKHab	Species-rich native hedgerow	The definition does not match exactly as UKHab uses additional secondary codes.
	<i>Species-rich native hedgerow - associated with bank or ditch</i>	UKHab	Species-rich native hedgerow	The definition does not match exactly as UKHab uses additional secondary codes.

Biodiversity Metric 4.0 broad habitat	Biodiversity Metric 4.0 habitat	Classification where definition derived	Habitat name in source classification	Other definition or notes
	<i>Native hedgerow with trees - associated with bank or ditch</i>	UKHab	Native hedgerow	The definition does not match exactly as UKHab uses additional secondary codes.
	Species-rich native hedgerow	UKHab	Species-rich native hedgerow	
	<i>Native hedgerow - associated with bank or ditch</i>	UKHab	Native hedgerow	The definition does not match exactly as UKHab uses additional secondary codes.
	<i>Native hedgerow with trees</i>	UKHab	Native hedgerow	The definition does not match exactly as UKHab uses additional secondary codes.
	Ecologically valuable line of trees	UKHab	Ecologically valuable line of trees	
	<i>Ecologically valuable line of trees - associated with bank or ditch</i>	UKHab	Ecologically valuable line of trees	The definition does not match exactly as UKHab uses additional secondary codes.
	Native hedgerow	UKHab	Native hedgerow	
	Line of trees	UKHab	Line of trees	
	<i>Line of trees - associated with bank or ditch</i>	UKHab	Line of trees	The definition does not match exactly as UKHab uses additional secondary codes.
	Non-native and ornamental hedgerow	UKHab	Non-native and ornamental hedgerow	
Watercourse	Priority habitat	UKHab	Rivers (priority habitat)	Highly naturally functioning stretches of rivers identified on the Priority River Habitat Map, and un-mapped stretches meeting the criteria for inclusion into the Priority River Habitat Map.
	Other rivers and streams	UKHab	Other rivers and streams	Rivers and streams that are not classified as Priority River Habitat
	<b>Ditches</b>	UKHab	Ditch	Artificially created linear water-conveyancing features which are less than 5m wide, and likely to retain water for more than 4 months of the year

Biodiversity Metric 4.0 broad habitat	Biodiversity Metric 4.0 habitat	Classification where definition derived	Habitat name in source classification	Other definition or notes
	Canals	UKHab	Canals	An artificial body of water originally created for the purposes of navigation, whether it is currently navigable or not.
	<b>Culvert</b>	N/A	N/A	As defined by the Flood and Water Management Act 2010. A covered channel or pipe designed to prevent the obstruction of a watercourse or drainage path by an artificial construction.

Habitat Type (Habitats in bold are Priority Habitats)	Condition Sheet
<b>Area habitats</b>	
Broad habitat type: Cropland	
Cropland - Arable field margins cultivated annually	Condition Assessment N/A
Cropland - Arable field margins game bird mix	
Cropland - Arable field margins pollen and nectar	
Cropland - Arable field margins tussocky	
Cropland - Cereal crops	
Cropland - Winter stubble	
Cropland - Horticulture	
Cropland - Intensive orchards	
Cropland - Non-cereal crops	
Cropland - Temporary grass and clover leys	
Broad habitat type: Grassland	
Grassland - Bracken	Condition Assessment N/A
<b>Grassland - Floodplain wetland mosaic and CFGM</b>	Use Wetland condition sheet (plus Ditch condition sheet for any ditches). If the area meets the definition of another high / very high distinctiveness type, record and treat as the relevant habitat type within the metric instead.
<b>Grassland - Lowland calcareous grassland</b>	Grassland Medium/High/Very High distinctiveness
<b>Grassland - Lowland dry acid grassland</b>	
<b>Grassland - Lowland meadows</b>	
Grassland - Modified grassland	Grassland Low distinctiveness
Grassland - Other lowland acid grassland	Grassland Medium/High/Very High distinctiveness
Grassland - Other neutral grassland	
<b>Grassland - Tall herb communities (H6430)</b>	
<b>Grassland - Traditional orchards</b>	Orchard
Grassland - Upland acid grassland	Grassland Medium/High/Very High distinctiveness
<b>Grassland - Upland calcareous grassland</b>	
<b>Grassland - Upland hay meadows</b>	
Broad habitat type: Heathland and scrub	
Heathland and shrub - Blackthorn scrub	Scrub
Heathland and shrub - Bramble scrub	Condition Assessment N/A
Heathland and shrub - Gorse scrub	Scrub
Heathland and shrub - Hawthorn scrub	
Heathland and shrub - Hazel scrub	
<b>Heathland and shrub - Lowland heathland</b>	
Heathland and shrub - Mixed scrub	Scrub
<b>Heathland and shrub - Mountain heaths and willow scrub</b>	Use Heathland condition sheet for Mountain heaths OR Scrub condition sheet for Willow scrub
Heathland and shrub - Rhododendron scrub	Condition Assessment N/A
<b>Heathland and shrub - Dunes with sea buckthorn (H2160)</b>	Scrub
Heathland and shrub - Other sea buckthorn scrub	Condition Assessment N/A
<b>Heathland and shrub - Upland heathland</b>	Heathland
Heathland and shrub - Willow scrub	Scrub
Broad habitat type: Lakes	
<b>Lakes - Aquifer fed naturally fluctuating water bodies</b>	Lakes
<b>Lakes - High alkalinity lakes</b>	
<b>Lakes - Low alkalinity lakes</b>	
<b>Lakes - Marl lakes</b>	
<b>Lakes - Moderate alkalinity lakes</b>	
<b>Lakes - Ornamental lake or pond</b>	Lakes OR Ponds
<b>Lakes - Peat lakes</b>	Lakes
<b>Lakes - Ponds (priority habitat)</b>	Ponds
Lakes - Ponds (non-priority habitat)	
Lakes - Reservoirs	Lakes
<b>Lakes - Temporary lakes ponds and pools (H3170)</b>	Use Lake condition sheet for Temporary lakes OR

Habitat Type (Habitats in bold are Priority Habitats)	Condition Sheet
<b>Lakes - Temporary lakes ponds and pools (H6116)</b>	Pond condition sheet for Temporary ponds and pools
Broad habitat type: Sparsely vegetated land	
<b>Sparsely vegetated land - Calaminarian grasslands</b>	Grassland Medium/High/Very High distinctiveness
<b>Sparsely vegetated land - Coastal sand dunes</b>	Coastal
<b>Sparsely vegetated land - Coastal vegetated shingle</b>	
Sparsely vegetated land - Ruderal/Ephemeral	Urban
Sparsely vegetated land - Tall forbs	
<b>Sparsely vegetated land - Inland rock outcrop and scree habitats</b>	Sparsely vegetated land
<b>Sparsely vegetated land - Limestone pavement</b>	Limestone pavement
<b>Sparsely vegetated land - Maritime cliff and slopes</b>	Coastal
Sparsely vegetated land - Other inland rock and scree	Sparsely vegetated land
Broad habitat type: Urban	
Urban - Allotments	Urban
Urban - Artificial unvegetated, unsealed surface	N/A - Other
Urban - Bioswale	Urban
Urban - Biodiverse green roof	
Urban - Built linear features	N/A - Other
Urban - Cemeteries and churchyards	Use Urban condition sheet as default.
Urban - Developed land; sealed surface	N/A - Other
Urban - Facade-bound green wall	Urban
Urban - Ground based green wall	
Urban - Ground level planters	Condition Assessment N/A
Urban - Intensive green roof	Urban
Urban - Introduced shrub	Condition Assessment N/A
<b>Urban - Open mosaic habitats on previously developed land</b>	Urban
Urban - Other green roof	Condition Assessment N/A
Urban - Rain garden	Urban
Urban - Actively worked sand pit, quarry or open cast mine	Condition Assessment N/A
Urban - Sustainable drainage system (SuDS)	Urban
Urban - Unvegetated garden	N/A - Other
Urban - Vacant or derelict land	Urban
Urban - Bare ground	
Urban - Vegetated garden	Condition Assessment N/A
Broad habitat type: Wetland	
<b>Wetland - Blanket bog</b>	Wetland
<b>Wetland - Depressions on peat substrates (H7150)</b>	
<b>Wetland - Fens (upland and lowland)</b>	
<b>Wetland - Lowland raised bog</b>	
<b>Wetland - Oceanic valley mire [1] (D2.1)</b>	
<b>Wetland - Purple moor grass and rush pastures</b>	
<b>Wetland - Reedbeds</b>	
<b>Wetland - Transition mires and quaking bogs (H7140)</b>	
Broad habitat type: Woodland	
<b>Woodland and forest - Felled</b>	No assessment required - condition fixed at Good
<b>Woodland and forest - Lowland beech and yew woodland</b>	Woodland
<b>Woodland and forest - Lowland mixed deciduous woodland</b>	
<b>Woodland and forest - Native pine woodlands</b>	
Woodland and forest - Other coniferous woodland	
Woodland and forest - Other Scot's pine woodland	
Woodland and forest - Other woodland; broadleaved	
Woodland and forest - Other woodland; mixed	
<b>Woodland and forest - Upland birchwoods</b>	
<b>Woodland and forest - Upland mixed ashwoods</b>	
<b>Woodland and forest - Upland oakwood</b>	
<b>Woodland and forest - Wet woodland</b>	
<b>Woodland and forest - Wood-pasture and parkland</b>	Wood-pasture and parkland

Habitat Type (Habitats in bold are Priority Habitats)	Condition Sheet
Broad habitat type: Coastal lagoons	
<b>Coastal lagoons - Coastal lagoons</b>	Coastal lagoons
Broad habitat type: Coastal saltmarsh	
<b>Coastal saltmarsh - Saltmarshes and saline reedbeds</b>	Coastal saltmarsh
<b>Coastal saltmarsh - Artificial saltmarshes and saline reedbeds</b>	
Broad habitat type: Intertidal hard structures	
<b>Intertidal hard structures - Artificial hard structures</b>	Intertidal hard structures
<b>Intertidal hard structures - Artificial features of hard structures</b>	
<b>Intertidal hard structures - Artificial hard structures with integrated greening of grey infrastructure (IGGI)</b>	
Broad habitat type: Intertidal sediment	
<b>Intertidal sediment - Littoral coarse sediment</b>	Intertidal sediment
<b>Intertidal sediment - Littoral sand</b>	
<b>Intertidal sediment - Littoral muddy sand</b>	
<b>Intertidal sediment - Littoral mud</b>	
<b>Intertidal sediment - Littoral mixed sediments</b>	
<b>Intertidal sediment - Features of littoral sediment</b>	
<b>Intertidal sediment - Artificial littoral coarse sediment</b>	
<b>Intertidal sediment - Artificial littoral mixed sediments</b>	
<b>Intertidal sediment - Artificial littoral mud</b>	
<b>Intertidal sediment - Artificial littoral muddy sand</b>	
<b>Intertidal sediment - Artificial littoral sand</b>	
<b>Intertidal sediment - Littoral seagrass</b>	Intertidal seagrass
<b>Intertidal sediment - Littoral seagrass - on peat, clay or chalk</b>	
<b>Intertidal sediment - Artificial littoral seagrass</b>	
<b>Intertidal sediment - Littoral biogenic reefs - Mussels</b>	Intertidal biogenic reefs
<b>Intertidal sediment - Littoral biogenic reefs – Sabellaria</b>	
<b>Intertidal sediment - Artificial littoral biogenic reefs</b>	
Broad habitat type: Rocky shore	
<b>Rocky shore - High energy littoral rock</b>	Rocky shore
<b>Rocky shore - Moderate energy littoral rock</b>	
<b>Rocky shore - Low energy littoral rock</b>	
<b>Rocky shore - Features of littoral rock</b>	
<b>Rocky Shore - Features of littoral rock - on peat, clay or chalk</b>	
<b>Rocky shore - High energy littoral rock - on peat, clay or chalk</b>	
<b>Rocky shore - Moderate energy littoral rock - on peat, clay or chalk</b>	
<b>Rocky shore - Low energy littoral rock - on peat, clay or chalk</b>	
<b>Hedgerows and lines of trees habitats</b>	
Broad habitat type: Individual trees	
<b>Individual trees – Rural tree</b>	Individual trees
<b>Individual trees – Urban tree</b>	
Broad habitat type: Hedgerows and lines of trees	
<b>Hedgerows and lines of trees - Line of trees</b>	Line of trees
<b>Hedgerows and lines of trees - Line of trees - associated with bank or ditch</b>	
<b>Hedgerows and lines of trees – Ecologically valuable line of trees</b>	
<b>Hedgerows and lines of trees - Ecologically valuable line of trees - associated with bank or ditch</b>	
<b>Hedgerows and lines of trees – Non-native and ornamental hedgerow</b>	No assessment required - condition fixed at Poor

Habitat Type (Habitats in bold are Priority Habitats)	Condition Sheet
<b>Hedgerows and lines of trees - Native hedgerow</b>	
<b>Hedgerows and lines of trees - Native hedgerow - associated with bank or ditch</b>	
<b>Hedgerows and lines of trees - Native hedgerow with trees</b>	
<b>Hedgerows and lines of trees - Native hedgerow with trees - associated with bank or ditch</b>	

Hedgerow

<b>Survey Cover Sheet</b>			
<b>Date</b>		<b>Site name or location</b>	
<b>Weather conditions</b>		<b>Project or development name</b>	
<b>Surveyor name</b>		<b>On-site or off-site</b>	
<b>Survey reference</b>		<b>Reason for assessment (if not baseline condition survey)</b>	
<b>Notes</b>			

Site or location	Condition sheets	Total number of condition sheets used, or habitat parcels	Number of parcels of each condition achieved				
			Good	Fairly Good	Moderate	Fairly Poor	Poor
	Coastal						
	Coastal lagoons						
	Coastal saltmarsh						
	Ditches						
	Grassland low distinctiveness						
	Grassland medium, high, very high distinctiveness						
	Heathland						
	Hedgerow						
	Individual trees						
	Intertidal biogenic reefs						
	Intertidal hard structures						
	Intertidal seagrass						
	Intertidal sediment						

	<b>Lakes</b>						
	<b>Limestone pavement</b>						
	<b>Line of trees</b>						
	<b>Orchard</b>						
	<b>Ponds</b>						
	<b>Rocky shore</b>						
	<b>Scrub</b>						
	<b>Sparsely vegetated land</b>						
	<b>Urban</b>						
	<b>Wetland</b>						
	<b>Woodland</b>						
	<b>Wood-pasture and parkland</b>						

Notes



**Condition Sheet: COASTAL Habitat Type**

**UK Habitat Classification (UKHab) Habitat Type(s)**

**Sparingly vegetated land - Coastal sand dunes  
Sparingly vegetated land - Coastal vegetated shingle  
Sparingly vegetated land - Maritime cliff and slopes**

**Habitat Description**

[See UKHab](#)

Site name and location		On-site or off-site	
Limitations (if applicable)		Survey reference (if relating to a wider survey)	
Grid reference		Habitat parcel reference	
Condition Assessment Criteria		Criterion passed (Yes or No)	Notes (such as justification)
A	<p>The habitat is a good representation of the habitat type it has been identified as: the vegetation composition is formed of native species typical of the relevant habitat and present in the typical successional stages, transitions and or mosaics, at sufficient cover and frequency to be a good example of the relevant habitat.</p> <p><b>Note - this criterion is essential for achieving Good condition.</b></p>		
B	<p>Vegetation structure (sward height variation, zonation) is varied and not uniform.</p>		
C	<p>Naturally open ground or bare surfaces are present as part of a sequence of colonisation and succession.</p>		
D	<p>Coastal processes needed to support the habitat are functional and are not modified by hard engineering or other forms of negative intervention.</p>		
E	<p>The landform reflects the interaction of coastal processes and geology, and there is a varied topography present supporting the relevant range of habitat types.</p>		
F	<p>There is an absence of invasive non-native species<sup>1</sup> (as listed on Schedule 9 of WCA<sup>2</sup>). Combined cover of species indicative of sub-optimal condition<sup>3</sup> and physical damage (such as excessive poaching, damage from machinery use or storage, damaging levels of access, or any other damaging management activities) accounts for less than 5% of total area.</p>		

G	Some scattered scrub (including bramble <i>Rubus fruticosus</i> agg.) may be present, but scrub covers less than 10% of area within the habitat or bare substrate matrix. Blocks of scrub or woodland, which might be desirable in their own right should be classified and mapped separately.		
H	Water quality and quantity (for example, seasonal fluctuations in dune slacks or seepages on cliff slopes) is sufficient to support the range of water-dependent parts of the habitat.		
<b>Essential criterion achieved (Yes or No)</b>			
<b>Number of criteria passed</b>			
<b>Condition Assessment Result (out of 8 criteria)</b>	<b>Condition Assessment Score</b>	<b>Score Achieved x/√</b>	
Passes 7 or 8 criteria including essential criterion A	Good (3)		
Passes 5 or 6 criteria; OR Passes 7 criteria excluding essential criterion A	Moderate (2)		
Passes 4 or fewer criteria	Poor (1)		
<b>Suggested enhancement interventions to improve condition score</b>			
<b>Footnotes</b>			
<p><b>Footnote 1</b> – Assess this for each distinct habitat parcel. If the distribution of invasive non-native species varies across the habitat, split into parcels accordingly, applying a buffer zone around the invasive non-native species with a size relative to its risk of spread into adjacent habitat, using professional judgement.</p> <p><b>Footnote 2</b> – Wildlife and Countryside Act 1981 (as amended).</p> <p><b>Footnote 3</b> - <u>General coastal species indicative of sub-optimal condition</u>: creeping thistle <i>Cirsium arvense</i> , spear thistle <i>Cirsium vulgare</i> , curled dock <i>Rumex crispus</i> , broad-leaved dock <i>Rumex obtusifolius</i> , common nettle <i>Urtica dioica</i> , bramble, white willow <i>Salix alba</i> hybrids, and non-native garden plants.</p> <p><u>Grassland species indicative of sub-optimal condition</u>: creeping thistle <i>Cirsium arvense</i> , spear thistle <i>Cirsium vulgare</i> , curled dock <i>Rumex crispus</i> , broad-leaved dock <i>Rumex obtusifolius</i> , common nettle <i>Urtica dioica</i> , creeping buttercup <i>Ranunculus repens</i> , greater plantain <i>Plantago major</i> and cow parsley <i>Anthriscus sylvestris</i> .</p> <p><u>Heathland species indicative of sub-optimal condition</u>: bracken <i>Pteridium aquilinum</i> .</p> <p>There may be additional relevant species local to the region and or site.</p>			



**Suggested enhancement interventions to improve condition score**

**Notes**

**Footnote 1** – Assess this for each distinct habitat parcel. If the distribution of invasive non-native species varies across the habitat, split into parcels accordingly, applying a buffer zone around the invasive non-native species with a size relative to its risk of spread into adjacent habitat, using professional judgement.

**Footnote 2** – Wildlife and Countryside Act 1981 (as amended).

**Footnote 3** - General coastal species indicative of sub-optimal condition: creeping thistle *Cirsium arvense*, spear thistle *Cirsium vulgare*, curled dock *Rumex crispus*, broad-leaved dock *Rumex obtusifolius*, common nettle *Urtica dioica*, bramble, white willow *Salix alba* hybrids, and non-native garden plants.

Grassland species indicative of sub-optimal condition: creeping thistle *Cirsium arvense*, spear thistle *Cirsium vulgare*, curled dock *Rumex crispus*, broad-leaved dock *Rumex obtusifolius*, common nettle *Urtica dioica*, creeping buttercup *Ranunculus repens*, greater plantain *Plantago major* and cow parsley *Anthriscus sylvestris*.

Heathland species indicative of sub-optimal condition: bracken *Pteridium aquilinum*.

There may be additional relevant species local to the region and or site.

Condition Sheet: COASTAL LAGOONS Habitat Type					
EUNIS Habitat Type(s)					
Coastal lagoons					
<b>Site name and location</b>		<b>On-site or off-site</b>			
<b>Limitations (if applicable)</b>		<b>Survey reference (if relating to a wider survey)</b>			
<b>Grid reference</b>		<b>Habitat parcel reference</b>			
Habitat Description					
The coastal lagoons EUNIS habitat description is available here: <a href="https://eunis.europa.eu/en/factsheet/coastal-lagoons">EUNIS -Factsheet for Coastal lagoons (europa.eu)</a>					
Habitat Attributes to Record					
The following information should be recorded within the condition assessment sheet:					
<ul style="list-style-type: none"> <li>• Extent of lagoon waterbody<sup>1</sup>;</li> <li>• Description of presence of typical communities and biotopes;</li> <li>• Description of species diversity and community composition<sup>2</sup>;</li> <li>• Salinity in parts per thousand (ppt);</li> <li>• Presence and abundance of non-native species;</li> <li>• Observations on coastal process functioning and any human physical modifications present;</li> <li>• Percentage cover of algal growths that could be attributed to nutrient enrichment;</li> <li>• Presence and density of non-natural structures and direct human impacts;</li> <li>• Assessment of litter;</li> <li>• Visual record of water clarity;</li> <li>• Observations of the functioning and state of the isolating barrier; and</li> <li>• Observations of the functioning and state of the lagoon banks.</li> </ul>					
Condition Assessment Criteria					
Indicator	Good (3 points)	Moderate (2 points)	Poor (1 point)	Score per criterion	Notes (such as justification)
<b>A</b> <b>Presence and abundance of invasive non-native species</b>	Not more than one invasive non-native species is 'Occasional' on the SACFOR scale <sup>3</sup> ; or is occupying more than 1% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 4.	No invasive non-native species are present above 'Frequent' on the SACFOR scale <sup>3</sup> ; or they occupy between 1-10% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 4.	One or more invasive non-native species are 'Abundant' on the SACFOR scale <sup>3</sup> ; they occupy more than 10% of the habitat; or a high-risk species indicative of sub-optimal condition is present – GB Non-native Species Secretariat should be notified, see Footnote 4.		
<b>B</b> <b>Water Quality</b>	No visual evidence of pollution. There are no nuisance algal growths that are likely to be attributable to nutrient enrichment. Consider seasonality of survey timing <sup>5</sup> .	Visual evidence of low to moderate levels of pollution. Elevated algal growth with increases in cover that may indicate nutrient enrichment. Consider seasonality of survey timing <sup>5</sup> .	Visual evidence of high algal growth that is indicative of nutrient enrichment. Signs of eutrophication that would impede bird feeding. Consider seasonality of survey timing <sup>5</sup> .		
<b>C</b> <b>Non-natural structures and direct human impacts</b>	No evidence of impacts from direct human activities, or they occupy <1% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies 1-10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies >10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).		
<b>D</b> <b>Litter (when examining a beach strandline, mean high water line or intertidal rocky shore)</b>	Following the Marine Conservation Society (MCS) beach litter survey method, the number of items of litter does not exceed 0.0036 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to up to 20 items per person per 100 m per hour. See Footnote 6 for details.	Following the MCS beach litter survey method, the number of items of litter does not exceed 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to between 21 and 47 items per person per 100 m per hour. See Footnote 6 for details.	Following the MCS beach litter survey method, the number of items of litter exceeds 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to more than 47 items per person per 100 m per hour. See Footnote 6 for details.		

<b>E</b>	<b>Salinity</b>	Salinity is between 15 - 40 ppt.	Salinity values are close to (but still within) the ends of range acceptable for lagoons (15 - 40 ppt).	Salinity values are either hypersaline >40 ppt or hyposaline <15 ppt.		
<b>F</b>	<b>Isolating barrier</b>	Fully functional and permitting tidal exchange.	Slightly damaged but some water exchange still occurring.	Not functioning. No water exchange occurring making the lagoon hyposaline.		
<b>G</b>	<b>Physical damage of lagoon banks</b>	No physical damage present <sup>7</sup> .	Only small, isolated patches of physical damage present <sup>7</sup> .	Evidence of significant physical damage <sup>7</sup> .		
<b>H</b>	<b>Water clarity</b>	Water is clear.	Water clarity is reduced.	Water is turbid and water clarity is poor (not just after heavy rain).		
<b>Total Score (out of a possible 24)</b>						
<b>Condition Assessment Result</b>					<b>Result Achieved</b>	
<b>TOTAL SCORE 18-24 (75-100%) = GOOD CONDITION</b>						
<b>TOTAL SCORE 12-17 (50-75%) = MODERATE CONDITION</b>						
<b>TOTAL SCORE 8-11 (0-50%) = POOR CONDITION</b>						
<b>Suggested enhancement interventions to improve condition score</b>						
<b>Footnotes</b>						

Condition Sheet: COASTAL LAGOONS Habitat Type																
EUNIS Habitat Type(s)																
Coastal lagoons																
Site name and location		On-site or off-site														
Limitations (if applicable)		Survey reference (if relating to a wider survey)														
Habitat Description																
The coastal lagoons EUNIS habitat description is available here: <a href="http://eunis.europa.eu">EUNIS -Factsheet for Coastal lagoons (europa.eu)</a>																
Habitat Attributes to Record																
The following information should be recorded within the condition assessment sheet: <ul style="list-style-type: none"> <li>• Extent of lagoon waterbody<sup>1</sup>;</li> <li>• Description of presence of typical communities and biotopes;</li> <li>• Description of species diversity and community composition<sup>2</sup>;</li> <li>• Salinity in parts per thousand (ppt);</li> <li>• Presence and abundance of non-native species;</li> <li>• Observations on coastal process functioning and any human physical modifications present;</li> <li>• Percentage cover of algal growths that could be attributed to nutrient enrichment;</li> <li>• Presence and density of non-natural structures and direct human impacts;</li> <li>• Assessment of litter;</li> <li>• Visual record of water clarity;</li> <li>• Observations of the functioning and state of the isolating barrier; and</li> <li>• Observations of the functioning and state of the lagoon banks.</li> </ul>											Habitat parcel reference					
											Grid reference					
Condition Assessment Criteria																
Indicator	Good (3 points)	Moderate (2 points)	Poor (1 point)	Score per criterion								Notes (such as justification)				
A	<b>Presence and abundance of invasive non-native species</b>	Not more than one invasive non-native species is 'Occasional' on the SACFOR scale <sup>3</sup> ; or is occupying more than 1% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 4.	No invasive non-native species are present above 'Frequent' on the SACFOR scale <sup>3</sup> ; or they occupy between 1-10% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 4.	One or more invasive non-native species are 'Abundant' on the SACFOR scale <sup>3</sup> ; they occupy more than 10% of the habitat; or a high-risk species indicative of sub-optimal condition is present – GB Non-native Species Secretariat should be notified, see Footnote 4.												
B	<b>Water Quality</b>	No visual evidence of pollution. There are no nuisance algal growths that are likely to be attributable to nutrient enrichment. Consider seasonality of survey timing <sup>5</sup> .	Visual evidence of low to moderate levels of pollution. Elevated algal growth with increases in cover that may indicate nutrient enrichment. Consider seasonality of survey timing <sup>5</sup> .	Visual evidence of high algal growth that is indicative of nutrient enrichment. Signs of eutrophication that would impede bird feeding. Consider seasonality of survey timing <sup>5</sup> .												
C	<b>Non-natural structures and direct human impacts</b>	No evidence of impacts from direct human activities, or they occupy <1% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies 1-10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies >10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).												
D	<b>Litter (when examining a beach strandline, mean high water line or intertidal rocky shore)</b>	Following the Marine Conservation Society (MCS) beach litter survey method the number of items of litter does not exceed 0.0036 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> equivalent to up to 20 items per person per 100 m per hour. See Footnote 6 for details.	Following the MCS beach litter survey method the number of items of litter does not exceed 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> equivalent to between 21 and 47 items per person per 100 m per hour. See Footnote 6 for details.	Following the MCS beach litter survey method the number of items of litter exceeds 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> equivalent to more than 47 items per person per 100 m per hour. See Footnote 6 for details.												
E	<b>Salinity</b>	Salinity is between 15 - 40 ppt.	Salinity values are close to (but still within) the ends of range acceptable for lagoons (15 - 40 ppt).	Salinity values are either hypersaline >40 ppt or hyposaline <15 ppt.												
F	<b>Isolating barrier</b>	Fully functional and permitting tidal exchange.	Slightly damaged but some water exchange still occurring.	Not functioning. No water exchange occurring making the lagoon hyposaline.												
G	<b>Physical damage of lagoon banks</b>	No physical damage present <sup>7</sup> .	Only small, isolated patches of physical damage present <sup>7</sup> .	Evidence of significant physical damage <sup>7</sup> .												
H	<b>Water clarity</b>	Water is clear.	Water clarity is reduced.	Water is turbid and water clarity is poor (not just after heavy rain).												
<b>Total Score (out of a possible 24)</b>																
Condition Assessment Result				Result Achieved												
TOTAL SCORE 18-24 (75-100%) = GOOD CONDITION																
TOTAL SCORE 12-17 (50-75%) = MODERATE CONDITION																
TOTAL SCORE 8-11 (0-50%) = POOR CONDITION																
Suggested enhancement interventions to improve condition score																
Footnotes																

Condition Sheet: COASTAL SALTMARSH Habitat Type					
EUNIS Habitat Type(s)					
Saltmarshes and saline reedbeds					
Artificial saltmarshes and saline reedbeds					
Site name and location			On-site or off-site		
Limitations (if applicable)			Survey reference (if relating to a wider survey)		
Grid reference			Habitat parcel reference		
Habitat Description					
<a href="https://eunis.europa.eu/en/saltmarshes-and-saline-reedbeds">EUNIS -Factsheet for Coastal saltmarshes and saline reedbeds (europa.eu)</a>					
Habitat Attributes to Record					
<p>The following information should be recorded within the condition assessment sheet:</p> <ul style="list-style-type: none"> <li>List of biological communities and species - including whether they are representative or characteristic of disturbance and or pollution;</li> <li>Observations on coastal process functioning and any human physical modifications present;</li> <li>Observations on zonation and transitions to other habitats, including variations in vegetation structure and sward height<sup>1</sup>;</li> <li>Observations of naturally open ground or bare surfaces such as creeks or pans being present in a mosaic with vegetated areas;</li> <li>Presence and abundance of non-native species;</li> <li>Assessment of litter; and</li> <li>Percentage cover of algal growths that could be attributed to nutrient enrichment.</li> </ul>					
Condition Assessment Criteria					
Indicator	Good (3 points)	Moderate (2 points)	Poor (1 point)	Score per indicator	Notes (such as justification)
A Coastal processes	Coastal processes are functioning naturally. No evidence of human physical modifications which are clearly impacting the habitat.	Artificial structures present, for example groynes that are impeding the natural movement of sediments or water, affecting up to 25% of the habitat.	Artificial structures present, for example groynes that are impeding the natural movement of sediments or water, affecting more than 25% of the habitat.		
B Presence and abundance of invasive non-native species	Not more than one invasive non-native species is 'Occasional' on the SACFOR scale or is occupying more than 1% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 2 for details.	No invasive non-native species are present above 'Frequent' on the SACFOR scale or they occupy between 1-10% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 2 for details.	One or more invasive non-native species present at an 'Abundant' level on the SACFOR scale; they occupy more than 10% of the habitat; or a high-risk species indicative of sub-optimal condition is present – GB Non-native Species Secretariat should be notified, see Footnote 2 for details.		
C Water Quality	No visual evidence of pollution. There are no nuisance algal growths that are likely to be attributable to nutrient enrichment. Consider seasonality of survey timing <sup>3</sup> .	Visual evidence of low to moderate levels of pollution. Elevated algal growth with increases in cover that may indicate nutrient enrichment. Consider seasonality of survey timing <sup>3</sup> .	Visual evidence of high algal growth that is indicative of nutrient enrichment. Signs of eutrophication that would impede bird feeding. Consider seasonality of survey timing <sup>3</sup> .		
D Non-natural structures and direct human impacts	No evidence of impacts from direct human activities, or they occupy <1% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies 1-10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies >10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).		

E	<b>Litter (when examining a beach strandline, mean high water line or intertidal rocky shore)</b>	Following the Marine Conservation Society (MCS) beach litter survey method, the number of items of litter does not exceed 0.0036 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to up to 20 items per person per 100 m per hour. See Footnote 4.	Following the MCS beach litter survey method the number of items of litter does not exceed 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> equivalent to between 21 and 47 items of litter per person per 100 m per hour. See Footnote 4.	Following the MCS beach litter survey method the number of items of litter exceeds 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> equivalent to more than 47 items of litter per person per 100 m per hour. See Footnote 4.		
F	<b>Zonation and transition to other habitats</b>	Zonation of vegetation or communities is clear and continuous <sup>5</sup> . Distribution of the feature and transition to other habitats, including associated transitional habitats within the site is reflective of expected natural distribution seaward and landward.	Up to 2 of the expected zones are absent or significantly impacted by human modification of the shoreline, and transitions to other habitats are restricted in less than 20% of the habitat boundaries <sup>5</sup> .	Zonation of vegetation or communities is not clearly visible or is significantly impacted by human modification of the shoreline <sup>5</sup> . Or transitions to other habitats are restricted in more than 20% of the habitat boundaries.		
<b>Total score (out of a possible 18)</b>						
<b>Condition Assessment Result</b>					<b>Result Achieved</b>	
<b>TOTAL SCORE 14 - 18 (75-100%) = GOOD CONDITION</b>						
<b>TOTAL SCORE 9 - 13 (50-75%) = MODERATE CONDITION</b>						
<b>TOTAL SCORE 6 - 8 (0-50%) = POOR CONDITION</b>						
<b>Suggested enhancement interventions to improve condition score</b>						
<b>Footnotes</b>						

<b>Condition Sheet: COASTAL SALTMARSH Habitat Type</b>			
<b>EUNIS Habitat Type(s)</b>			
Saltmarshes and saline reedbeds			
Artificial saltmarshes and saline reedbeds			
Site name and location		On-site or off-site	
Limitations (if applicable)		Survey reference (if relating to a wider survey)	
<b>Habitat Description</b>			

[EUNIS -Factsheet for Coastal saltmarshes and saline reedbeds \(europa.eu\)](https://eunis.europa.eu/en/habitat-type/artificial-saltmarshes-and-saline-reedbeds)

<b>Habitat Attributes to Record</b>												
The following information should be recorded within the condition assessment sheet:												
<ul style="list-style-type: none"> <li>List of biological communities and species - including whether they are representative or characteristic of disturbance and or pollution;</li> <li>Observations on coastal process functioning and any human physical modifications present;</li> <li>Observations on zonation and transitions to other habitats, including variations in vegetation structure and sward height<sup>1</sup>;</li> <li>Observations of naturally open ground or bare surfaces such as creeks or pans being present in a mosaic with vegetated areas;</li> <li>Presence and abundance of non-native species;</li> <li>Assessment of litter; and</li> <li>Percentage cover of algal growths that could be attributed to nutrient enrichment.</li> </ul>												
										<b>Habitat parcel reference</b>		
										<b>Grid reference</b>		

<b>Condition Assessment Criteria</b>																		
Indicator	Good (3 points)	Moderate (2 points)	Poor (1 point)	Score per indicator									Notes (such as justification)					
<b>A</b>	<b>Coastal processes</b>	Coastal processes are functioning naturally. No evidence of human physical modifications which are clearly impacting the habitat.	Artificial structures present, for example groynes that are impeding the natural movement of sediments or water, affecting up to 25% of the habitat.	Artificial structures present, for example groynes that are impeding the natural movement of sediments or water, affecting more than 25% of the habitat.														
<b>B</b>	<b>Presence and abundance of invasive non-native species</b>	Not more than one invasive non-native species is 'Occasional' on the SACFOR scale or is occupying more than 1% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 2 for details.	No invasive non-native species are present above 'Frequent' on the SACFOR scale or they occupy between 1-10% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 2 for details.	One or more invasive non-native species present at an 'Abundant' level on the SACFOR scale; they occupy more than 10% of the habitat; or a high-risk species indicative of sub-optimal condition is present – GB Non-native Species Secretariat should be notified, see Footnote 2 for details.														
<b>C</b>	<b>Water Quality</b>	No visual evidence of pollution. There are no nuisance algal growths that are likely to be attributable to nutrient enrichment. Consider seasonality of survey timing <sup>3</sup> .	Visual evidence of low to moderate levels of pollution. Elevated algal growth with increases in cover that may indicate nutrient enrichment. Consider seasonality of survey timing <sup>3</sup> .	Visual evidence of high algal growth that is indicative of nutrient enrichment. Signs of eutrophication that would impede bird feeding. Consider seasonality of survey timing <sup>3</sup> .														
<b>D</b>	<b>Non-natural structures and direct human impacts</b>	No evidence of impacts from direct human activities, or they occupy <1% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies 1-10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies >10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).														
<b>E</b>	<b>Litter (when examining a beach strandline, mean high water line or intertidal rocky shore)</b>	Following the Marine Conservation Society (MCS) beach litter survey method, the number of items of litter does not exceed 0.0036 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to up to 20 items per person per 100 m per hour. See Footnote 4.	Following the MCS beach litter survey method the number of items of litter does not exceed 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> equivalent to between 21 and 47 items of litter per person per 100 m per hour. See Footnote 4.	Following the MCS beach litter survey method the number of items of litter exceeds 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> equivalent to more than 47 items of litter per person per 100 m per hour. See Footnote 4.														
<b>F</b>	<b>Zonation and transition to other habitats</b>	Zonation of vegetation or communities is clear and continuous <sup>5</sup> . Distribution of the feature and transition to other habitats, including associated transitional habitats within the site is reflective of expected natural distribution seaward and landward.	Up to 2 of the expected zones are absent or significantly impacted by human modification of the shoreline, and transitions to other habitats are restricted in less than 20% of the habitat boundaries <sup>5</sup> .	Zonation of vegetation or communities is not clearly visible or is significantly impacted by human modification of the shoreline <sup>5</sup> . Or transitions to other habitats are restricted in more than 20% of the habitat boundaries.														
<b>Total score (out of a possible 18)</b>																		

<b>Condition Assessment Result</b>													<b>Result Achieved</b>				
<b>TOTAL SCORE 14 - 18 (75-100%) = GOOD CONDITION</b>																	
<b>TOTAL SCORE 9 - 13 (50-75%) = MODERATE CONDITION</b>																	
<b>TOTAL SCORE 6 - 8 (0-50%) = POOR CONDITION</b>																	

Suggested enhancement interventions to improve condition score

Footnotes

Condition Sheet: DITCH Habitat Type			
Habitat Type			
Watercourses - Ditches			
Habitat Description			
See the Biodiversity Metric 4.0 User Guide.			
Site name and location		On-site or off-site	
Limitations (if applicable)		Survey reference (if relating to a wider survey)	
Grid reference		Habitat parcel reference	
Condition Assessment Criteria		Criterion passed (Yes or No)	Notes (such as justification)
A	The ditch is of good water quality, with clear water (low turbidity) indicating no obvious signs of pollution.		
B	A range of emergent, submerged and floating-leaved plants are present. As a guide >10 species of emergent, floating or submerged plants present in a 20 m ditch length.		
C	There is less than 10% cover of filamentous algae and or duckweed <i>Lemna</i> spp. (these are signs of eutrophication).		
D	A fringe of aquatic marginal vegetation is present along more than 75% of the ditch.		
E	Physical damage is evident along less than 5% of the ditch, with examples of damage including: excessive poaching, damage from machinery use or storage, or any other damaging management activities.		
F	Sufficient water levels are maintained - as a guide a minimum summer depth of approximately 50 cm in minor ditches and 1 m in main drains.		
G	Less than 10% of the ditch is heavily shaded.		
H	There is an absence of non-native plant and animal species <sup>1</sup> .		
<b>Number of criteria passed</b>			
Condition Assessment Result (out of 8 criteria)	Condition Assessment Score	Score Achieved ×/✓	
Passes 8 criteria	Good (3)		
Passes 6 or 7 criteria	Moderate (2)		
Passes 5 or fewer criteria	Poor (1)		
Suggested enhancement interventions to improve condition score			
Footnotes			

Condition Sheet: DITCH Habitat Type											
Habitat Type											
Watercourses - Ditches											
Habitat Description											
See the Biodiversity Metric 4.0 User Guide.											
Site name and location		On-site or off-site									
Limitations (if applicable)		Survey reference (if relating to a wider survey)									
		Habitat parcel reference									
		Grid reference									
Condition Assessment Criteria		Criterion passed (Yes or No)								Notes (such as justification)	
A	The ditch is of good water quality, with clear water (low turbidity) indicating no obvious signs of pollution.										
B	A range of emergent, submerged and floating-leaved plants are present. As a guide >10 species of emergent, floating or submerged plants present in a 20 m ditch length.										
C	There is less than 10% cover of filamentous algae and or duckweed <i>Lemna</i> spp. (these are signs of eutrophication).										
D	A fringe of aquatic marginal vegetation is present along more than 75% of the ditch.										
E	Physical damage is evident along less than 5% of the ditch, with examples of damage including: excessive poaching, damage from machinery use or storage, or any other damaging management activities.										
F	Sufficient water levels are maintained - as a guide a minimum summer depth of approximately 50 cm in minor ditches and 1 m in main drains.										
G	Less than 10% of the ditch is heavily shaded.										
H	There is an absence of non-native plant and animal species <sup>1</sup> .										
Number of criteria passed											
Condition Assessment Result (out of 8 criteria)		Condition Assessment Score		Score Achieved * / ✓							
Passes 8 criteria		Good (3)									
Passes 6 or 7 criteria		Moderate (2)									
Passes 5 or fewer criteria		Poor (1)									
Suggested enhancement interventions to improve condition score											
Footnotes											

Condition Sheet: GRASSLAND Habitat Type (low distinctiveness)			
UK Habitat Classification (UKHab) Habitat Type(s)			
Grassland - Modified grassland			
Site name and location		On-site or off-site	
Limitations (if applicable)		Survey reference (if relating to a wider survey)	
Grid reference		Habitat parcel reference	
Habitat Description			
<a href="#">ukhab – UK Habitat Classification</a>			
Condition Assessment Criteria		Criterion passed (Yes or No)	Notes (such as justification)
A	There are 6-8 vascular plant species per m <sup>2</sup> present, including at least 2 forbs (this may include those listed in Footnote 1). <b>Note - this criterion is essential for achieving Moderate or Good condition.</b>  Where the vascular plant species present are characteristic of medium, high or very high distinctiveness grassland, or there are 9 or more of these characteristic species per m <sup>2</sup> (excluding those listed in Footnote 1), please review the full UKHab description to assess whether the grassland should instead be classified as a higher distinctiveness grassland. Where a grassland is classed as medium, high, or very high distinctiveness, please use the relevant condition sheet.		
B	Sward height is varied (at least 20% of the sward is less than 7 cm and at least 20% is more than 7 cm) creating microclimates which provide opportunities for vertebrates and invertebrates to live and breed.		
C	Some scattered scrub (including bramble <i>Rubus fruticosus</i> agg.) may be present, but scrub accounts for less than 20% of total grassland area.  Note - patches of scrub with continuous (more than 90%) cover should be classified as the relevant scrub habitat type.		
D	Physical damage is evident in less than 5% of total grassland area. Examples of physical damage include excessive poaching, damage from machinery use or storage, erosion caused by high levels of access, or any other damaging management activities.		
E	Cover of bare ground is between 1% and 10%, including localised areas (for example, a concentration of rabbit warrens) <sup>2</sup> .		
F	Cover of bracken <i>Pteridium aquilinum</i> is less than 20%.		
G	There is an absence of invasive non-native plant species <sup>3</sup> (as listed on Schedule 9 of WCA <sup>4</sup> ).		
		Essential criterion achieved (Yes or No)	
		Number of criteria passed	
Condition Assessment Result (out of 7 criteria)	Condition Assessment Score	Score Achieved x/√	
Passes 6 or 7 criteria including passing essential criterion A	Good (3)		
Passes 4 or 5 criteria including passing essential criterion A	Moderate (2)		
Passes 3 or fewer criteria; OR Passes 4 - 6 criteria (excluding criterion A)	Poor (1)		
Suggested enhancement interventions to improve condition score			
Footnotes			

**Footnote 1** – Creeping thistle *Cirsium arvense*, spear thistle *Cirsium vulgare*, curled dock *Rumex crispus*, broad-leaved dock *Rumex obtusifolius*, common nettle *Urtica dioica*, creeping buttercup *Ranunculus repens*, greater plantain *Plantago major*, white clover *Trifolium repens* and cow parsley *Anthriscus sylvestris*.

**Footnote 2** – For example, this could include small, scattered areas of bare ground allowing establishment of new species, or localised patches where not exceeding 10% cover.

**Footnote 3** – Assess this for each distinct habitat parcel. If the distribution of invasive non-native species varies across the habitat, split into parcels accordingly, applying a buffer zone around the invasive non-native species with a size relative to its risk of spread into adjacent habitat, using professional judgement.

**Footnote 4** – Wildlife and Countryside Act 1981 (as amended).

Condition Sheet: GRASSLAND Habitat Type (low distinctiveness)												
UK Habitat Classification (UKHab) Habitat Type(s)												
Grassland - Modified grassland												
Habitat Description												
ukhab – UK Habitat Classification												
Site name and location												
	On-site or off-site											
Survey reference (if relating to a wider survey)												
	Habitat parcel reference											
Limitations (if applicable)	MG1	MG2	MG3									
	Grid reference											
Condition Assessment Criteria												
	Criterion passed (Yes or No)											Notes (such as justification)
A	There are 6-8 vascular plant species per m <sup>2</sup> present, including at least 2 forbs (this may include those listed in Footnote 1). <b>Note - this criterion is essential for achieving Moderate or Good condition.</b>  Where the vascular plant species present are characteristic of medium, high or very high distinctiveness grassland, or there are 9 or more of these characteristic species per m <sup>2</sup> (excluding those listed in Footnote 1), please review the full UKHab description to assess whether the grassland should instead be classified as a higher distinctiveness grassland. Where a grassland is classed as medium, high, or very high distinctiveness, please use the relevant condition sheet.	N	N	N								
B	Sward height is varied (at least 20% of the sward is less than 7 cm and at least 20% is more than 7 cm) creating microclimates which provide opportunities for vertebrates and invertebrates to live and breed.	N	Y	N								
C	Some scattered scrub (including bramble <i>Rubus fruticosus</i> agg.) may be present, but scrub accounts for less than 20% of total grassland area.  Note - patches of scrub with continuous (more than 90%) cover should be classified as the relevant scrub habitat type.	Y	Y	Y								
D	Physical damage is evident in less than 5% of total grassland area. Examples of physical damage include excessive poaching, damage from machinery use or storage, erosion caused by high levels of access, or any other damaging management activities.	Y	Y	N								
E	Cover of bare ground is between 1% and 10%, including localised areas (for example, a concentration of rabbit warrens) <sup>2</sup> .	Y	Y	N								
F	Cover of bracken <i>Pteridium aquilinum</i> is less than 20%.	Y	Y	Y								
G	There is an absence of invasive non-native plant species <sup>3</sup> (as listed on Schedule 9 of WCA <sup>4</sup> ).	Y	Y	Y								
Essential criterion achieved (Yes or No)		N	N	N								
Number of criteria passed		5	6	3								
Condition Assessment Result (out of 7 criteria)	Condition Assessment Score	Score Achieved * / ✓										
Passes 6 or 7 criteria including passing essential criterion A	Good (3)											
Passes 4 or 5 criteria including passing essential criterion A	Moderate (2)											
Passes 3 or fewer criteria; OR Passes 4 - 6 criteria (excluding criterion A)	Poor (1)	Poor	Poor	Poor								
Suggested enhancement interventions to improve condition score												
Footnotes												
<b>Footnote 1</b> – Creeping thistle <i>Cirsium arvense</i> , spear thistle <i>Cirsium vulgare</i> , curled dock <i>Rumex crispus</i> , broad-leaved dock <i>Rumex obtusifolius</i> , common nettle <i>Urtica dioica</i> , creeping buttercup <i>Ranunculus repens</i> , greater plantain <i>Plantago major</i> , white clover <i>Trifolium repens</i> and cow parsley <i>Anthriscus sylvestris</i> .												
<b>Footnote 2</b> – For example, this could include small, scattered areas of bare ground allowing establishment of new species, or localised patches where not exceeding 10% cover.												
<b>Footnote 3</b> – Assess this for each distinct habitat parcel. If the distribution of invasive non-native species varies across the habitat, split into parcels accordingly, applying a buffer zone around the invasive non-native species with a size relative to its risk of spread into adjacent habitat, using professional judgement.												
<b>Footnote 4</b> – Wildlife and Countryside Act 1981 (as amended).												

Condition Sheet: GRASSLAND Habitat Type (medium, high and very high distinctiveness)			
UK Habitat Classification (UKHab) Habitat Type(s)			
<b>Grassland - Lowland calcareous grassland</b> <b>Grassland - Lowland dry acid grassland</b> <b>Grassland - Lowland meadows</b> <b>Grassland - Other lowland acid grassland</b> <b>Grassland - Other neutral grassland</b> <b>Grassland - Tall herb communities (H6430)</b> [Note Tall herb habitat that does not meet the Annex 1 definition should be recorded as 'Other neutral grassland'] [Not to be confused with the Tall forbs secondary code – see UKHab guidance for details.] <b>Grassland - Upland acid grassland</b> <b>Grassland - Upland calcareous grassland</b> <b>Grassland - Upland hay meadows</b> <b>Sparsely vegetated land - Calaminarian grassland</b>			
<b>Site name and location</b>		<b>On-site or off-site</b>	
<b>Limitations (if applicable)</b>		<b>Survey reference (if relating to a wider survey)</b>	
<b>Grid reference</b>		<b>Habitat parcel reference</b>	
Habitat Description			
<a href="#">ukhab – UK Habitat Classification</a>			
Condition Assessment Criteria		Criterion passed (Yes or No)	Notes (such as justification)
A	<p>The grassland is a good representation of the habitat type it has been identified as, based on its UKHab description - the appearance and composition of the vegetation closely matches the characteristics of the specific grassland habitat type. Indicator species listed by UKHab for the specific grassland habitat type are consistently present.</p> <p><b>Note - this criterion is essential for achieving Moderate or Good condition for non-acid grassland types only.</b></p>		
B	Sward height is varied (at least 20% of the sward is less than 7 cm and at least 20% is more than 7 cm) creating microclimates which provide opportunities for insects, birds and small mammals to live and breed.		
C	Cover of bare ground is between 1% and 5%, including localised areas, for example, rabbit warrens <sup>1</sup> .		
D	Cover of bracken <i>Pteridium aquilinum</i> is less than 20% and cover of scrub (including bramble <i>Rubus fruticosus</i> agg.) is less than 5%.		
E	<p>Combined cover of species indicative of sub-optimal condition<sup>2</sup> and physical damage (such as excessive poaching, damage from machinery use or storage, damaging levels of access, or any other damaging management activities) accounts for less than 5% of total area.</p> <p>If any invasive non-native plant species<sup>3</sup> (as listed on Schedule 9 of WCA<sup>4</sup>) are present, this criterion is automatically failed.</p>		
Additional Criterion - must be assessed for all non-acid grassland types			
F	<p>There are 10 or more vascular plant species per m<sup>2</sup> present, including forbs that are characteristic of the habitat type (species referenced in Footnote 2 and 4 cannot contribute towards this count).</p> <p><b>Note - this criterion is essential for achieving Good condition for non-acid grassland types only.</b></p>		
<b>Essential criterion for Good condition achieved (for non-acid grassland) (Yes or No)</b>			
<b>Number of criteria passed</b>			

Condition Assessment Result	Condition Assessment Score	Score Achieved x/✓
<b>Acid Grassland Types (Result out of 5 criteria)</b>		
Passes 5 criteria	Good (3)	
Passes 3 or 4 criteria	Moderate (2)	
Passes 2 or fewer criteria	Poor (1)	
<b>Non-acid grassland Types (Result out of 6 criteria)</b>		
Passes 5 or 6 criteria, including essential criterion A and additional criterion F.	Good (3)	
Passes 3 - 5 criteria, including essential criterion A.	Moderate (2)	
Passes 2 or fewer criteria; OR Passes 3 or 4 criteria excluding criterion A and F.	Poor (1)	
<b>Suggested enhancement interventions to improve condition score</b>		
<b>Notes</b>		
<p><b>Footnote 1</b> – For example, this could include small, scattered areas of bare ground allowing for plant colonisation, or localised patches not exceeding 5% cover.</p> <p><b>Footnote 2</b> - Species indicative of sub-optimal condition for this habitat type include: creeping thistle <i>Cirsium arvense</i> , spear thistle <i>Cirsium vulgare</i> , curled dock <i>Rumex crispus</i> , broad-leaved dock <i>Rumex obtusifolius</i> , common nettle <i>Urtica dioica</i> , creeping buttercup <i>Ranunculus repens</i> , greater plantain <i>Plantago major</i> , white clover <i>Trifolium repens</i> and cow parsley <i>Anthriscus sylvestris</i> . There may be additional relevant species local to the region and or site.</p> <p><b>Footnote 3</b> – Assess this for each distinct habitat parcel. If the distribution of invasive non-native species varies across the habitat, split into parcels accordingly, applying a buffer zone around the invasive non-native species with a size relative to its risk of spread into adjacent habitat, by applying professional judgement.</p> <p><b>Footnote 4</b> – Wildlife and Countryside Act 1981 (as amended).</p>		

Condition Sheet: GRASSLAND Habitat Type (medium, high and very high distinctiveness)												
UK Habitat Classification (UKHab) Habitat Type(s)												
Grassland - Lowland calcareous grassland Grassland - Lowland dry acid grassland Grassland - Lowland meadows Grassland - Other lowland acid grassland Grassland - Other neutral grassland Grassland - Tall herb communities (H6430) [Note Tall herb habitat that does not meet the Annex 1 definition should be recorded as 'Other neutral grassland'] [Not to be confused with the Tall forbs secondary code – see UKHab guidance for details.] Grassland - Upland acid grassland Grassland - Upland calcareous grassland Grassland - Upland hay meadows Sparsely vegetated land - Calaminarian grassland												
Habitat Description												
ukhab – UK Habitat Classification												
Site name and location		On-site or off-site										
Limitations (if applicable)		Survey reference (if relating to a wider survey)										
Condition Assessment Criteria		Habitat parcel reference										
		ONG										
		Grid reference										
		Criterion passed (Yes or No)										
				Notes (such as justification)								
A	The grassland is a good representation of the habitat type it has been identified as, based on its UKHab description - the appearance and composition of the vegetation closely matches the characteristics of the specific grassland habitat type. Indicator species listed by UKHab for the specific grassland habitat type are consistently present.  <b>Note - this criterion is essential for achieving Moderate or Good condition for non-acid grassland types only.</b>	Y										
B	Sward height is varied (at least 20% of the sward is less than 7 cm and at least 20% is more than 7 cm) creating microclimates which provide opportunities for insects, birds and small mammals to live and breed.	Y										
C	Cover of bare ground is between 1% and 5%, including localised areas, for example, rabbit warrens <sup>1</sup> .	Y										
D	Cover of bracken <i>Pteridium aquilinum</i> is less than 20% and cover of scrub (including bramble <i>Rubus fruticosus</i> agg.) is less than 5%.	Y										
E	Combined cover of species indicative of sub-optimal condition <sup>2</sup> and physical damage (such as excessive poaching, damage from machinery use or storage, damaging levels of access, or any other damaging management activities) accounts for less than 5% of total area.  If any invasive non-native plant species <sup>3</sup> (as listed on Schedule 9 of WCA <sup>4</sup> ) are present, this criterion is automatically failed.	N										
Additional Criterion - must be assessed for all non-acid grassland types												
F	There are 10 or more vascular plant species per m <sup>2</sup> present, including forbs that are characteristic of the habitat type (species referenced in Footnote 2 and 4 cannot contribute towards this count).  <b>Note - this criterion is essential for achieving Good condition for non-acid grassland types only.</b>	N										
Essential criterion for Good condition achieved (for non-acid grassland) (Yes or No)		N										
Number of criteria passed		3										
Condition Assessment Result	Condition Assessment Score	Score Achieved x/✓										
Acid Grassland types (Result out of 5 criteria)												
Passes 5 criteria	Good (3)											
Passes 3 or 4 criteria	Moderate (2)											
Passes 2 or fewer criteria	Poor (1)											
Non-acid grassland types (Result out of 6 criteria)												
Passes 5 or 6 criteria, including essential criterion A and additional criterion F.	Good (3)											
Passes 3 - 5 criteria, including essential criterion A.	Moderate (2)											
Passes 2 or fewer criteria; OR Passes 3 or 4 criteria excluding criterion A and F.	Poor (1)											
Suggested enhancement interventions to improve condition score												
Notes												

**Footnote 1** – For example, this could include small, scattered areas of bare ground allowing for plant colonisation, or localised patches not exceeding 5% cover.

**Footnote 2** - Species indicative of sub-optimal condition for this habitat type include: creeping thistle *Cirsium arvense* , spear thistle *Cirsium vulgare* , curled dock *Rumex crispus* , broad-leaved dock *Rumex obtusifolius* , common nettle *Urtica dioica* , creeping buttercup *Ranunculus repens* , greater plantain *Plantago major* , white clover *Trifolium repens* and cow parsley *Anthriscus sylvestris* . There may be additional relevant species local to the region and or site.

**Footnote 3** – Assess this for each distinct habitat parcel. If the distribution of invasive non-native species varies across the habitat, split into parcels accordingly, applying a buffer zone around the invasive non-native species with a size relative to its risk of spread into adjacent habitat, by applying professional judgement.

**Footnote 4** – Wildlife and Countryside Act 1981 (as amended).

Condition Sheet: HEATHLAND Habitat Type			
UK Habitat Classification (UKHab) Habitat Type(s)			
Heathland and shrub - Lowland heathland			
Heathland and shrub - Mountain heaths and willow scrub			
Heathland and shrub - Upland heathland			
Habitat Description			
<a href="#">ukhab – UK Habitat Classification</a>			
Site name and location		On-site or off-site	
Limitations (if applicable)		Survey reference (if relating to a wider survey)	
Central grid reference of habitat		Habitat parcel reference	
Condition Assessment Criteria		Criterion passed (Yes or No)	Notes (such as justification)
A	The heathland is a good representation of the habitat type it has been identified as, based on its UKHab description - the appearance and composition of the vegetation closely matches the characteristics of the specific heathland habitat type. Indicator shrubs, grasses, forbs and lower (non-vascular) plants listed by UKHab for the specific heathland habitat type are consistently present. <b>Note - this criterion is essential for achieving Good condition.</b>		
B	There are at least two dwarf shrub species Frequent <sup>1</sup> , and cover of dwarf shrubs is between 25-75% for lowland heathland, 50-75% for upland dry heath, or >20% for upland wet heath. <b>Note - this criterion is essential for achieving Good condition.</b>		
C	All heather <i>Calluna vulgaris</i> age-classes (pioneer, degenerate and mature) present with at least 10% pioneer heather in the lowlands or at least 10% degenerate or mature in the uplands. <b>Note - this criterion is essential for achieving Good condition.</b>		
D	Unshaded bare ground is between 1-10%. <b>Note - this criterion is essential for achieving Good condition.</b>		
E	There is an absence of invasive non-native plant species listed on Schedule 9 of WCA <sup>2</sup> and shallon <i>Gaultheria shallon</i> <sup>3</sup> . <b>Note - this criterion is essential for achieving Good condition.</b>		
F	No signs of disturbance of sensitive areas <sup>4</sup> , including managed burns.		
G	No more than 33% of heather shoots have been recently grazed, or flowering heather plants are at least Frequent <sup>1</sup> in autumn.		
H	The canopy cover of scattered trees and or scrub (not including gorse <i>Ulex</i> spp.) is: •less than 20% for upland heaths; •less than 15% for lowland dry heaths; and •less than 10% for lowland wet heaths.		
I	Total gorse cover is less than 50%, with common gorse <i>Ulex europaeus</i> less than 25%.		
J	The cover of bracken <i>Pteridium aquilinum</i> is less than 5% <sup>5</sup> .		
K	No signs of any damaging activities <sup>6</sup> or contamination to the habitat such as: artificial drains, peat extraction, silt, leachate or eutrophication.		
<b>Essential criteria for achieving Good condition achieved (Yes or No)</b>			
<b>Number of criteria passed</b>			

Condition Assessment Result (out of 11 criteria)	Condition Assessment Score	Score Achieved x/√
Passes 9 - 11 criteria including all essential criteria A - E.	Good (3)	
Passes 7 or 8 criteria; OR Passes 9 - 10 criteria but fails any essential criteria (criteria A - E).	Moderate (2)	
Passes 6 or fewer criteria.	Poor (1)	

**Suggested enhancement interventions to improve condition score**

**Footnotes**

- Footnote 1** – According to the relative abundance DAFOR scale – Dominant, Abundant, Frequent, Occasional or Rare.
- Footnote 2** – Wildlife and Countryside Act 1981 (as amended).
- Footnote 3** – Assess this for each distinct habitat parcel. If the distribution of invasive non-native species varies across the habitat, split into parcels accordingly, applying a buffer zone around the invasive non-native species with a size relative to its risk of spread into adjacent habitat, using professional judgement.
- Footnote 4** – Professional judgement should be used to assess this and evidence should be provided according to the INSTRUCTIONS Tab of this spreadsheet.  
Definition of sensitive areas:  
(a) Vegetation severely wind-clipped, mostly forming a mat less than 10 cm thick.  
(b) Areas where soils are thin and less than 5 cm deep.  
(c) Hill slopes greater than 1 in 2 (26°), and all the sides of gullies.  
(d) Ground with abundant, and or an almost continuous carpet of Sphagnum moss *Sphagnum* spp., bilberry *Vaccinium myrtillus*, liverworts and or lichens.  
(e) Areas with noticeably uneven structure, at a spatial scale of around 1 m<sup>2</sup> or less. The unevenness (more commonly found in very old heather stands) will relate to distinct, often large, spreading dwarf shrub bushes. The dwarf shrub canopy will not be completely continuous, and some of its upper surface may be twice as high as other parts. Layering is likely to be present and may be common.  
(f) Pools, wet hollows, peat hags and erosion gullies within 10 m of the edge of watercourses.
- Footnote 5** - Cover of bracken may exceed 5% where there is an identified biodiversity benefit, for example bracken beds in the South Pennines as nesting sites for twite *Linaria flavirostris*.
- Footnote 6** - Damaging activities include: accidental or unmanaged fires; managed fires on wet heath; excessive poaching; damage from machinery use or storage; and damaging levels of public access resulting in trampling and or litter.

Condition Sheet: HEATHLAND Habitat Type																				
UK Habitat Classification (UKHab) Habitat Type(s)																				
Heathland and shrub - Lowland heathland																				
Heathland and shrub - Mountain heaths and willow scrub																				
Heathland and shrub - Upland heathland																				
Habitat Description																				
<a href="#">ukhab – UK Habitat Classification</a>																				
Site name and location											On-site or off-site									
											Survey reference (if relating to a wider survey)									
Limitations (if applicable)											Habitat parcel reference									
Condition Assessment Criteria											Grid reference									
Criterion passed (Yes or No)											Notes (such as justification)									
A	The heathland is a good representation of the habitat type it has been identified as, based on its UKHab description - the appearance and composition of the vegetation closely matches the characteristics of the specific heathland habitat type. Indicator shrubs, grasses, forbs and lower (non-vascular) plants listed by UKHab for the specific heathland habitat type are consistently present. <b>Note - this criterion is essential for achieving Good condition.</b>																			
B	There are at least two dwarf shrub species Frequent <sup>1</sup> , and cover of dwarf shrubs is between 25-75% for lowland heathland, 50-75% for upland dry heath, or >20% for upland wet heath. <b>Note - this criterion is essential for achieving Good condition.</b>																			
C	All heather <i>Calluna vulgaris</i> age-classes (pioneer, degenerate and mature) present with at least 10% pioneer heather in the lowlands or at least 10% degenerate or mature in the uplands. <b>Note - this criterion is essential for achieving Good condition.</b>																			
D	Unshaded bare ground is between 1-10%. <b>Note - this criterion is essential for achieving Good condition.</b>																			
E	There is an absence of invasive non-native plant species listed on Schedule 9 of WCA <sup>2</sup> and shallon <i>Gaultheria shallon</i> <sup>3</sup> . <b>Note - this criterion is essential for achieving Good condition.</b>																			
F	No signs of disturbance of sensitive areas <sup>4</sup> , including managed burns.																			
G	No more than 33% of heather shoots have been recently grazed, or flowering heather plants are at least Frequent <sup>1</sup> in autumn.																			
H	The canopy cover of scattered trees and or scrub (not including gorse <i>Ulex</i> spp.) is: •less than 20% for upland heaths; •less than 15% for lowland dry heaths; and •less than 10% for lowland wet heaths.																			
I	Total gorse cover is less than 50%, with common gorse <i>Ulex europaeus</i> less than 25%.																			
J	The cover of bracken <i>Pteridium aquilinum</i> is less than 5% <sup>5</sup> .																			
K	No signs of any damaging activities <sup>6</sup> or contamination to the habitat such as: artificial drains, peat extraction, silt, leachate or eutrophication.																			
Essential criteria for achieving Good condition achieved (Yes or No)																				
Number of criteria passed																				
Condition Assessment Result (out of 11 criteria)	Condition Assessment Score	Score Achieved ×/✓																		
Passes 9 - 11 criteria including all essential criteria A - E.	Good (3)																			
Passes 7 or 8 criteria; OR Passes 9 - 10 criteria but fails any essential criteria (criteria A - E).	Moderate (2)																			
Passes 6 or fewer criteria.	Poor (1)																			
Suggested enhancement interventions to improve condition score																				
Footnotes																				

**Footnote 1** – According to the relative abundance DAFOR scale – Dominant, Abundant, Frequent, Occasional or Rare.

**Footnote 2** – Wildlife and Countryside Act 1981 (as amended).

**Footnote 3** – Assess this for each distinct habitat parcel. If the distribution of invasive non-native species varies across the habitat, split into parcels accordingly, applying a buffer zone around the invasive non-native species with a size relative to its risk of spread into adjacent habitat, using professional judgement.

**Footnote 4** – Professional judgement should be used to assess this and evidence should be provided according to the INSTRUCTIONS Tab of this spreadsheet.

Definition of sensitive areas:

(a) Vegetation severely wind-clipped, mostly forming a mat less than 10 cm thick.

(b) Areas where soils are thin and less than 5 cm deep.

(c) Hill slopes greater than 1 in 2 (26°), and all the sides of gullies.

(d) Ground with abundant, and or an almost continuous carpet of Sphagnum moss *Sphagnum* spp., bilberry *Vaccinium myrtillus*, liverworts and or lichens.

(e) Areas with noticeably uneven structure, at a spatial scale of around 1 m<sup>2</sup> or less. The unevenness (more commonly found in very old heather stands) will relate to distinct, often large, spreading dwarf shrub bushes. The dwarf shrub canopy will not be completely continuous, and some of its upper surface may be twice as high as other parts. Layering is likely to be present and may be common.

(f) Pools, wet hollows, peat hags and erosion gullies within 10 m of the edge of watercourses.

**Footnote 5** - Cover of bracken may exceed 5% where there is an identified biodiversity benefit, for example bracken beds in the South Pennines as nesting sites for twite *Linaria flavirostris*.

**Footnote 6** - Damaging activities include: accidental or unmanaged fires; managed fires on wet heath; excessive poaching; damage from machinery use or storage; and damaging levels of public access resulting in trampling and or litter.

Condition sheet: HEDGEROW Habitat Types				
Habitat Type				
Native hedgerow				
Native hedgerow - associated with bank or ditch				
Native hedgerow with trees				
Native hedgerow with trees - associated with bank or ditch				
Species-rich native hedgerow				
Species-rich native hedgerow - associated with bank or ditch				
Species-rich native hedgerow with trees				
Species-rich native hedgerow with trees - associated with bank or ditch				
Habitat Description				
See the Biodiversity Metric 4.0 User Guide Section 9. Each attribute is assigned to one of five functional groups (A – E) and the condition of a hedgerow is assessed according to the number of attributes from these functional groups which pass or fail the 'favourable condition' criteria.				
Site name and location		On-site or off-site		
Limitations (if applicable)		Survey reference (if relating to a wider survey)		
Grid reference		Habitat parcel reference		
Condition Assessment Criteria				
A series of ten attributes, representing key physical characteristics are used for this assessment. This assessment is based on the Hedgerow Survey Handbook <sup>1</sup> and Favourable Conservation Status document <sup>2</sup> . For further clarification please refer to the Hedgerow Survey Handbook. Each attribute is assigned to one of five functional groups (A – E) and the condition of a hedgerow is assessed according to the number of attributes from these functional groups which pass or fail the 'favourable condition' criteria.				
Hedgerow favourable condition attributes				
Attributes and functional groupings (A, B, C, D and E)	Criteria - the minimum requirements for 'favourable condition'	Description	Criterion passed (Yes or No)	Notes (such as justification)
Core groups - applicable to all hedgerow types				
A1.	Height	>1.5 m average along length	The average height of woody growth estimated from base of stem to the top of the shoots, excluding any bank beneath the hedgerow, any gaps or isolated trees.  Newly laid or coppiced hedgerows are indicative of good management and pass this criterion for up to a maximum of four years (if undertaken according to good practice).  A newly planted hedgerow does not pass this criterion (unless it is >1.5 m height).	
A2.	Width	>1.5 m average along length	The average width of woody growth estimated at the widest point of the canopy, excluding gaps and isolated trees.  Outgrowths (such as blackthorn <i>Prunus spinosa</i> suckers) are only included in the width estimate when they are >0.5 m in height.  Laid, coppiced, cut and newly planted hedgerows are indicative of good management and pass this criterion for up to a maximum of four years (if undertaken according to good practice).	
B1.	Gap - hedge base	Gap between ground and base of canopy <0.5 m for >90% of length	This is the vertical 'gappiness' of the woody component of the hedgerow, and its distance from the ground to the lowest leafy growth.  Certain exceptions to this criterion are acceptable (see page 65 of the Hedgerow Survey Handbook).	
B2.	Gap - hedge canopy continuity	Gaps make up <10% of total length; and No canopy gaps >5 m	This is the horizontal 'gappiness' of the woody component of the hedgerow. Gaps are complete breaks in the woody canopy (no matter how small).  Access points and gates contribute to the overall 'gappiness' but are not subject to the >5 m criterion (as this is the typical size of a gate).	
C1.	Undisturbed ground and perennial vegetation	>1 m width of undisturbed ground with perennial herbaceous vegetation for >90% of length: · Measured from outer edge of hedgerow; and · Is present on one side of the hedgerow (at least).	This is the level of disturbance (excluding wildlife disturbance) at the base of the hedgerow.  Undisturbed ground is present for at least 90% of the hedgerow length, greater than 1 m in width and must be present along at least one side of the hedgerow.  This criterion recognises the value of the hedgerow base as a boundary habitat with the capacity to support a wide range of species. Cultivation, heavily trodden footpaths, poached ground etc. can limit available habitat niches.	
C2.	Nutrient-enriched perennial vegetation	Plant species indicative of nutrient enrichment of soils dominate <20% cover of the area of undisturbed ground.	The indicator species used are nettles <i>Urtica</i> spp., cleavers <i>Galium aparine</i> and docks <i>Rumex</i> spp. Their presence, either singly or together, does not exceed the 20% cover threshold.	
D1.	Invasive and neophyte species	>90% of the hedgerow and undisturbed ground is free of invasive non-native plant species (including those listed on Schedule 9 of WCA <sup>3</sup> ) and recently introduced species.	Recently introduced species refer to plants that have naturalised in the UK since AD 1500 (neophytes). Archaeophytes count as natives. For information on archaeophytes and neophytes see the JNCC website <sup>4</sup> , as well as the BSBI website <sup>5</sup> where the 'Online Atlas of the British and Irish Flora' <sup>6</sup> contains an up-to-date list of the status of species. For information on invasive non-native species see the GB Non-Native Secretariat website <sup>7</sup> .	

D2.	Current damage	>90% of the hedgerow or undisturbed ground is free of damage caused by human activities.	This criterion addresses damaging activities that may have led to or lead to deterioration in other attributes.  This could include evidence of pollution, piles of manure or rubble, or inappropriate management practices (e.g., excessive hedgerow cutting).		
-----	----------------	--	---	--	--

**Additional group - applicable to hedgerows with trees only**

E1.	Tree class	There is more than one age-class (or morphology) of tree present (for example: young, mature, veteran and or ancient <sup>8</sup> ), and there is on average at least one mature, ancient or veteran tree present per 20 - 50m of hedgerow.	This criterion addresses if there are a range of age-classes or morphologies which allow for replacement of trees and provide opportunities for different species.		
E2.	Tree health	At least 95% of hedgerow trees are in a healthy condition (excluding veteran features valuable for wildlife). There is little or no evidence of an adverse impact on tree health by damage from livestock or wild animals, pests or diseases, or human activity.	This criterion identifies if the trees are subject to damage which compromises the survival and health of the individual specimens.		

The hedgerow condition assessment generates a weighting (score) ranging from 1 - 3, which is used within the metric. The scores for each are set out in the tables below.

Condition categories for hedgerows without trees		
Category	Category Requirements	Metric Score
Good	No more than 2 failures in total; <b>AND</b> No more than 1 failure in any functional group.	3
Moderate	No more than 4 failures in total; <b>AND</b> Does not fail both attributes in more than one functional group (e.g. fails attributes A1, A2, B1 and C2 = Moderate condition).	2
Poor	Fails a total of more than 4 attributes; <b>OR</b> Fails both attributes in more than one functional group (e.g. fails attributes A1, A2, B1 and B2 = Poor condition).	1
<b>Score achieved:</b>		
Condition categories for hedgerows with trees		
Category	Category Requirements	Metric score
Good	No more than 2 failures in total; <b>AND</b> No more than 1 failure in any functional group.	3
Moderate	No more than 5 failures in total; <b>AND</b> Does not fail both attributes in more than one functional group (e.g., fails attributes A1, A2, B1, C2 and E1 = Moderate condition).	2
Poor	Fails a total of more than 5 attributes; <b>OR</b> Fails both attributes in more than one functional group (e.g. fails attributes A1, A2, B1 and B2 = Poor condition).	1
<b>Score achieved:</b>		
Suggested enhancement interventions to improve condition score		



C1.	Undisturbed ground and perennial vegetation	>1 m width of undisturbed ground with perennial herbaceous vegetation for >90% of length: - Measured from outer edge of hedgerow; and - Is present on one side of the hedgerow (at least).	This is the level of disturbance (excluding wildlife disturbance) at the base of the hedgerow.  Undisturbed ground is present for at least 90% of the hedgerow length, greater than 1 m in width and must be present along at least one side of the hedgerow.  This criterion recognises the value of the hedgerow base as a boundary habitat with the capacity to support a wide range of species. Cultivation, heavily trodden footpaths, poached ground etc. can limit available habitat	N															
C2.	Nutrient-enriched perennial vegetation	Plant species indicative of nutrient enrichment of soils dominate <20% cover of the area of undisturbed ground.	The indicator species used are nettles <i>Urtica</i> spp., cleavers <i>Galium aparine</i> and docks <i>Rumex</i> spp. Their presence, either singly or together, does not exceed the 20% cover threshold.	Y															
D1.	Invasive and neophyte species	>90% of the hedgerow and undisturbed ground is free of invasive non-native plant species (including those listed on Schedule 9 of WCA <sup>3</sup> ) and recently introduced species.	Recently introduced species refer to plants that have naturalised in the UK since AD 1500 (neophytes). Archaeophytes count as natives. For information on archaeophytes and neophytes see the JNCC website <sup>4</sup> , as well as the BSBI website <sup>5</sup> where the "Online Atlas of the British and Irish Flora" <sup>6</sup> contains an up-to-date list of the status of species. For information on invasive non-native species see the GB Non-Native Secretariat website <sup>7</sup> .	Y															
D2.	Current damage	>90% of the hedgerow or undisturbed ground is free of damage caused by human activities.	This criterion addresses damaging activities that may have led to or lead to deterioration in other attributes.  This could include evidence of pollution, piles of manure or rubble, or inappropriate management practices (e.g., excessive hedgerow cutting).	N															

**Additional group - applicable to hedgerows with trees only**

E1.	Tree class	There is more than one age-class (or morphology) of tree present (for example: young, mature, veteran and or ancient <sup>8</sup> ), and there is on average at least one mature, ancient or veteran tree present per 20 - 50m of hedgerow.	This criterion addresses if there are a range of age-classes or morphologies which allow for replacement of trees and provide opportunities for different species.																
E3.	Tree health	At least 95% of hedgerow trees are in a healthy condition (excluding veteran features valuable for wildlife). There is little or no evidence of an adverse impact on tree health by damage from livestock or wild animals, pests or diseases, or human activity.	This criterion identifies if the trees are subject to damage which compromises the survival and health of the individual specimens.																

The hedgerow condition assessment generates a weighting (score) ranging from 1 - 3, which is used within the metric. The scores for each are set out in the tables below.

Condition categories for hedgerows without trees		
Category	Category Requirements	Metric Score
Good	No more than 2 failures in total; <b>AND</b> No more than 1 failure in any functional group.	3
Moderate	No more than 4 failures in total; <b>AND</b> <b>Does not fail both attributes</b> in more than one functional group (e.g. fails attributes A1, A2, B1 and C2 = Moderate condition).	2
Poor	Fails a total of more than 4 attributes; <b>OR</b> <b>Fails both attributes</b> in more than one functional group (e.g. fails attributes A1, A2, B1 and B2 = Poor condition).	1
<b>Score achieved:</b>		
Condition categories for hedgerows with trees		
Category	Category Requirements	Metric score
Good	No more than 2 failures in total; <b>AND</b> No more than 1 failure in any functional group.	3
Moderate	No more than 5 failures in total; <b>AND</b> <b>Does not fail both attributes</b> in more than one functional group (e.g., fails attributes A1, A2, B1, C2 and E1 = Moderate condition).	2

Poor	Fails a total of more than 5 attributes; <b>OR</b> Fails <b>both attributes</b> in more than one functional group (e.g. fails attributes A1, A2, B1 and B2 = Poor condition).	1	
<b>Score achieved:</b>			
<b>Suggested enhancement interventions to improve condition score</b>			

**Condition Sheet: INDIVIDUAL TREES Habitat Type****Habitat Type(s)****Individual trees – Urban trees****Individual trees – Rural trees**

Complete a condition sheet for each tree or block of trees.

**Please see separate Line of trees condition sheet for a line of Rural trees.****Habitat Description****Individual trees (description applied to the urban or rural environment):**

Young trees over 7.5 cm in diameter at breast height whose canopies are not touching.

**Urban Perimeter / Linear Blocks and Groups (description applied to the urban environment only):**

Groups or stands of trees (size requirement as defined above) within and around the perimeter of urban land. This includes those along urban streets, highways, railways and canals, and also former field boundary trees incorporated into developments. Canopies must overlap continuously. Groups of urban trees that don't match the descriptions for woodland may be assessed within this category.

<b>Site name and location</b>		<b>On-site or off-site</b>	
<b>Limitations (if applicable)</b>		<b>Survey reference (if relating to a wider survey)</b>	
<b>Grid reference</b>		<b>Habitat parcel reference</b>	
<b>Condition Assessment Criteria</b>		<b>Criterion passed (Yes or No)</b>	<b>Notes (such as justification)</b>
A	The tree is a native species (or at least 70% within the block are native species).		
B	The tree canopy is predominantly continuous, with gaps in canopy cover making up <10% of total area and no individual gap being >5 m wide (individual trees automatically pass this criterion).		
C	The tree is mature (or more than 50% within the block are mature).		

D	There is little or no evidence of an adverse impact on tree health by human activities (such as vandalism, herbicide or detrimental agricultural activity). And there is no current regular pruning regime, so the trees retain >75% of expected canopy for their age range and height.		
E	Natural ecological niches for vertebrates and invertebrates are present, such as presence of deadwood, cavities, ivy or loose bark.		
F	More than 20% of the tree canopy area is oversailing vegetation beneath.		
<b>Number of criteria passed</b>			
<b>Condition Assessment Result (out of 6 criteria)</b>	<b>Condition Assessment Score</b>	<b>Score Achieved ×/✓</b>	
Passes 5 or 6 criteria	Good (3)		
Passes 3 or 4 criteria	Moderate (2)		
Passes 2 or fewer criteria	Poor (1)		
Note that 'Fairly Good and Fairly Poor' condition categories are not available for this broad habitat type.			
<b>Suggested enhancement interventions to improve condition score</b>			

Condition Sheet: INDIVIDUAL TREES Habitat Type											
Habitat Type(s)											
<b>Individual trees – Urban trees</b> <b>Individual trees – Rural trees</b> Complete a condition sheet for each tree or block of trees.											
<b>Please see separate Line of trees condition sheet for a line of Rural trees.</b>											
Habitat Description											
<b>Individual trees (description applied to the urban or rural environment):</b> Young trees over 7.5 cm in diameter at breast height whose canopies are not touching.											
<b>Urban Perimeter / Linear Blocks and Groups (description applied to the urban environment only):</b> Groups or stands of trees (size requirement as defined above) within and around the perimeter of urban land. This includes those along urban streets, highways, railways and canals, and also former field boundary trees incorporated into developments. Canopies must overlap continuously. Groups of urban trees that don't match the descriptions for woodland may be assessed within this category.											
Site name and location	On-site or off-site										
	Survey reference (if relating to a wider survey)										
Limitations (if applicable)	Habitat parcel reference										
	UT1	UT2	UT3								
Grid reference										Notes (such as justification)	
Condition Assessment Criteria										Notes (such as justification)	
Criterion passed (Yes or No)											
A	The tree is a native species (or at least 70% within the block are native species).	N	N	Y							
B	The tree canopy is predominantly continuous, with gaps in canopy cover making up <10% of total area and no individual gap being >5 m wide (individual trees automatically pass this criterion).	Y	Y	Y							
C	The tree is mature (or more than 50% within the block are mature).	N	N	N							
D	There is little or no evidence of an adverse impact on tree health by human activities (such as vandalism, herbicide or detrimental agricultural activity). And there is no current regular pruning regime, so the trees retain >75% of expected canopy for their age range and height.	Y	Y	Y							
E	Natural ecological niches for vertebrates and invertebrates are present, such as presence of deadwood, cavities, ivy or loose bark.	N	N	N							
F	More than 20% of the tree canopy area is oversailing vegetation beneath.	N	Y	Y							
Number of criteria passed		2	3	4							
Condition Assessment Result (out of 6 criteria)	Condition Assessment Score	Score Achieved x/√									
Passes 5 or 6 criteria	Good (3)										
Passes 3 or 4 criteria	Moderate (2)		2	2							
Passes 2 or fewer criteria	Poor (1)	1									
Note that 'Fairly Good and Fairly Poor' condition categories are not available for this broad habitat type.											
Suggested enhancement interventions to improve condition score											

Condition Sheet: INTERTIDAL BIOGENIC REEFS Habitat Type							
EUNIS Habitat Type(s)							
Littoral biogenic reefs - Mussels Littoral biogenic reefs - Sabellaria Artificial littoral biogenic reefs							
Habitat Description							
See the Biodiversity Metric 4.0 Technical Annex 2 and the below: <a href="#">Littoral biogenic reefs - JNCC Marine Habitat Classification</a>							
Site name and location		On-site or off-site					
Limitations (if applicable)		Survey reference (if relating to a wider survey)					
Grid reference		Habitat parcel reference					
Habitat Attributes to Record							
The following information should be recorded within the condition assessment sheet:							
<ul style="list-style-type: none"> <li>• Percentage cover of recognisable biogenic reef structures across the bed;</li> <li>• Distribution of the habitat seaward and landward limits and extent should be recorded;</li> <li>• Description of presence of typical communities and biotopes;</li> <li>• Description of species diversity and community composition;</li> <li>• Observations on coastal process functioning and any human physical modifications present;</li> <li>• Presence and abundance of non-native species;</li> <li>• Percentage cover of algal growths that could be attributed to nutrient enrichment;</li> <li>• Presence and density of non-natural structures and direct human impacts;</li> <li>• Assessment of litter;</li> <li>• Whether the habitat distribution is constrained by human modification; and</li> <li>• Water Framework Directive (WFD) classification of overlying water.</li> </ul>							
Condition Assessment Criteria							
Indicator	Good (3 points)	Moderate (2 points)	Poor (1 point)	Score per criterion	Notes (such as justification)		
<b>A Coastal processes</b>	Coastal processes are functioning naturally. No evidence of human physical modifications which are impacting the habitat.	Artificial structures present, for example groynes, that are impeding the natural movement of sediments or water, affecting up to 25% of the habitat.	Artificial structures present, for example groynes, that are impeding the natural movement of sediments or water, affecting more than 25% of the habitat.				
<b>B Presence and abundance of invasive non-native species</b>	Not more than one invasive non-native species is 'Occasional' on the SACFOR scale or is occupying more than 1% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 1 for details.	No invasive non-native species are present above 'Frequent' on the SACFOR scale or they occupy between 1-10% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 1 for details.	One or more invasive non-native species are present at an 'Abundant' level on the SACFOR scale; they occupy more than 10% of the habitat; or a high-risk species indicative of sub-optimal condition is present – GB Non-native Species Secretariat should be notified, see Footnote 1 for details.				
<b>C Water Quality</b>	No visual evidence of pollution. There are no nuisance algal growths that are likely to be attributable to nutrient enrichment. Consider seasonality of survey timing <sup>2</sup> .	Visual evidence of low to moderate levels of pollution. Elevated algal growth with increases in cover that may indicate nutrient enrichment. Consider seasonality of survey timing <sup>2</sup> .	Visual evidence of high algal growth that is indicative of nutrient enrichment. Signs of eutrophication that would impede bird feeding. Consider seasonality of survey timing <sup>2</sup> .				

D	<b>Non-natural structures and direct human impacts</b>	No evidence of impacts from direct human activities, or they occupy <1% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies 1-10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies >10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).		
E	<b>Litter (when examining a beach strandline / mean high water line or intertidal rocky shore)</b>	Following the Marine Conservation Society (MCS) beach litter survey method, the number of items of litter does not exceed 0.0036 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to up to 20 items per person per 100 m per hour. See Footnote 3 for details.	Following the MCS beach litter survey method, the number of items of litter does not exceed 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to between 21 and 47 items of litter per person per 100 m per hour. See Footnote 3 for details.	Following the MCS beach litter survey method, the number of items of litter exceeds 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to more than 47 items of litter per person per 100 m per hour. See Footnote 3 for details.		
<b>Total Score (out of a possible 15)</b>						
<b>Condition Assessment Result</b>					<b>Result Achieved</b>	
<b>TOTAL SCORE 12-15 (75-100%) = GOOD CONDITION</b>						
<b>TOTAL SCORE 8-11 (50-75%) = MODERATE CONDITION</b>						
<b>TOTAL SCORE 5-7 (0-50%) = POOR CONDITION</b>						
<b>Suggested enhancement interventions to improve condition score</b>						
<b>Footnotes</b>						

Condition Sheet: INTERTIDAL BIOGENIC REEFS Habitat Type																			
EUNIS Habitat Type(s)																			
Littoral biogenic reefs - Mussels																			
Littoral biogenic reefs - Sabellaria																			
Artificial littoral biogenic reefs																			
Habitat Description																			
Site name and location		On-site or off-site																	
Limitations (if applicable)		Survey reference (if relating to a wider survey)																	
See the Biodiversity Metric 4.0 Technical Annex 2 and the below:																			
<a href="#">Littoral biogenic reefs - JNCC Marine Habitat Classification</a>																			
Habitat Attributes to Record																			
The following information should be recorded within the condition assessment sheet:											Habitat parcel reference								
<ul style="list-style-type: none"> <li>Percentage cover of recognisable biogenic reef structures across the bed;</li> <li>Distribution of the habitat seaward and landward limits and extent should be recorded;</li> <li>Description of presence of typical communities and biotopes;</li> <li>Description of species diversity and community composition;</li> <li>Observations on coastal process functioning and any human physical modifications present;</li> </ul>																			
<ul style="list-style-type: none"> <li>Presence and abundance of non-native species;</li> <li>Percentage cover of algal growths that could be attributed to nutrient enrichment;</li> <li>Presence and density of non-natural structures and direct human impacts;</li> <li>Assessment of litter;</li> <li>Whether the habitat distribution is constrained by human modification; and</li> <li>Water Framework Directive (WFD) classification of overlying water.</li> </ul>											Grid reference								
Condition Assessment Criteria																			
Indicator	Good (3 points)	Moderate (2 points)	Poor (1 point)	Score per criterion										Notes (such as justification)					
A Coastal processes	Coastal processes are functioning naturally. No evidence of human physical modifications which are impacting the habitat.	Artificial structures present, for example groynes, that are impeding the natural movement of sediments or water, affecting up to 25% of the habitat.	Artificial structures present, for example groynes, that are impeding the natural movement of sediments or water, affecting more than 25% of the habitat.																
B Presence and abundance of invasive non-native species	Not more than one invasive non-native species is 'Occasional' on the SACFOR scale or is occupying more than 1% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 1 for details.	No invasive non-native species are present above 'Frequent' on the SACFOR scale or they occupy between 1-10% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 1 for details.	One or more invasive non-native species are present at an 'Abundant' level on the SACFOR scale; they occupy more than 10% of the habitat; or a high-risk species indicative of sub-optimal condition is present – GB Non-native Species Secretariat should be notified, see Footnote 1 for details.																
C Water Quality	No visual evidence of pollution. There are no nuisance algal growths that are likely to be attributable to nutrient enrichment. Consider seasonality of survey timing <sup>2</sup> .	Visual evidence of low to moderate levels of pollution. Elevated algal growth with increases in cover that may indicate nutrient enrichment. Consider seasonality of survey timing <sup>2</sup> .	Visual evidence of high algal growth that is indicative of nutrient enrichment. Signs of eutrophication that would impede bird feeding. Consider seasonality of survey timing <sup>2</sup> .																
D Non-natural structures and direct human impacts	No evidence of impacts from direct human activities, or they occupy <1% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies 1-10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies >10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).																
E Litter (when examining a beach strandline / mean high water line or intertidal rocky shore)	Following the Marine Conservation Society (MCS) beach litter survey method, the number of items of litter does not exceed 0.0036 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to up to 20 items per person per 100 m per hour. See Footnote 3 for details.	Following the MCS beach litter survey method, the number of items of litter does not exceed 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to between 21 and 47 items of litter per person per 100 m per hour. See Footnote 3 for details.	Following the MCS beach litter survey method, the number of items of litter exceeds 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to more than 47 items of litter per person per 100 m per hour. See Footnote 3 for details.																
<b>Total Score (out of a possible 15)</b>																			
Condition Assessment Result											Result Achieved								
<b>TOTAL SCORE 12-15 (75-100%) = GOOD CONDITION</b>																			

<b>TOTAL SCORE 8-11 (50-75%) = MODERATE CONDITION</b>		
<b>TOTAL SCORE 5-7 (0-50%) = POOR CONDITION</b>		
<b>Suggested enhancement interventions to improve condition score</b>		
<b>Footnotes</b>		

Condition Sheet: INTERTIDAL HARD STRUCTURES Habitat Type					
Artificial Habitat Type(s)					
Intertidal hard structures - Artificial hard structures Intertidal hard structures - Artificial features of hard structures Intertidal hard structures - Artificial hard structures with integrated greening of grey infrastructure (IGGI)					
Site name and location		On-site or off-site			
Limitations (if applicable)		Survey reference (if relating to a wider survey)			
Grid reference		Habitat parcel reference			
Habitat Description					
See the Biodiversity Metric 4.0 Technical Annex 2.					
Habitat Attributes to Record					
The following information should be recorded within the condition assessment sheet:					
<ul style="list-style-type: none"> <li>• Description of presence of typical communities and biotopes;</li> <li>• Description of species diversity and community composition;</li> <li>• Presence and abundance of non-native species;</li> <li>• Observations on coastal process functioning and any human physical modifications present;</li> <li>• Percentage cover of algal growths that could be attributed to nutrient enrichment;</li> <li>• Water Framework Directive (WFD) classification of overlying water; and</li> <li>• Assessment of litter.</li> </ul>					
Condition Assessment Criteria					
Indicator	Good (3 points)	Moderate (2 points)	Poor (1 point)	Score per criterion	Notes (such as justification)
<b>A Coastal processes</b>	Coastal processes are functioning naturally. No evidence of human physical modifications which are clearly impacting the habitat.	Artificial structures present, for example groynes that are impeding the natural movement of sediments or water, affecting up to 25% of the habitat.	Artificial structures present, for example groynes that are impeding the natural movement of sediments or water, affecting more than 25% of the habitat.		
<b>B Presence and abundance of invasive non-native species</b>	Not more than one invasive non-native species is 'Occasional' on the SACFOR scale or is occupying more than 1% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 1 for details.	No invasive non-native species are present above 'Frequent' on the SACFOR scale or they occupy between 1-10% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 1 for details.	One or more invasive non-native species present at an 'Abundant' level on the SACFOR scale; they occupy more than 10% of the habitat; or a high-risk species indicative of sub-optimal condition is present – GB Non-native Species Secretariat should be notified, see Footnote 1 for details.		
<b>C Water Quality</b>	No visual evidence of pollution. There are no nuisance algal growths that are likely to be attributable to nutrient enrichment. Consider seasonality of survey timing <sup>2</sup> .	Visual evidence of low to moderate levels of pollution. Elevated algal growth with increases in cover that may indicate nutrient enrichment. Consider seasonality of survey timing <sup>2</sup> .	Visual evidence of high algal growth that is indicative of nutrient enrichment. Signs of eutrophication that would impede bird feeding. Consider seasonality of survey timing <sup>2</sup> .		

D	<b>Litter (when examining a beach strandline, mean high water line or intertidal rocky shore)</b>	Following the Marine Conservation Society (MCS) beach litter survey method, the number of items of litter does not exceed 0.0036 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to up to 20 items per person per 100 m per hour. See Footnote 3 for details.	Following the MCS beach litter survey method, the number of items of litter does not exceed 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to between 21 and 47 items of litter per person per 100 m per hour. See Footnote 3 for details.	Following the MCS beach litter survey method, the number of items of litter exceeds 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to more than 47 items of litter per person per 100 m per hour. See Footnote 3 for details.		
E	<b>Amount of colonisation</b>	More than three different communities of flora or fauna present.	Two or three different communities of flora or fauna present.	One or no communities of flora or fauna present.		
<b>Total Score (out of a possible 15)</b>						
<b>Condition Assessment Result</b>					<b>Result Achieved</b>	
<b>TOTAL SCORE 12-15 (75-100%) = GOOD CONDITION</b>						
<b>TOTAL SCORE 8-11 (50-75%) = MODERATE CONDITION</b>						
<b>TOTAL SCORE 5-7 (0-50%) = POOR CONDITION</b>						
<b>Suggested enhancement interventions to improve condition score</b>						

Condition Sheet: INTERTIDAL HARD STRUCTURES Habitat Type																	
Artificial Habitat Type(s)																	
Intertidal hard structures - Artificial hard structures																	
Intertidal hard structures - Artificial features of hard structures																	
Intertidal hard structures - Artificial hard structures with integrated greening of grey infrastructure (IGGI)																	
Site name and location		On-site or off-site															
Limitations (if applicable)		Survey reference (if relating to a wider survey)															
Habitat Description																	
See the Biodiversity Metric 4.0 Technical Annex 2.																	
Habitat Attributes to Record																	
The following information should be recorded within the condition assessment sheet:										Habitat parcel reference							
<ul style="list-style-type: none"> <li>• Description of presence of typical communities and biotopes;</li> <li>• Description of species diversity and community composition;</li> <li>• Presence and abundance of non-native species;</li> <li>• Observations on coastal process functioning and any human physical modifications present;</li> </ul>																	
<ul style="list-style-type: none"> <li>• Percentage cover of algal growths that could be attributed to nutrient enrichment;</li> <li>• Water Framework Directive (WFD) classification of overlying water; and</li> <li>• Assessment of litter.</li> </ul>										Grid reference							
Condition Assessment Criteria																	
Indicator		Good (3 points)		Moderate (2 points)		Poor (1 point)		Score per criterion						Notes (such as justification)			
A	Coastal processes	Coastal processes are functioning naturally. No evidence of human physical modifications which are clearly impacting the habitat.		Artificial structures present, for example groynes that are impeding the natural movement of sediments or water, affecting up to 25% of the habitat.		Artificial structures present, for example groynes that are impeding the natural movement of sediments or water, affecting more than 25% of the habitat.											
		Not more than one invasive non-native species is 'Occasional' on the SACFOR scale or is occupying more than 1% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 1 for details.		No invasive non-native species are present above 'Frequent' on the SACFOR scale or they occupy between 1-10% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 1 for details.		One or more invasive non-native species present at an 'Abundant' level on the SACFOR scale; they occupy more than 10% of the habitat; or a high-risk species indicative of sub-optimal condition is present – GB Non-native Species Secretariat should be notified, see Footnote 1 for details.											
C	Water Quality	No visual evidence of pollution. There are no nuisance algal growths that are likely to be attributable to nutrient enrichment. Consider seasonality of survey timing <sup>2</sup> .		Visual evidence of low to moderate levels of pollution. Elevated algal growth with increases in cover that may indicate nutrient enrichment. Consider seasonality of survey timing <sup>2</sup> .		Visual evidence of high algal growth that is indicative of nutrient enrichment. Signs of eutrophication that would impede bird feeding. Consider seasonality of survey timing <sup>2</sup> .											
		Following the Marine Conservation Society (MCS) beach litter survey method, the number of items of litter does not exceed 0.0036 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to up to 20 items per person per 100 m per hour. See Footnote 3 for details.		Following the MCS beach litter survey method, the number of items of litter does not exceed 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to between 21 and 47 items of litter per person per 100 m per hour. See Footnote 3 for details.		Following the MCS beach litter survey method, the number of items of litter exceeds 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to more than 47 items of litter per person per 100 m per hour. See Footnote 3 for details.											
E	Amount of colonisation	More than three different communities of flora or fauna present.		Two or three different communities of flora or fauna present.		One or no communities of flora or fauna present.											
<b>Total Score (out of a possible 15)</b>																	
Condition Assessment Result								Result Achieved									
TOTAL SCORE 12-15 (75-100%) = GOOD CONDITION																	
TOTAL SCORE 8-11 (50-75%) = MODERATE CONDITION																	
TOTAL SCORE 5-7 (0-50%) = POOR CONDITION																	
Suggested enhancement interventions to improve condition score																	

Condition Sheet: INTERTIDAL SEAGRASS Habitat Type					
Habitat Type(s)					
Intertidal sediment - Littoral seagrass Intertidal sediment - Littoral seagrass - on peat, clay or chalk Intertidal sediment - Artificial littoral seagrass					
Site name and location		On-site or off-site			
Limitations (if applicable)		Survey reference (if relating to a wider survey)			
Grid reference		Habitat parcel reference			
Habitat Description					
See the Biodiversity Metric 4.0 Technical Annex 2 and the below: <a href="#">JNCC littoral seagrass bed habitat description</a>					
Habitat Attributes to Record					
The following information should be recorded within the condition assessment sheet:					
<ul style="list-style-type: none"> <li>• Percentage cover of seagrass across the bed;</li> <li>• Distribution of the seagrass landward, seaward and extent should be recorded;</li> <li>• Description of presence of typical communities and biotopes;</li> <li>• Description of species diversity and community composition;</li> <li>• Observations on coastal process functioning and any human physical modifications present;</li> <li>• Presence and abundance of non-native species;</li> <li>• Percentage cover of algal growths that could be attributed to nutrient enrichment;</li> <li>• Water Framework Directive (WFD) classification of overlying water;</li> <li>• Presence and density of non-natural structures and direct human impacts;</li> <li>• Assessment of litter; and</li> <li>• Evidence of visible rhizomes.</li> </ul>					
Condition Assessment Criteria					
Indicator	Good (3 points)	Moderate (2 points)	Poor (1 point)	Score per criterion	Notes (such as justification)
<b>A Coastal processes</b>	Coastal processes are functioning naturally. No evidence of human physical modifications which are clearly impacting the habitat.	Artificial structures present, for example groynes, that are impeding the natural movement of sediments or water, affecting up to 25% of the habitat.	Artificial structures present, for example groynes, that are impeding the natural movement of sediments or water, affecting more than 25% of the habitat.		
<b>B Presence and abundance of invasive non-native species</b>	Not more than one invasive non-native species is 'Occasional' on the SACFOR scale or is occupying more than 1% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 1 for details.	No invasive non-native species are present above 'Frequent' on the SACFOR scale or they occupy between 1-10% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 1 for list.	One or more invasive non-native species present at an 'Abundant' level on the SACFOR scale; they occupy more than 10% of the habitat; or a high-risk species indicative of sub-optimal condition is present – GB Non-native Species Secretariat should be notified, see Footnote 1 for details.		

C	<b>Water Quality</b>	No visual evidence of pollution. There are no nuisance algal growths that are likely to be attributable to nutrient enrichment. Consider seasonality of survey timing <sup>2</sup> .	Visual evidence of low to moderate levels of pollution. Elevated algal growth with increases in cover that may indicate nutrient enrichment. Consider seasonality of survey timing <sup>2</sup> .	Visual evidence of high algal growth that is indicative of nutrient enrichment. Signs of eutrophication that would impede bird feeding. Consider seasonality of survey timing <sup>2</sup> .		
D	<b>Non-natural structures and direct human impacts</b>	No evidence of impacts from direct human activities, or they occupy <1% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies 1-10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies >10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).		
E	<b>Litter (when examining a beach strandline, mean high water line or intertidal rocky shore)</b>	Following the Marine Conservation Society (MCS) beach litter survey method, the number of items of litter does not exceed 0.0036 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to up to 20 items per person per 100 m per hour. See Footnote 3 for details.	Following the MCS beach litter survey method, the number of items of litter does not exceed 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to between 21 and 47 items of litter per person per 100 m per hour. See Footnote 3 for details.	Following the MCS beach litter survey method, the number of items of litter exceeds 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to more than 47 items of litter per person per 100 m per hour. See Footnote 3 for details.		
<b>Total score (out of a possible 15)</b>						
<b>Condition Assessment Result</b>					<b>Result Achieved</b>	
<b>TOTAL SCORE 12 - 15 (75-100%) = GOOD CONDITION</b>						
<b>TOTAL SCORE 8 - 11 (50-75%) = MODERATE CONDITION</b>						
<b>TOTAL SCORE 5 - 7 (0-50%) = POOR CONDITION</b>						
<b>Suggested enhancement interventions to improve condition score</b>						
<b>Footnotes</b>						

Condition Sheet: INTERTIDAL SEAGRASS Habitat Type												
Habitat Type(s)												
Intertidal sediment - Littoral seagrass												
Intertidal sediment - Littoral seagrass - on peat, clay or chalk												
Intertidal sediment - Artificial littoral seagrass												
Site name and location					On-site or off-site							
Limitations (if applicable)					Survey reference (if relating to a wider survey)							
Habitat Description												
See the Biodiversity Metric 4.0 Technical Annex 2 and the below: <a href="#">JNCC littoral seagrass bed habitat description</a>												
Habitat Attributes to Record												
The following information should be recorded within the condition assessment sheet:					Habitat parcel reference							
<ul style="list-style-type: none"> <li>Percentage cover of seagrass across the bed;</li> <li>Distribution of the seagrass landward, seaward and extent should be recorded;</li> <li>Description of presence of typical communities and biotopes;</li> <li>Description of species diversity and community composition;</li> <li>Observations on coastal process functioning and any human physical modifications present;</li> <li>Presence and abundance of non-native species;</li> <li>Percentage cover of algal growths that could be attributed to nutrient enrichment;</li> <li>Water Framework Directive (WFD) classification of overlying water;</li> <li>Presence and density of non-natural structures and direct human impacts;</li> <li>Assessment of litter; and</li> <li>Evidence of visible rhizomes.</li> </ul>												
					Grid reference							
Condition Assessment Criteria												
Indicator	Good (3 points)	Moderate (2 points)	Poor (1 point)	Score per criterion					Notes (such as justification)			
A Coastal processes	Coastal processes are functioning naturally. No evidence of human physical modifications which are clearly impacting the habitat.	Artificial structures present, for example groynes, that are impeding the natural movement of sediments or water, affecting up to 25% of the habitat.	Artificial structures present, for example groynes, that are impeding the natural movement of sediments or water, affecting more than 25% of the habitat.									
B Presence and abundance of invasive non-native species	Not more than one invasive non-native species is 'Occasional' on the SACFOR scale or is occupying more than 1% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 1 for details.	No invasive non-native species are present above 'Frequent' on the SACFOR scale or they occupy between 1-10% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 1 for list.	One or more invasive non-native species present at an 'Abundant' level on the SACFOR scale; they occupy more than 10% of the habitat; or a high-risk species indicative of sub-optimal condition is present – GB Non-native Species Secretariat should be notified, see Footnote 1 for details.									
C Water Quality	No visual evidence of pollution. There are no nuisance algal growths that are likely to be attributable to nutrient enrichment. Consider seasonality of survey timing <sup>2</sup> .	Visual evidence of low to moderate levels of pollution. Elevated algal growth with increases in cover that may indicate nutrient enrichment. Consider seasonality of survey timing <sup>2</sup> .	Visual evidence of high algal growth that is indicative of nutrient enrichment. Signs of eutrophication that would impede bird feeding. Consider seasonality of survey timing <sup>2</sup> .									
D Non-natural structures and direct human impacts	No evidence of impacts from direct human activities, or they occupy <1% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies 1-10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies >10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).									
E Litter (when examining a beach strandline, mean high water line or intertidal rocky shore)	Following the Marine Conservation Society (MCS) beach litter survey method, the number of items of litter does not exceed 0.0036 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to up to 20 items per person per 100 m per hour. See Footnote 3 for details.	Following the MCS beach litter survey method, the number of items of litter does not exceed 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to between 21 and 47 items of litter per person per 100 m per hour. See Footnote 3 for details.	Following the MCS beach litter survey method, the number of items of litter exceeds 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to more than 47 items of litter per person per 100 m per hour. See Footnote 3 for details.									
<b>Total Score (out of a possible 15)</b>												
Condition Assessment Result				Result Achieved								
<b>TOTAL SCORE 12 - 15 (75-100%) = GOOD CONDITION</b>												
<b>TOTAL SCORE 8 - 11 (50-75%) = MODERATE CONDITION</b>												
<b>TOTAL SCORE 5 - 7 (0-50%) = POOR CONDITION</b>												
Suggested enhancement interventions to improve condition score												
Footnotes												

Condition Sheet: INTERTIDAL SEDIMENT Habitat Type						
<b>Habitat Type(s)</b>						
Littoral sand Littoral muddy sand Littoral mud Littoral mixed sediments Features of littoral sediment Artificial littoral coarse sediment Artificial littoral mixed sediments Artificial littoral mud Artificial littoral muddy sand Artificial littoral sand						
<b>Site name and location</b>		<b>On-site or off-site</b>				
<b>Limitations (if applicable)</b>		<b>Survey reference (if relating to a wider survey)</b>				
<b>Central grid reference of habitat</b>		<b>Habitat parcel reference</b>				
<b>Habitat Description</b>						
See the Biodiversity Metric 4.0 Technical Annex 2 and the below: <a href="#">EUNIS littoral sediment description</a>						
<b>Habitat Attributes to Record</b>						
The following information should be recorded within the condition assessment sheet: <ul style="list-style-type: none"> <li>• Description of sediment character;</li> <li>• Description of presence of typical communities and biotopes;</li> <li>• Description of species diversity and community composition;</li> <li>• Observations on coastal process functioning and any human physical modifications present;</li> <li>• Observations on transitions to other habitats;</li> <li>• Assessment of litter;</li> <li>• Percentage cover of algal growths that could be attributed to nutrient enrichment;</li> <li>• Water Framework Directive (WFD) classification of overlying water; and</li> <li>• Description of zonation.</li> </ul>						
<b>Condition Assessment Criteria</b>						
Indicator		Good (3 points)	Moderate (2 points)	Poor (1 point)	Score per criterion	Notes (such as justification)
A	<b>Coastal processes</b>	Coastal processes are functioning naturally. No evidence of human physical modifications which are clearly impacting the habitat.	Artificial structures present e.g. groynes, that are impeding the natural movement of sediments or water, affecting up to 25% of the habitat.	Artificial structures present e.g. groynes, that are impeding the natural movement of sediments or water, affecting more than 25% of the habitat.		
B	<b>Presence and abundance of invasive non-native species</b>	Not more than one invasive non-native species is 'Occasional' on the SACFOR scale or is occupying more than 1% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 1 for details.	No invasive non-native species are present above 'Frequent' on the SACFOR scale or they occupy between 1-10% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 1 for details.	One or more invasive non-native species are present at an 'Abundant' level on the SACFOR scale; they occupy more than 10% of the habitat; or a high-risk species indicative of sub-optimal condition is present – GB Non-native Species Secretariat should be notified, see Footnote 1 for details.		

C	<b>Water Quality</b>	No visual evidence of pollution. There are no nuisance algal growths that are likely to be attributable to nutrient enrichment. Consider seasonality of survey timing <sup>2</sup> .	Visual evidence of low to moderate levels of pollution. Elevated algal growth with increases in cover that may indicate nutrient enrichment. Consider seasonality of survey timing <sup>2</sup> .	Visual evidence of high algal growth that is indicative of nutrient enrichment. Signs of eutrophication that would impede bird feeding. Consider seasonality of survey timing <sup>2</sup> .		
D	<b>Non-natural structures and direct human impacts</b>	No evidence of impacts from direct human activities, or they occupy <1% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies 1-10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies >10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).		
E	<b>Litter (when examining a beach strandline, mean high water line or intertidal rocky shore)</b>	Following the Marine Conservation Society (MCS) beach litter survey method, the number of items of litter does not exceed 0.0036 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to up to 20 items per person per 100 m per hour. See Footnote 3 for details.	Following the MCS beach litter survey method, the number of items of litter does not exceed 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to between 21 and 47 items of litter per person per 100 m per hour. See Footnote 3 for details.	Following the MCS beach litter survey method, the number of items of litter exceeds 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to more than 47 items of litter per person per 100 m per hour. See Footnote 3 for details.		
<b>Total Score (out of a possible 15)</b>						
<b>Condition Assessment Result</b>					<b>Result Achieved</b>	
<b>TOTAL SCORE 12-15 (75-100%) = GOOD CONDITION</b>						
<b>TOTAL SCORE 8-11 (50-75%) = MODERATE CONDITION</b>						
<b>TOTAL SCORE 5-7 (0-50%) = POOR CONDITION</b>						
<b>Suggested enhancement interventions to improve condition score</b>						
<b>Footnotes</b>						



Suggested enhancement interventions to improve condition score

Footnotes

Condition Sheet: LAKE Habitat Type			
<b>Habitat Type(s)</b>			
Lakes - Aquifer fed naturally fluctuating waterbodies Lakes - Ornamental lake or pond [Use this condition sheet for Ornamental lakes, or use Pond condition sheet for Ornamental ponds and pools] Lakes - High alkalinity lakes Lakes - Low alkalinity lakes Lakes - Marl lakes Lakes - Moderate alkalinity lakes Lakes - Peat lakes Lakes - Reservoirs Lakes - Temporary lakes ponds and pools (H3170) [Use this condition sheet for Temporary lakes, or use Pond condition sheet for Temporary ponds and pools]			
<b>Habitat Description</b>			
See Water Framework Directive:			
<a href="#">WFD Lakes typologies description</a>			
For 'Aquifer fed naturally fluctuating waterbodies', 'Reservoirs' and 'Temporary lakes, ponds and pools' see UK Habitat Classification:			
<a href="#">UKHab</a>			
<b>Condition Assessment Criteria</b>			
The Freshwater Biological Association 'Habitat Naturalness Assessment' is used to assess the condition of lakes. Scores for four attributes (physical, hydrological, chemical, and biological naturalness) are averaged to generate an overall 'habitat naturalness assessment score' which can then be translated into a condition score for use in the metric (see below).			
There are other elements considered in the lake naturalness assessment, but these are not included when calculating the condition assessment score.			
Details of the methodology for assessing naturalness of lakes are available at: <a href="http://priorityhab.wpengine.com/contribute/">http://priorityhab.wpengine.com/contribute/</a>			
The key documents are: <a href="#">Lake naturalness assessment – guidance document (PDF)</a> <a href="#">Annex I – Printable lake naturalness survey form to use in field (PDF)</a> <a href="#">Annex II – Physical naturalness photographs (PDF)</a> <a href="#">Annex-III - Hydrological naturalness photographs (PDF)</a> <a href="#">Annex IV – Chemical naturalness photographs (PDF)</a> <a href="#">Annex V – Plant functional group photographs (PDF)</a> <a href="#">Annex VI – Further species recording (PDF)</a>			
We encourage recording of data on lakes on the Freshwater Biological Association 'Habitat Naturalness Assessment' website portal: <a href="#">Contribute data – Discovering Priority Habitats in England (wpengine.com)</a>			
<b>Site name and location</b>		<b>On-site or off-site</b>	
<b>Limitations (if applicable)</b>		<b>Survey reference (if relating to a wider survey)</b>	
<b>Grid reference</b>		<b>Habitat parcel reference</b>	
<b>Average 'Habitat Naturalness Assessment' Class</b>	<b>Condition Assessment Score</b>	<b>Score Achieved</b>	
1 Natural	Good (3)		
2	Fairly good (2.5)		
3	Moderate (2)		
4	Fairly poor (1.5)		
5 Least natural	Poor (1)		
<b>Suggested enhancement interventions to improve condition score</b>			

Condition Sheet: LAKE Habitat Type										
<b>Habitat Type(s)</b>										
Lakes - Aquifer fed naturally fluctuating waterbodies Lakes - Ornamental lake or pond [Use this condition sheet for Ornamental lakes, or use Pond condition sheet for Ornamental ponds and pools] Lakes - High alkalinity lakes Lakes - Low alkalinity lakes Lakes - Marl lakes Lakes - Moderate alkalinity lakes Lakes - Peat lakes Lakes - Reservoirs Lakes - Temporary lakes ponds and pools (H3170) [Use this condition sheet for Temporary lakes, or use Pond condition sheet for Temporary ponds and pools]										
<b>Habitat Description</b>										
See Water Framework Directive: <a href="#">WFD Lakes typologies description</a>										
For 'Aquifer fed naturally fluctuating waterbodies', 'Reservoirs' and 'Temporary lakes, ponds and pools' see UK Habitat Classification: <a href="#">UKHab</a>										
<b>Condition Assessment Criteria</b>										
The Freshwater Biological Association 'Habitat Naturalness Assessment' is used to assess the condition of lakes. Scores for four attributes (physical, hydrological, chemical, and biological naturalness) are averaged to generate an overall 'habitat naturalness assessment score' which can then be translated into a condition score for use in the metric (see below).										
There are other elements considered in the lake naturalness assessment, but these are not included when calculating the condition assessment score.										
Details of the methodology for assessing naturalness of lakes are available at: <a href="http://priorityhab.wpengine.com/contribute/">http://priorityhab.wpengine.com/contribute/</a>										
The key documents are: <a href="#">Lake naturalness assessment – guidance document (PDF)</a> <a href="#">Annex I – Printable lake naturalness survey form to use in field (PDF)</a> <a href="#">Annex II – Physical naturalness photographs (PDF)</a> <a href="#">Annex - III Hydrological naturalness photographs (PDF)</a> <a href="#">Annex IV – Chemical naturalness photographs (PDF)</a> <a href="#">Annex V – Plant functional group photographs (PDF)</a> <a href="#">Annex VI – Further species recording (PDF)</a>										
We encourage recording of data on lakes on the Freshwater Biological Association 'Habitat Naturalness Assessment' website portal: <a href="#">Contribute data – Discovering Priority Habitats in England (wpengine.com)</a>										
<b>Site name and location</b>	<b>On-site or off-site</b>									
	<b>Survey reference (if relating to a wider survey)</b>									
	<b>Habitat parcel reference</b>									
<b>Limitations (if applicable)</b>	<b>Grid reference</b>									
<b>Average 'Habitat Naturalness Assessment' Class</b>	<b>Condition Assessment Score</b>	<b>Score Achieved</b>								
1 Natural	Good (3)									
2	Fairly good (2.5)									
3	Moderate (2)									
4	Fairly poor (1.5)									
5 Least natural	Poor (1)									
<b>Suggested enhancement interventions to improve condition score</b>										

Condition Sheet: LIMESTONE PAVEMENT Habitat Type			
UK Habitat Classification (UKHab) Habitat Type			
Sparsely vegetated land - Limestone pavement			
Habitat Description			
<a href="#">ukhab – UK Habitat Classification</a>			
Site name and location		On-site or off-site	
Limitations (if applicable)		Survey reference (if relating to a wider survey)	
Grid reference		Habitat parcel reference	
Condition Assessment Criteria		Criterion passed (Yes or No)	Notes (such as justification)
A	Cover of typical emergent pavement flora and clint-top vegetation accounts for at least 25% of total vegetation cover (the area excluding bare rock).		
B	Cover of invasive non-native species (as listed on Schedule 9 of WCA) <sup>1</sup> is less than 1%. Non-native species in this instance include beech <i>Fagus sylvatica</i> and sycamore <i>Acer pseudoplatanus</i> <sup>2</sup> .		
C	Species indicative of sub-optimal condition <sup>3</sup> make up less than 1% of vegetated ground cover.		
D	Less than 25% of live leaves (broadleaved plants), fronds (ferns) or shoots (dwarf shrubs) show signs of grazing or browsing.		
E	There is no evidence of damage to the pavement surface.		
Number of criteria passed			
Condition Assessment Result (out of 5 criteria)	Condition Assessment Score	Criterion passed (Yes or No)	
Passes 5 criteria	Good (3)		
Passes 4 criteria	Moderate (2)		
Passes 3 or fewer criteria	Poor (1)		
Suggested enhancement interventions to improve condition score			
Footnotes			
<p><b>Footnote 1</b> – Wildlife and Countryside Act 1981 (as amended).</p> <p><b>Footnote 2</b> – Assess this for each distinct habitat parcel. If the distribution of invasive non-native species varies across the habitat, split into parcels accordingly, applying a buffer zone around the invasive non-native species with a size relative to its risk of spread into adjacent habitat, using professional judgement.</p> <p><b>Footnote 3</b> – Species indicative of sub-optimal condition for this habitat type include: perennial rye-grass <i>Lolium perenne</i>, false oat-grass <i>Arrhenatherum elatius</i>, crested dog's-tail <i>Cynosurus cristatus</i>, bramble <i>Rubus fruticosus</i> agg., creeping thistle <i>Cirsium arvense</i>, spear thistle <i>Cirsium vulgare</i>, curled dock <i>Rumex crispus</i>, broad-leaved dock <i>Rumex obtusifolius</i>, common ragwort <i>Jacobaea vulgaris</i>, common nettle <i>Urtica dioica</i>, other pernicious perennial species. There may be additional relevant species local to the region and or site.</p>			

Condition Sheet: LIMESTONE PAVEMENT Habitat Type											
UK Habitat Classification (UKHab) Habitat Type											
Sparsely vegetated land - Limestone pavement											
Habitat Description											
<a href="#">ukhab – UK Habitat Classification</a>											
Site name and location	On-site or off-site										
	Survey reference (if relating to a wider survey)										
Limitations (if applicable)	Habitat parcel reference										
	Grid reference										
Condition Assessment Criteria											Notes (such as justification)
			Criterion passed (Yes or No)								
A	Cover of typical emergent pavement flora and clint-top vegetation accounts for at least 25% of total vegetation cover (the area excluding bare rock).										
B	Cover of invasive non-native species (as listed on Schedule 9 of WCA) <sup>1</sup> is less than 1%. Non-native species in this instance include beech <i>Fagus sylvatica</i> and sycamore <i>Acer pseudoplatanus</i> <sup>2</sup> .										
C	Species indicative of sub-optimal condition <sup>3</sup> make up less than 1% of vegetated ground cover.										
D	Less than 25% of live leaves (broadleaved plants), fronds (ferns) or shoots (dwarf shrubs) show signs of grazing or browsing.										
E	There is no evidence of damage to the pavement surface.										
Number of criteria passed											
Condition Assessment Result (out of 5 criteria)	Condition Assessment Score	Score Achieved ×/✓									
Passes 5 criteria	Good (3)										
Passes 4 criteria	Moderate (2)										
Passes 3 or fewer criteria	Poor (1)										
Suggested enhancement interventions to improve condition score											
Footnotes											
<p><b>Footnote 1</b> – Wildlife and Countryside Act 1981 (as amended).</p> <p><b>Footnote 2</b> – Assess this for each distinct habitat parcel. If the distribution of invasive non-native species varies across the habitat, split into parcels accordingly, applying a buffer zone around the invasive non-native species with a size relative to its risk of spread into adjacent habitat, using professional judgement.</p> <p><b>Footnote 3</b> – Species indicative of sub-optimal condition for this habitat type include: perennial rye-grass <i>Lolium perenne</i>, false oat-grass <i>Arrhenatherum elatius</i>, crested dog's-tail <i>Cynosurus cristatus</i>, bramble <i>Rubus fruticosus</i> agg., creeping thistle <i>Cirsium arvense</i>, spear thistle <i>Cirsium vulgare</i>, curled dock <i>Rumex crispus</i>, broad-leaved dock <i>Rumex obtusifolius</i>, common ragwort <i>Jacobaea vulgaris</i>, common nettle <i>Urtica dioica</i>, other pernicious perennial species. There may be additional relevant species local to the region and or site.</p>											

Condition Sheet: LINE OF TREES Habitat Type			
Habitat Type(s)			
<b>Line of trees</b> <b>Line of trees – associated with bank or ditch</b> <b>Ecologically valuable line of trees</b> <b>Ecologically valuable line of trees – associated with bank or ditch</b>			
Habitat Description			
<p>See the Biodiversity Metric 4.0 User Guide Section 9.</p> <p>This assessment is based on the Hedgerow Survey Handbook<sup>1</sup>. For further clarifications please refer to the Handbook.</p> <p>Where ancient and veteran trees are present within the line of trees, see Footnote 2 for standing advice.</p>			
Site name and location		On-site or off-site	
Limitations (if applicable)		Survey reference (if relating to a wider survey)	
Grid reference		Habitat parcel reference	
Condition Assessment Criteria		Criterion passed (Yes or No)	Notes (such as justification)
A	At least 70% of trees are native species.		
B	Tree canopy is predominantly continuous with gaps in canopy cover making up <10% of total area and no individual gap being >5 m wide.		
C	One or more trees has veteran features and or natural ecological niches for vertebrates and invertebrates, such as presence of standing and attached deadwood, cavities, ivy or loose bark.		

D	There is an undisturbed naturally-vegetated strip of at least 6 m on both sides to protect the line of trees from farming and other human activities (excluding grazing). Where veteran trees are present, root protection areas should follow standing advice <sup>2</sup> .		
E	At least 95% of the trees are in a healthy condition (deadwood or veteran features valuable for wildlife are excluded from this). There is little or no evidence of an adverse impact on tree health by damage from livestock or wild animals, pests or diseases, or human activity.		
			<b>Number of criteria passed</b>
<b>Condition Assessment Result (out of 5 criteria)</b>		<b>Condition Assessment Score</b>	<b>Score Achieved ×/✓</b>
Passes 5 criteria		Good (3)	
Passes 3 or 4 criteria		Moderate (2)	
Passes 2 or fewer criteria		Poor (1)	
<b>Suggested enhancement interventions to improve condition score</b>			
<b>Footnotes</b>			

Condition Sheet: LINE OF TREES Habitat Type												
Habitat Type(s)												
<b>Line of trees</b> <b>Line of trees – associated with bank or ditch</b> <b>Ecologically valuable line of trees</b> <b>Ecologically valuable line of trees – associated with bank or ditch</b>												
Habitat Description												
<p>See the Biodiversity Metric 4.0 User Guide Section 9.</p> <p>This assessment is based on the Hedgerow Survey Handbook<sup>1</sup>. For further clarifications please refer to the Handbook.</p> <p>Where ancient and veteran trees are present within the line of trees, see Footnote 2 for standing advice.</p>												
Site name and location		On-site or off-site										
		Survey reference (if relating to a wider survey)										
Limitations (if applicable)		Habitat parcel reference										
		Grid reference										
Condition Assessment Criteria		Criterion passed (Yes or No)										Notes (such as justification)
A	At least 70% of trees are native species.											
B	Tree canopy is predominantly continuous with gaps in canopy cover making up <10% of total area and no individual gap being >5 m wide.											
C	One or more trees has veteran features and or natural ecological niches for vertebrates and invertebrates, such as presence of standing and attached deadwood, cavities, ivy or loose bark.											
D	There is an undisturbed naturally-vegetated strip of at least 6 m on both sides to protect the line of trees from farming and other human activities (excluding grazing). Where veteran trees are present, root protection areas should follow standing advice <sup>2</sup> .											
E	At least 95% of the trees are in a healthy condition (deadwood or veteran features valuable for wildlife are excluded from this). There is little or no evidence of an adverse impact on tree health by damage from livestock or wild animals, pests or diseases, or human activity.											
Number of criteria passed												
Condition Assessment Result (out of 5 criteria)		Condition Assessment Score		Score Achieved ×/✓								
Passes 5 criteria		Good (3)										
Passes 3 or 4 criteria		Moderate (2)										
Passes 2 or fewer criteria		Poor (1)										
Suggested enhancement interventions to improve condition score												
Footnotes												

Condition Sheet: ORCHARD Habitat Type			
UK Habitat Classification (UKHab) Habitat Type			
Grassland - Traditional orchard			
Habitat Description			
<a href="#">ukhab – UK Habitat Classification</a>			
Site name and location		On-site or off-site	
Limitations (if applicable)		Survey reference (if relating to a wider survey)	
Grid reference		Habitat parcel reference	
Condition Assessment Criteria		Criterion passed (Yes or No)	Notes (such as justification)
A	Presence of ancient <sup>1</sup> and or veteran <sup>1</sup> trees. <b>Note - this criterion is essential for achieving Good condition.</b>		
B	Presence of deadwood in or on trees, or on the ground: at least 20% of mature trees have deadwood associated with them.  Some examples of deadwood are: standing, attached and fallen trees or limbs; dead stems; branches and branch stubs greater than 10 cm diameter; and internal cavities. The types and distribution of deadwood provide a range of habitats suitable to support a wide assemblage of saproxylic invertebrates. <b>Note - this criterion is essential for achieving Good condition.</b>		
C	Less than 5% of fruit trees are smothered by scrub. Small patches of dense scrub and or scattered scrub growing between trees can be beneficial to biodiversity, however these occupy less than 10% of ground cover.		
D	There is evidence of formative and or restorative pruning to maintain longevity of trees.		
E	At least 95% of the trees are free from damage caused by humans or animals, for example browsing, bark stripping or rubbing on non-adjusted ties.		
F	Grassland is not overgrazed, poaching is not evident around the trees, with no more than 10% of trees poached under the canopy.		
G	Species richness of the grassland is equivalent to a medium, high, or very high distinctiveness grassland.		
H	There is an absence of invasive non-native plant species <sup>2</sup> (as listed on Schedule 9 of WCA <sup>3</sup> ) and species indicative of sub-optimal condition <sup>4</sup> make up less than 10% of ground cover.		
<b>Essential criteria achieved (required for good condition - Yes or No)</b>			
<b>Number of criteria passed</b>			
Condition Assessment Result (out of 8 criteria)	Condition Assessment Score	Score Achieved ×/✓	
Passes 6- 8 criteria, including essential criteria A and B.	Good (3)		
Passes 4 or 5 criteria; OR Passes 6 or 7 criteria but fails an essential criterion.	Moderate (2)		

Passes 3 or fewer criteria.	Poor (1)		
Suggested enhancement interventions to improve condition score			
Footnotes			

Condition Sheet: ORCHARD Habitat Type												
UK Habitat Classification (UKHab) Habitat Type												
Grassland - Traditional orchard												
Habitat Description												
<a href="#">ukhab – UK Habitat Classification</a>												
Site name and location												
	On-site or off-site Survey reference (if relating to a wider survey)											
Limitations (if applicable)	Habitat parcel reference											
Condition Assessment Criteria	Grid reference											
Criterion passed (Yes or No)											Notes (such as justification)	
A	Presence of ancient <sup>1</sup> and or veteran <sup>1</sup> trees. <b>Note - this criterion is essential for achieving Good condition.</b>											
B	Presence of deadwood in or on trees, or on the ground: at least 20% of mature trees have deadwood associated with them.  Some examples of deadwood are: standing, attached and fallen trees or limbs; dead stems; branches and branch stubs greater than 10 cm diameter; and internal cavities. The types and distribution of deadwood provide a range of habitats suitable to support a wide assemblage of saproxylic invertebrates. <b>Note - this criterion is essential for achieving Good condition.</b>											
C	Less than 5% of fruit trees are smothered by scrub. Small patches of dense scrub and or scattered scrub growing between trees can be beneficial to biodiversity, however these occupy less than 10% of ground cover.											
D	There is evidence of formative and or restorative pruning to maintain longevity of trees.											
E	At least 95% of the trees are free from damage caused by humans or animals, for example browsing, bark stripping or rubbing on non-adjusted ties.											
F	Grassland is not overgrazed, poaching is not evident around the trees, with no more than 10% of trees poached under the canopy.											
G	Species richness of the grassland is equivalent to a medium, high, or very high distinctiveness grassland.											
H	There is an absence of invasive non-native plant species <sup>2</sup> (as listed on Schedule 9 of WCA <sup>3</sup> ) and species indicative of sub-optimal condition <sup>4</sup> make up less than 10% of ground cover.											
Essential criteria achieved (required for Good condition - Yes or No)												
Number of criteria passed												
Condition Assessment Result (out of 8 criteria)	Condition Assessment Score	Score Achieved ×/✓										
Passes 6- 8 criteria, including essential criteria A and B.	Good (3)											
Passes 4 or 5 criteria; OR Passes 6 or 7 criteria but fails an essential criterion.	Moderate (2)											
Passes 3 or fewer criteria.	Poor (1)											
Suggested enhancement interventions to improve condition score												
Footnotes												

Condition Sheet: POND Habitat Type			
<b>Habitat Type(s)</b>			
Lakes - Ponds (priority habitat)			
Lakes - Ponds (non-priority habitat)			
Lakes - Temporary lakes ponds and pools (H3170) [Use this condition sheet for Temporary ponds and pools, use Lake condition sheet for Temporary lakes]			
Lakes - Ornamental lake or pond [Use this condition sheet for Ornamental ponds, use Lake condition sheet for Ornamental lakes]			
<b>Habitat Description</b>			
<a href="#">ukhab – UK Habitat Classification</a>			
For ponds (non-priority) – see the Biodiversity Metric 4.0 Technical Annex 2.			
<b>Site name and location</b>		<b>On-site or off-site</b>	
<b>Limitations (if applicable)</b>		<b>Survey reference (if relating to a wider survey)</b>	
<b>Grid reference</b>		<b>Habitat parcel reference</b>	
<b>Condition Assessment Criteria</b>		<b>Criterion passed (Yes or No)</b>	<b>Notes (such as justification)</b>
<b>Core Criteria - applicable to all ponds (woodland<sup>1</sup> and non-woodland):</b>			
A	The pond is of good water quality, with clear water (low turbidity) indicating no obvious signs of pollution. Turbidity is acceptable if the pond is grazed by livestock.		
B	There is semi-natural habitat (moderate distinctiveness or above) completely surrounding the pond, for at least 10 m from the pond edge for its entire perimeter.		
C	Less than 10% of the water surface is covered with duckweed <i>Lemna</i> spp. or filamentous algae.		
D	The pond is not artificially connected to other waterbodies, e.g. agricultural ditches or artificial pipework.		
E	Pond water levels can fluctuate naturally throughout the year. No obvious artificial dams <sup>2</sup> , pumps or pipework.		
F	There is an absence of listed non-native plant and animal species <sup>3</sup> .		
G	The pond is not artificially stocked with fish. If the pond naturally contains fish, it is a native fish assemblage at low densities.		
<b>Additional Criteria - must be assessed for all non-woodland ponds:</b>			
H	Emergent, submerged or floating plants (excluding duckweed) <sup>4</sup> cover at least 50% of the pond area which is less than 3 m deep.		
I	The pond surface is no more than 50% shaded by adjacent trees and scrub.		
<b>Number of criteria passed</b>			
<b>Condition Assessment Result</b>	<b>Condition Assessment Score</b>	<b>Score Achieved ×/√</b>	
<b>Results for woodland ponds which require assessment of 7 core criteria</b>			
Passes 7 criteria	Good (3)		
Passes 5 or 6 criteria	Moderate (2)		
Passes 4 or fewer criteria	Poor (1)		
<b>Results for non-woodland ponds which require assessment of 9 criteria</b>			
Passes 9 criteria	Good (3)		
Passes 6 to 8 criteria	Moderate (2)		
Passes 5 or fewer criteria	Poor (1)		
<b>Suggested enhancement interventions to improve condition score</b>			

**Footnote 1** - A woodland pond will be surrounded on all sides by woodland habitat.

**Footnote 2** – This excludes natural dams such as those created by Eurasian beaver *Castor fiber*.

**Footnote 3** - Any species included on the Water Framework Directive (WFD) UKTAG GB High Impact Species List should be absent: WFD UKTAG (2021) *Classification of aquatic alien species according to their level of impact* [online]. Available from:

Condition Sheet: POND Habitat Type												
Habitat Type(s)												
Lakes - Ponds (priority habitat)												
Lakes - Ponds (non-priority habitat)												
Lakes - Temporary lakes ponds and pools (H3170) [Use this condition sheet for Temporary ponds and pools, use Lake condition sheet for Temporary lakes]												
Lakes - Ornamental lake or pond [Use this condition sheet for Ornamental ponds, use Lake condition sheet for Ornamental lakes]												
Habitat Description												
ukhab – UK Habitat Classification												
For ponds (non-priority) – see the Biodiversity Metric 4.0 Technical Annex 2.												
Site name and location		On-site or off-site										
		Survey reference (if relating to a wider survey)										
Limitations (if applicable)		Habitat parcel reference										Notes (such as justification)
Condition Assessment Criteria		Grid reference										
Criterion passed (Yes or No)												
<b>Core Criteria - applicable to all ponds (woodland<sup>1</sup> and non-woodland):</b>												
A	The pond is of good water quality, with clear water (low turbidity) indicating no obvious signs of pollution. Turbidity is acceptable if the pond is grazed by livestock.											
B	There is semi-natural habitat (moderate distinctiveness or above) completely surrounding the pond, for at least 10 m from the pond edge for its entire perimeter.											
C	Less than 10% of the water surface is covered with duckweed <i>Lemna</i> spp. or filamentous algae.											
D	The pond is not artificially connected to other waterbodies, e.g. agricultural ditches or artificial pipework.											
E	Pond water levels can fluctuate naturally throughout the year. No obvious artificial dams <sup>2</sup> , pumps or pipework.											
F	There is an absence of listed non-native plant and animal species <sup>3</sup> .											
G	The pond is not artificially stocked with fish. If the pond naturally contains fish, it is a native fish assemblage at low densities.											
<b>Additional Criteria - must be assessed for all non-woodland ponds:</b>												
H	Emergent, submerged or floating plants (excluding duckweed) <sup>4</sup> cover at least 50% of the pond area which is less than 3 m deep.											
I	The pond surface is no more than 50% shaded by adjacent trees and scrub.											
Number of criteria passed												
Condition Assessment Result		Condition Assessment Score		Score Achieved ×/√								
<b>Results for woodland ponds which require assessment of 7 core criteria</b>												
Passes 7 criteria		Good (3)										
Passes 5 or 6 criteria		Moderate (2)										
Passes 4 or fewer criteria		Poor (1)										
<b>Results for non-woodland ponds which require assessment of 9 criteria</b>												
Passes 9 criteria		Good (3)										
Passes 6 to 8 criteria		Moderate (2)										
Passes 5 or fewer criteria		Poor (1)										
Suggested enhancement interventions to improve condition score												

**Footnote 1** - A woodland pond will be surrounded on all sides by woodland habitat.

**Footnote 2** – This excludes natural dams such as those created by Eurasian beaver *Castor fiber*.

**Footnote 3** - Any species included on the Water Framework Directive (WFD) UKTAG GB High Impact Species List should be absent: WFD UKTAG (2021) *Classification of aquatic alien species according to their level of impact* [online]. Available from:

Condition Sheet: ROCKY SHORE Habitat Type					
Habitat Type(s)					
Rocky shore - High energy littoral rock Rocky shore - Moderate energy littoral rock Rocky shore - Low energy littoral rock Rocky shore - Features of littoral rock Rocky shore - High energy littoral rock - on peat, clay or chalk Rocky shore - Moderate energy littoral rock - on peat, clay or chalk Rocky shore - Low energy littoral rock - on peat, clay or chalk Rocky shore - Features of littoral rock - on peat, clay or chalk					
Site name and location		On-site or off-site			
Limitations (if applicable)		Survey reference (if relating to a wider survey)			
Grid reference		Habitat parcel reference			
Habitat Description					
<a href="#">EUNIS -Factsheet for Features of littoral rock (europa.eu)</a>					
Habitat Attributes to Record					
The following information should be recorded within the condition assessment sheet: <ul style="list-style-type: none"> <li>• Description of presence of typical communities and biotopes across the full vertical extent of the shore<sup>1</sup>;</li> <li>• Description of species diversity and community composition across the full vertical extent of the shore<sup>1</sup>;</li> <li>• Observations on coastal process functioning and any human physical modifications present;</li> <li>• Presence and abundance of non-native species;</li> <li>• Percentage cover of algal growths that could be attributed to nutrient enrichment;</li> <li>• Presence and density of non-natural structures and direct human impacts;</li> <li>• Assessment of litter; and</li> <li>• Water Framework Directive (WFD) classification of overlying water.</li> </ul>					
Condition Assessment Criteria					
Indicator	Good (3 points)	Moderate (2 point)	Poor (1)	Score per indicator	Notes (such as justification)
<b>A Coastal processes</b>	Coastal processes are functioning naturally. No evidence of human physical modifications which are clearly impacting the habitat.	Artificial structures present, for example groynes that are impeding the natural movement of sediments or water, affecting up to 25% of the habitat.	Artificial structures present, for example groynes that are impeding the natural movement of sediments or water, affecting more than 25% of the habitat.		
<b>B Presence and abundance of invasive non-native species</b>	Not more than one invasive non-native species is 'Occasional' on the SACFOR scale or is occupying more than 1% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 2 for details.	No invasive non-native species are present above 'Frequent' on the SACFOR scale or they occupy between 1-10% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 2 for details.	One or more invasive non-native species present at an 'Abundant' level on the SACFOR scale, they occupy more than 10% of the habitat or a high-risk species indicative of sub-optimal condition is present – GB Non-native Species Secretariat should be notified, see Footnote 2 for details.		
<b>C Water Quality</b>	No visual evidence of pollution. There are no nuisance algal growths that are likely to be attributable to nutrient enrichment. Consider seasonality of survey timing <sup>3</sup> .	Visual evidence of low to moderate levels of pollution. elevated algal growth with increases in cover that may indicate nutrient enrichment. Consider seasonality of survey timing <sup>3</sup> .	Visual evidence of high algal growth that is indicative of nutrient enrichment. Signs of eutrophication that would impede bird feeding. Consider seasonality of survey timing <sup>3</sup> .		
<b>D Non-natural structures and direct human impacts</b>	No evidence of impacts from direct human activities, or they occupy <1% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies 1-10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies >10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).		
<b>E Litter (when examining a beach strandline, mean high water line or intertidal rocky shore)</b>	Following the Marine Conservation Society (MCS) beach litter survey method, the number of items of litter does not exceed 0.0036 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to up to 20 items per person per 100 m per hour. See Footnote 4 for details.	Following the MCS beach litter survey method, the number of items of litter does not exceed 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to between 21 and 47 items of litter per person per 100 m per hour. See Footnote 4 for details.	Following the MCS beach litter survey method, the number of items of litter exceeds 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to more than 47 items of litter per person per 100 m per hour. See Footnote 4 for details.		
<b>Total score (out of a possible 15)</b>					

Condition Assessment Result	Result Achieved
<b>TOTAL SCORE 12-15 (75-100%) = GOOD CONDITION</b>	
<b>TOTAL SCORE 8-11 (50-75%) = MODERATE CONDITION</b>	
<b>TOTAL SCORE 5-7 (0-50%) = POOR CONDITION</b>	
<b>Suggested enhancement interventions to improve condition score</b>	

Condition Sheet: ROCKY SHORE Habitat Type														
Habitat Type(s)														
Rocky shore - High energy littoral rock														
Rocky shore - Moderate energy littoral rock														
Rocky shore - Low energy littoral rock														
Rocky shore - Features of littoral rock														
Rocky shore - High energy littoral rock - on peat, clay or chalk														
Rocky shore - Moderate energy littoral rock - on peat, clay or chalk														
Rocky shore - Low energy littoral rock - on peat, clay or chalk														
Rocky shore - Features of littoral rock - on peat, clay or chalk														
Site name and location				On-site or off-site										
Limitations (if applicable)				Survey reference (if relating to a wider survey)										
Habitat Description														
EUNIS - Factsheet for Features of littoral rock (europa.eu)														
Habitat Attributes to Record														
The following information should be recorded within the condition assessment sheet:														
<ul style="list-style-type: none"> <li>Description of presence of typical communities and biotopes across the full vertical extent of the shore<sup>1</sup>;</li> <li>Description of species diversity and community composition across the full vertical extent of the shore<sup>1</sup>;</li> <li>Observations on coastal process functioning and any human physical modifications present;</li> </ul>								Habitat parcel reference						
<ul style="list-style-type: none"> <li>Presence and abundance of non-native species;</li> <li>Percentage cover of algal growths that could be attributed to nutrient enrichment;</li> </ul>								Grid reference						
<ul style="list-style-type: none"> <li>Presence and density of non-natural structures and direct human impacts;</li> <li>Assessment of litter; and</li> <li>Water Framework Directive (WFD) classification of overlying water.</li> </ul>														
Condition Assessment Criteria														
Indicator	Good (3 points)	Moderate (2 point)	Poor (1)	Score per indicator								Notes (such as justification)		
A Coastal processes	Coastal processes are functioning naturally. No evidence of human physical modifications which are clearly impacting the habitat.	Artificial structures present, for example groynes that are impeding the natural movement of sediments or water, affecting up to 25% of the habitat.	Artificial structures present, for example groynes that are impeding the natural movement of sediments or water, affecting more than 25% of the habitat.											
B Presence and abundance of invasive non-native species	Not more than one invasive non-native species is 'Occasional' on the SACFOR scale or is occupying more than 1% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 2 for details.	No invasive non-native species are present above 'Frequent' on the SACFOR scale or they occupy between 1-10% of the habitat. No high-risk species indicative of sub-optimal condition present, see Footnote 2 for details.	One or more invasive non-native species present at an 'Abundant' level on the SACFOR scale, they occupy more than 10% of the habitat or a high-risk species indicative of sub-optimal condition is present – GB Non-native Species Secretariat should be notified, see Footnote 2 for details.											
C Water Quality	No visual evidence of pollution. There are no nuisance algal growths that are likely to be attributable to nutrient enrichment. Consider seasonality of survey timing <sup>3</sup> .	Visual evidence of low to moderate levels of pollution. Elevated algal growth with increases in cover that may indicate nutrient enrichment. Consider seasonality of survey timing <sup>3</sup> .	Visual evidence of high algal growth that is indicative of nutrient enrichment. Signs of eutrophication that would impede bird feeding. Consider seasonality of survey timing <sup>3</sup> .											
D Non-natural structures and direct human impacts	No evidence of impacts from direct human activities, or they occupy <1% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies 1-10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).	Evidence of impacts from direct human activities occupies >10% of the habitat area (for example, pontoons, moorings, boats, crab tiles, bait digging or anchoring scars).											
E Litter (when examining a beach strandline, mean high water line or intertidal rocky shore)	Following the Marine Conservation Society (MCS) beach litter survey method, the number of items of litter does not exceed 0.0036 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to up to 20 items per person per 100 m per hour. See Footnote 4 for details.	Following the MCS beach litter survey method, the number of items of litter does not exceed 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to between 21 and 47 items of litter per person per 100 m per hour. See Footnote 4 for details.	Following the MCS beach litter survey method, the number of items of litter exceeds 0.0078 m <sup>-1</sup> min <sup>-1</sup> person <sup>-1</sup> , equivalent to more than 47 items of litter per person per 100 m per hour. See Footnote 4 for details.											
<b>Total score (out of a possible 15)</b>														
Condition Assessment Result				Result Achieved										
TOTAL SCORE 12-15 (75-100%) = GOOD CONDITION														
TOTAL SCORE 8-11 (50-75%) = MODERATE CONDITION														
TOTAL SCORE 5-7 (0-50%) = POOR CONDITION														
Suggested enhancement interventions to improve condition score														

Condition Sheet: SCRUB Habitat Type			
UK Habitat Classification (UKHab) Habitat Type			
Heathland and shrub - Blackthorn scrub Heathland and shrub - Gorse scrub Heathland and shrub - Hawthorn scrub Heathland and shrub - Hazel scrub Heathland and shrub - Mixed scrub Heathland and shrub - Dunes with sea buckthorn (H2160) Heathland and shrub - Willow scrub			
Habitat Description			
For Dunes with sea buckthorn see:	<a href="#">Dunes with sea-buckthorn (Dunes with <i>Hippophae rhamnoides</i>) - Special Areas of Conservation (jncc.gov.uk)</a>		
For other scrub types see:	<a href="#">ukhab – UK Habitat Classification</a>		
Site name and location		On-site or off-site	
Limitations (if applicable)		Survey reference (if relating to a wider survey)	
Grid reference		Habitat parcel reference	
Condition Assessment Criteria		Criterion passed (Yes or No)	Notes (such as justification)
A	The scrub is a good representation of the habitat type it has been identified as, based on its UKHab description (where in its natural range). The appearance and composition of the vegetation closely matches the characteristics of the specific scrub type.		
A	At least 80% of scrub is native, and there are at least three native woody species <sup>1</sup> , with no single species comprising more than 75% of the cover (except hazel <i>Corylus avellana</i> , common juniper <i>Juniperus communis</i> , sea buckthorn <i>Hippophae rhamnoides</i> or box <i>Buxus sempervirens</i> , which can be up to 100% cover).		
B	Seedlings, saplings, young shrubs and mature (or ancient or veteran <sup>2</sup> ) shrubs are all present.		
C	There is an absence of invasive non-native plant species <sup>3</sup> (as listed on Schedule 9 of WCA <sup>4</sup> ) and species indicative of sub-optimal condition <sup>5</sup> make up less than 5% of ground cover.		
D	The scrub has a well-developed edge with scattered scrub and tall grassland and or forbs present between the scrub and adjacent habitat.		
E	There are clearings, glades or rides present within the scrub, providing sheltered edges.		
<b>Number of criteria passed</b>			
Condition Assessment Result (out of 5 criteria)	Condition Assessment Score	Score Achieved x/√	
Passes 5 criteria	Good (3)		
Passes 3 or 4 criteria	Moderate (2)		
Passes 2 or fewer criteria	Poor (1)		
Suggested enhancement interventions to improve condition score			

Condition Sheet: SCRUB Habitat Type												
UK Habitat Classification (UKHab) Habitat Type												
<b>Heathland and shrub - Blackthorn scrub</b> <b>Heathland and shrub - Gorse scrub</b> <b>Heathland and shrub - Hawthorn scrub</b> <b>Heathland and shrub - Hazel scrub</b> <b>Heathland and shrub - Mixed scrub</b> <b>Heathland and shrub - Dunes with sea buckthorn (H2160)</b> <b>Heathland and shrub - Willow scrub</b>												
Habitat Description												
For Dunes with sea buckthorn see:	<a href="#">Dunes with sea-buckthorn (Dunes with Hippophae rhamnoides) - Special Areas of Conservation (incc.gov.uk)</a>											
For other scrub types see:	<a href="#">ukhab – UK Habitat Classification</a>											
Site name and location												
	On-site or off-site											
		Survey reference (if relating to a wider survey)										
Limitations (if applicable)												
	Habitat parcel reference											
WS											Notes (such as justification)	
Grid reference												
											Notes (such as justification)	
Condition Assessment Criteria												
		Criterion passed (Yes or No)									Notes (such as justification)	
A	The scrub is a good representation of the habitat type it has been identified as, based on its UKHab description (where in its natural range). The appearance and composition of the vegetation closely matches the characteristics of the specific scrub type.	N										
A	At least 80% of scrub is native, and there are at least three native woody species <sup>1</sup> , with no single species comprising more than 75% of the cover (except hazel <i>Corylus avellana</i> , common juniper <i>Juniperus communis</i> , sea buckthorn <i>Hippophae rhamnoides</i> or box <i>Buxus sempervirens</i> , which can be up to 100% cover).	N										
B	Seedlings, saplings, young shrubs and mature (or ancient or veteran <sup>2</sup> ) shrubs are all present.	N										
C	There is an absence of invasive non-native plant species <sup>3</sup> (as listed on Schedule 9 of WCA <sup>4</sup> ) and species indicative of sub-optimal condition <sup>5</sup> make up less than 5% of ground cover.	Y										
D	The scrub has a well-developed edge with scattered scrub and tall grassland and or forbs present between the scrub and adjacent habitat.	Y										
E	There are clearings, glades or rides present within the scrub, providing sheltered edges.	N										
Number of criteria passed		2										
Condition Assessment Result (out of 5 criteria)	Condition Assessment Score	Score Achieved * / ✓										
Passes 5 criteria	Good (3)											
Passes 3 or 4 criteria	Moderate (2)											
Passes 2 or fewer criteria	Poor (1)	Poor										
Suggested enhancement interventions to improve condition score												

<b>Condition Sheet: SPARSELY VEGETATED LAND Habitat Type</b>			
<b>UK Habitat Classification (UKHab) Habitat Type(s)</b>			
Sparsely vegetated land - Inland rock outcrop and scree habitats			
Sparsely vegetated land - Other inland rock and scree			
<b>Habitat Description</b>			
<a href="#">ukhab – UK Habitat Classification</a>			
<b>Site name and location</b>		<b>On-site or off-site</b>	
<b>Limitations (if applicable)</b>		<b>Survey reference (if relating to a wider survey)</b>	
<b>Grid reference</b>		<b>Habitat parcel reference</b>	
<b>Condition Assessment Criteria</b>		<b>Criterion passed (Yes or No)</b>	<b>Notes (such as justification)</b>
A	The parcel is a good representation of the sparsely vegetated habitat type it has been identified as, based on its UKHab description - the appearance and composition of the vegetation closely matches the characteristics of the specific habitat type.  Indicator species for the specific sparsely vegetated habitat type listed by UKHab are consistently present.		
B	The cover of bracken <i>Pteridium aquilinum</i> , scrub and trees is less than 25%.		

C	There is an absence of invasive non-native plant species <sup>1</sup> (as listed on Schedule 9 of WCA <sup>2</sup> ) and species indicative of sub-optimal condition <sup>3</sup> make up less than 5% of vegetated ground cover.		
D	Vegetation cover of vascular and non-vascular plants is between 5 and 50%.		
			<b>Number of criteria passed</b>
<b>Condition Assessment Result (out of 4 criteria)</b>		<b>Condition Assessment Score</b>	<b>Score Achieved ×/✓</b>
Passes 4 criteria		Good (3)	
Passes 3 criteria		Moderate (2)	
Passes 2 or fewer criteria		Poor (1)	
<b>Suggested enhancement interventions to improve condition score</b>			
<b>Footnotes</b>			



D	Vegetation cover of vascular and non-vascular plants is between 5 and 50%.												
<b>Number of criteria passed</b>													
<b>Condition Assessment Result (out of 4 criteria)</b>	<b>Condition Assessment Score</b>	<b>Score Achieved ×/✓</b>											
Passes 4 criteria	Good (3)												
Passes 3 criteria	Moderate (2)												
Passes 2 or fewer criteria	Poor (1)												
<b>Suggested enhancement interventions to improve condition score</b>													
<b>Footnotes</b>													

Condition Sheet: URBAN Habitat Type			
<b>Habitat Type</b>			
Where a parcel contains areas of higher distinctiveness habitats within it, then the area of higher distinctiveness habitat must be separated and recorded and assessed as such.			
<b>Sparsely vegetated land - Ruderal/Ephemeral</b>			
<b>Sparsely vegetated land – Tall forbs</b>			
<b>Urban – Allotments</b>			
<b>Urban – Biodiverse green roof</b>			
<b>Urban - Bioswale</b>			
<b>Urban - Cemeteries and churchyards</b>			
<b>Urban - Facade-bound green wall</b>			
<b>Urban - Ground based green wall</b>			
<b>Urban - Intensive green roof</b>			
<b>Urban - Open mosaic habitats on previously developed land</b>			
<b>Urban - Rain garden</b>			
<b>Urban - Sustainable drainage system (SuDS)</b>			
<b>Urban - Vacant or derelict land</b>			
<b>Urban – Bare ground</b>			
<b>Habitat Description</b>			
See Biodiversity Metric 4.0 User Guide for green roofs and UK Habitat Classification (UKHab) for other habitats:			<a href="#">UKHab – UK Habitat Classification</a>
<b>Site name and location</b>		<b>On-site or off-site</b>	
<b>Limitations (if applicable)</b>		<b>Survey reference (if relating to a wider survey)</b>	
<b>Grid reference</b>		<b>Habitat parcel reference</b>	
<b>Condition Assessment Criteria</b>		<b>Criterion passed (Yes or No)</b>	<b>Notes (such as justification)</b>
Core Criteria - must be assessed for <b>all urban habitat types</b> :			
A	Vegetation structure is varied, providing opportunities for vertebrates and invertebrates to live, eat and breed. A single structural habitat component or vegetation type does not account for more than 80% of the total habitat area.		
B	The habitat parcel contains different plant species that are beneficial for wildlife, for example flowering species providing nectar sources for a range of invertebrates at different times of year.		
C	Invasive non-native plant species (listed on Schedule 9 of WCA <sup>1</sup> ) and others which are to the detriment of native wildlife (using professional judgement) <sup>2</sup> cover less than 5% of the total vegetated area <sup>3</sup> .  <b>Note - to achieve Good condition, this criterion must be satisfied by a complete absence of invasive non-native species (rather than &lt;5% cover).</b>		
Additional Criteria - must be assessed for <b>Open mosaic habitat on previously developed land</b> only:			
D1	The parcel shows spatial variation and forms a mosaic of at least four early successional communities (a) to (h) PLUS bare substrate.  (a) annuals; (b) mosses/liverworts; (c) lichens; (d) ruderals; (e) inundation species; (f) open grassland; (g) flower-rich grassland; (h) heathland.		
D2	The parcel contains pools of water such as permanent and ephemeral waterbodies.		
Additional Criteria - must be assessed for <b>Bioswale and SuDS</b> habitat types only:			
E1	Plant species are mostly native. If non-native species are present, they should not be detrimental to the habitat or native wildlife <sup>4</sup> .		
E2	The vegetation is comprised of plant species suited to wetland or riparian situations.		
Additional Criterion - must be assessed for <b>Intensive green roofs</b> only:			
F	The roof has a minimum of 50% native and non-native wildflowers. 70% of the roof area is soil and vegetation (including water features).		
Additional Criterion - must be assessed for <b>Biodiverse green roofs</b> only:			

G	<p>The roof has a varied depth of 80 – 150 mm; at least 50% is at 150 mm and is planted and seeded with wildflowers and sedums or is pre-prepared with sedums and wildflowers.</p> <p><b>Note – to achieve Good condition some additional habitat, such as sand piles, stones, logs etc are present.</b></p>		
<b>Essential criteria relevant for habitat type achieved (Yes or No)</b>			
<b>Number of criteria passed</b>			
<b>Condition Assessment Result</b>	<b>Condition Assessment Score</b>	<b>Score Achieved ×/✓</b>	
<b>Results for habitats requiring assessment of 3 core criteria only (all listed urban habitats except Open mosaic habitat on previously developed land, Bioswale, SuDS and Green roofs):</b>			
<ul style="list-style-type: none"> <li>• Passes all 3 core criteria;</li> </ul> <b>AND</b> <ul style="list-style-type: none"> <li>• Meets the requirements for Good condition within criterion C.</li> </ul>	Good (3)		
<ul style="list-style-type: none"> <li>• Passes 2 of 3 core criteria;</li> </ul> <b>OR</b> <ul style="list-style-type: none"> <li>• Passes 3 of 3 core criteria but does not meet the requirements for Good condition within criterion C.</li> </ul>	Moderate (2)		
<ul style="list-style-type: none"> <li>• Passes 0 or 1 of 3 core criteria.</li> </ul>	Poor (1)		
<b>Results for Green roofs (requiring assessment of 4 criteria only - core criteria plus additional criterion specified for habitat type):</b>			
<ul style="list-style-type: none"> <li>• Passes all 3 core criteria;</li> </ul> <b>AND</b> <ul style="list-style-type: none"> <li>• Meets the requirements for Good condition within criterion C;</li> </ul> <b>AND</b> <ul style="list-style-type: none"> <li>• Passes additional criterion relevant to specific habitat type (F or G).</li> </ul>	Good (3)		
<ul style="list-style-type: none"> <li>• Passes 2 or 3 of 4 criteria;</li> </ul> <b>OR</b> <ul style="list-style-type: none"> <li>• Passes 4 of 4 criteria but does not meet the requirements for Good condition within criterion C.</li> </ul>	Moderate (2)		
<ul style="list-style-type: none"> <li>• Passes 0 or 1 of 4 criteria.</li> </ul>	Poor (1)		
<b>Results for Open mosaic habitat on previously developed land, Bioswale or SuDS (requiring assessment of 5 criteria - core criteria plus additional criteria specified for habitat type):</b>			
<ul style="list-style-type: none"> <li>• Passes all 3 core criteria;</li> </ul> <b>AND</b> <ul style="list-style-type: none"> <li>• Meets the requirements for Good condition within criterion C;</li> </ul> <b>AND</b> <ul style="list-style-type: none"> <li>• Passes all additional criteria relevant to specific habitat type (Group D or Group E)</li> </ul>	Good (3)		
<ul style="list-style-type: none"> <li>• Passes 3 or 4 of 5 criteria;</li> </ul> <b>OR</b> <ul style="list-style-type: none"> <li>• Passes 5 of 5 criteria but does not meet the requirements for Good condition within criterion C.</li> </ul>	Moderate (2)		
<ul style="list-style-type: none"> <li>• Passes 2 or fewer of 5 criteria.</li> </ul>	Poor (1)		
<b>Suggested enhancement interventions to improve condition score</b>			
<b>Footnotes</b>			

Condition Sheet: URBAN Habitat Type												
<b>Habitat Type</b>												
Where a parcel contains areas of higher distinctiveness habitats within it, then the area of higher distinctiveness habitat must be separated and recorded and assessed as such.												
<b>Sparsely vegetated land - Ruderal/Ephemeral</b> <b>Sparsely vegetated land – Tall forbs</b> <b>Urban – Allotments</b> <b>Urban – Biodiverse green roof</b> <b>Urban - Bioswale</b> <b>Urban - Cemeteries and churchyards</b> <b>Urban - Facade-bound green wall</b> <b>Urban - Ground based green wall</b> <b>Urban - Intensive green roof</b> <b>Urban - Open mosaic habitats on previously developed land</b> <b>Urban - Rain garden</b> <b>Urban - Sustainable drainage system (SuDS)</b> <b>Urban - Vacant or derelict land</b> <b>Urban – Bare ground</b>												
<b>Habitat Description</b>												
See the Biodiversity Metric 4.0 User Guide for green roofs, and UK Habitat Classification (UKHab) for other habitats: <a href="#">ukhab – UK Habitat Classification</a>												
<b>Site name and location</b>	<b>On-site or off-site</b>											
	<b>Survey reference (if relating to a wider survey)</b>											
<b>Limitations (if applicable)</b>	<b>Habitat parcel reference</b>											<b>Notes (such as justification)</b>
	VL											
<b>Grid reference</b>												
<b>Condition Assessment Criteria</b>	<b>Criterion passed (Yes or No)</b>											
<b>Core Criteria - must be assessed for all urban habitat types:</b>												
A	Vegetation structure is varied, providing opportunities for vertebrates and invertebrates to live, eat and breed. A single structural habitat component or vegetation type does not account for more than 80% of the total habitat area.	N										
B	The habitat parcel contains different plant species that are beneficial for wildlife, for example flowering species providing nectar sources for a range of invertebrates at different times of year.	N										
C	Invasive non-native plant species (listed on Schedule 9 of WCA <sup>1</sup> ) and others which are to the detriment of native wildlife (using professional judgement) <sup>2</sup> cover less than 5% of the total vegetated area <sup>3</sup> .  <b>Note - to achieve Good condition, this criterion must be satisfied by a complete absence of invasive non-native species (rather than &lt;5% cover).</b>	Y										
<b>Additional Criteria - must be assessed for Open mosaic habitat on previously developed land only:</b>												
D1	The parcel shows spatial variation and forms a mosaic of at least four early successional communities (a) to (h) PLUS bare substrate.  (a) annuals; (b) mosses/liverworts; (c) lichens; (d) ruderals; (e) inundation species; (f) open grassland; (g) flower-rich grassland; (h) heathland.											
D2	The parcel contains pools of water such as permanent and ephemeral waterbodies.											
<b>Additional Criteria - must be assessed for Bioswale and SuDS habitat types only:</b>												
E1	Plant species are mostly native. If non-native species are present, they should not be detrimental to the habitat or native wildlife <sup>4</sup> .											
E2	The vegetation is comprised of plant species suited to wetland or riparian situations.											
<b>Additional Criterion - must be assessed for Intensive green roofs only:</b>												
F	The roof has a minimum of 50% native and non-native wildflowers. 70% of the roof area is soil and vegetation (including water features).											
<b>Additional Criterion - must be assessed for Biodiverse green roofs only:</b>												
G	The roof has a varied depth of 80 – 150 mm; at least 50% is at 150 mm and is planted and seeded with wildflowers and sedums or is pre-prepared with sedums and wildflowers.  <b>Note – to achieve Good condition, some additional habitat, such as sand piles, stones, logs etc are present.</b>											
<b>Essential criteria relevant for habitat type achieved (Yes or No)</b>												
<b>Number of criteria passed</b> 1												
<b>Condition Assessment Result</b>	<b>Condition Assessment Score</b>	<b>Score Achieved x/√</b>										
Results for habitats requiring assessment of 3 core criteria only (all listed urban habitats except Open mosaic habitat on previously developed land, Bioswale, SuDS and Green roofs):												

<ul style="list-style-type: none"> <li>• Passes all 3 core criteria;</li> </ul> AND <ul style="list-style-type: none"> <li>• Meets the requirements for Good condition within criterion C.</li> </ul>	Good (3)																		
<ul style="list-style-type: none"> <li>• Passes 2 of 3 core criteria;</li> </ul> OR <ul style="list-style-type: none"> <li>• Passes 3 of 3 core criteria but does not meet the requirements for Good condition within criterion C.</li> </ul>	Moderate (2)																		
<ul style="list-style-type: none"> <li>• Passes 0 or 1 of 3 core criteria.</li> </ul>	Poor (1)	Poor																	
<b>Results for Green roofs (requiring assessment of 4 criteria only - core criteria plus additional criterion specified for habitat type):</b>																			
<ul style="list-style-type: none"> <li>• Passes all 3 core criteria;</li> </ul> AND <ul style="list-style-type: none"> <li>• Meets the requirements for Good condition within criterion C;</li> </ul> AND <ul style="list-style-type: none"> <li>• Passes additional criterion relevant to specific habitat type (F or G).</li> </ul>	Good (3)																		
<ul style="list-style-type: none"> <li>• Passes 2 or 3 of 4 criteria;</li> </ul> OR <ul style="list-style-type: none"> <li>• Passes 4 of 4 criteria but does not meet the requirements for Good condition within criterion C.</li> </ul>	Moderate (2)																		
<ul style="list-style-type: none"> <li>• Passes 0 or 1 of 4 criteria.</li> </ul>	Poor (1)																		
<b>Results for Open mosaic habitat on previously developed land, Bioswale or SuDS (requiring assessment of 5 criteria - core criteria plus additional criteria specified for habitat type):</b>																			
<ul style="list-style-type: none"> <li>• Passes all 3 core criteria;</li> </ul> AND <ul style="list-style-type: none"> <li>• Meets the requirements for Good condition within criterion C;</li> </ul> AND <ul style="list-style-type: none"> <li>• Passes all additional criteria relevant to specific habitat type (Group D or Group E)</li> </ul>	Good (3)																		
<ul style="list-style-type: none"> <li>• Passes 3 or 4 of 5 criteria;</li> </ul> OR <ul style="list-style-type: none"> <li>• Passes 5 of 5 criteria but does not meet the requirements for Good condition within criterion C.</li> </ul>	Moderate (2)																		
<ul style="list-style-type: none"> <li>• Passes 2 or fewer of 5 criteria.</li> </ul>	Poor (1)																		
<b>Suggested enhancement interventions to improve condition score</b>																			
<b>Footnotes</b>																			

Condition Sheet: WETLAND Habitat Type			
<b>Habitat Type(s)</b>			
<b>Grassland - Floodplain wetland mosaic and CFGM</b> - See the Biodiversity Metric 4.0 User Guide. <b>Wetland - Blanket bog</b> <b>Wetland - Depression on peat substrates (H7150)</b> <b>Wetland - Fens (upland and lowland)</b> <b>Wetland - Lowland raised bog</b> <b>Wetland - Oceanic valley mire [1] (D2.1)</b> <b>Wetland - Purple moor grass and rush pastures</b> <b>Wetland - Reedbeds</b> <b>Wetland - Transition mires and quaking bogs (H7140)</b>			
<b>Habitat Description</b>			
<a href="#">For Oceanic valley mires - see EUNIS</a> See the Biodiversity Metric 4.0 User Guide for Floodplain wetland mosaic and coastal and floodplain grazing marsh (CFGM). For CFGM also see the below: <a href="#">Coastal and floodplain grazing marsh UK BAP Priority Habitat description</a> <a href="#">Priority Habitat Inventory (England) - data.gov.uk</a>			
All other wetland habitats - see UK Habitat Classification (UKHab):			
<a href="#">UKHab</a>			
<b>Site name and location</b>		<b>On-site or off-site</b>	
<b>Limitations (if applicable)</b>		<b>Survey reference (if relating to a wider survey)</b>	
<b>Grid reference</b>		<b>Habitat parcel reference</b>	
<b>Condition Assessment Criteria</b>		<b>Criterion passed (Yes or No)</b>	<b>Notes (such as justification)</b>
Core Criteria - must be assessed for <b>all wetland habitat types</b> :			
A	The water table is at, or near the surface throughout the year - this could be open water or saturation of soil at the surface. There is no artificial drainage, unless specifically to maintain water levels as specified above. <b>Note - this criterion is essential for achieving Good condition.</b>		
B	The parcel is a good representation of the wetland habitat type it has been identified as, based on its UKHab description - as in, the appearance and composition of the vegetation closely matches the characteristics of the specific habitat type. Indicator species for the specific wetland habitat type <sup>1</sup> listed by UKHab are consistently present.		
C	The water supplies (groundwater, surface water and or rainwater) to the wetland are of good water quality, with clear water (low turbidity) indicating no obvious signs of pollution.		
D	Cover of scrub and scattered trees are less than 10%.		
E	Cover of bare ground is less than 5%.		
F	There is an absence of invasive non-native plant species <sup>2</sup> (as listed on Schedule 9 of WCA <sup>3</sup> ) and species indicative of sub-optimal condition <sup>4</sup> make up less than 5% of ground cover.		
Additional Criterion - must be assessed for <b>Fen and Purple moor grass and rush pasture</b> habitats only:			
G	No more than 25% of the habitat area has a continuous cover of litter (such as dead vegetation) preventing regeneration.		
Additional Criterion - must be assessed for <b>Bog</b> habitats only:			
H	Sphagnum moss <i>Sphagnum</i> spp. and cottongrasses <i>Eriophorum</i> spp. are at least Frequent <sup>5</sup> . Cover of ericaceous dwarf shrubs <sup>6</sup> is less than 75%.		
Additional Criterion - must be assessed for <b>Reedbed</b> habitats only:			
I	The reedbed has a diverse structure with between 60 and 80% reeds <i>Phragmites australis</i> . Other areas may include open water (at least 10%), species-rich fen and or wet woodland.		
Additional Criterion - must be assessed for <b>Floodplain wetland mosaic and CFGM</b> only:			

J	All ditches recorded within the habitat achieve Good condition as assessed using the Ditch condition sheet. Note – do not record ditches which are part of the floodplain wetland mosaic and CFGM within the Watercourse module.		
<b>Essential criterion achieved (required for Good condition) Yes or No:</b>			
<b>Number of criteria passed</b>			
<b>Condition Assessment Result</b>		<b>Condition Assessment Score</b>	<b>Score Achieved x/√</b>
<b>Results for habitats requiring assessment of 6 criteria</b> (Depression on peat substrates (H7150) and Oceanic valley mire [1] (D2.1)):			
•Passes 5 or 6 core criteria, including criterion A.		Good (3)	
•Passes 3 or 4 core criteria; OR •Passes 5 core criteria but fails criterion A.		Moderate (2)	
•Passes 2 or fewer core criteria.		Poor (1)	
<b>Results for habitats requiring assessment of 7 criteria - core criteria and additional criterion specified for habitat type</b> (all habitat types except Depression on peat substrates (H7150) and Oceanic valley mire [1] (D2.1)):			
•Passes 5 or 6 core criteria including criterion A; AND •Passes additional criterion G, H, I or J (choose the one specified for the habitat type).		Good (3)	
•Passes 4 or 5 of 7 criteria; OR •Passes 6 of 7 criteria but fails criterion A or additional criterion G, H, I or J (choose the one specified for the habitat type).		Moderate (2)	
•Passes 3 or fewer criteria.		Poor (1)	
<b>Suggested enhancement interventions to improve condition score</b>			





Condition Sheet: WOODLAND Habitat Type						
UK Habitat Classification (UKHab) Habitat Type(s)						
Woodland and forest - Lowland beech and yew woodland Woodland and forest - Lowland mixed deciduous woodland Woodland and forest - Native pine woodlands Woodland and forest - Other coniferous woodland Woodland and forest - Other Scot's pine woodland Woodland and forest - Other woodland; broadleaved Woodland and forest - Other woodland; mixed Woodland and forest - Upland birchwoods Woodland and forest - Upland mixed ashwoods Woodland and forest - Upland oakwood Woodland and forest - Wet woodland						
Habitat Description						
<a href="#">ukhab – UK Habitat Classification</a>						
This condition sheet is based on the England Woodland Biodiversity Group (EWBG) Woodland Condition Survey Method, available here:						
<a href="#">Woodland Wildlife Toolkit (sylva.org.uk)</a>						
IMPORTANT: This biodiversity metric woodland condition assessment must be used to assess woodland being input into the biodiversity metric. The outputs of this condition assessment are not equivalent to, nor are they comparable with the scores from the EWBG condition assessment, because the EWBG assessment has been adapted for the biodiversity metric, including the removal of EWBG Indicator 7 (Proportion of favourable land cover around woodland) and Indicator 14 (Size of woodland), and minor changes to other indicators.						
Site name and location		On-site or off-site				
Limitations (if applicable)		Survey reference (if relating to a wider survey)				
Grid reference		Habitat parcel reference				
Condition Assessment Criteria						
Indicator		Good (3 points)	Moderate (2 points)	Poor (1 point)	Score per indicator	Notes (such as justification)
A	Age distribution of trees	Three age-classes <sup>1</sup> present.	Two age-classes <sup>1</sup> present.	One age-class <sup>1</sup> present.		
B	Wild, domestic and feral herbivore damage	No significant browsing damage evident in woodland <sup>2</sup> .	Evidence of significant browsing pressure is present in 40% or less of whole woodland <sup>2</sup> .	Evidence of significant browsing pressure is present in 40% or more of whole woodland <sup>2</sup> .		
C	Invasive plant species	No invasive species <sup>3</sup> present in woodland.	Rhododendron <i>Rhododendron ponticum</i> or cherry laurel <i>Prunus laurocerasus</i> not present, other invasive species <sup>3</sup> <10% cover.	Rhododendron or cherry laurel present, or other invasive species <sup>3</sup> >10% cover.		
D	Number of native tree species	Five or more native tree or shrub species <sup>4</sup> found across woodland parcel.	Three to four native tree or shrub species <sup>4</sup> found across woodland parcel.	Two or less native tree or shrub species <sup>4</sup> across woodland parcel.		
E	Cover of native tree and shrub species	>80% of canopy trees and >80% of understory shrubs are native <sup>5</sup> .	50 - 80% of canopy trees and 50 - 80% of understory shrubs are native <sup>5</sup> .	<50% of canopy trees and <50% of understory shrubs are native <sup>5</sup> .		

<b>F</b>	<b>Open space within woodland</b>	10 - 20% of woodland has areas of temporary open space <sup>6</sup> . Unless woodland is <10ha, in which case 0 - 20% temporary open space is permitted <sup>7</sup> .	21 - 40% of woodland has areas of temporary open space <sup>6</sup> .	<10% or >40% of woodland has areas of temporary open space <sup>6</sup> . But if woodland <10ha has <10% temporary open space, please see Good category <sup>7</sup> .		
<b>G</b>	<b>Woodland regeneration</b>	All three classes present in woodland <sup>8</sup> ; trees 4 - 7 cm Diameter at Breast Height (DBH), saplings and seedlings or advanced coppice regrowth.	One or two classes only present in woodland <sup>8</sup> .	No classes or coppice regrowth present in woodland <sup>8</sup> .		
<b>H</b>	<b>Tree health</b>	Tree mortality less than 10%, no pests or diseases and no crown dieback <sup>9</sup> .	11% to 25% mortality and/or crown dieback or low-risk pest or disease present <sup>9</sup> .	Greater than 25% tree mortality and or any high-risk pest or disease present <sup>9</sup> .		
<b>I</b>	<b>Vegetation and ground flora</b>	Recognisable NVC plant community <sup>10</sup> at ground layer present, strongly characterised by ancient woodland flora specialists.	Recognisable woodland NVC plant community <sup>10</sup> at ground layer present.	No recognisable woodland NVC plant community <sup>10</sup> at ground layer present.		
<b>J</b>	<b>Woodland vertical structure</b>	Three or more storeys across all survey plots or a complex woodland <sup>11</sup> .	Two storeys across all survey plots <sup>11</sup> .	One or less storey across all survey plots <sup>11</sup> .		
<b>K</b>	<b>Veteran trees</b>	Two or more veteran trees <sup>12</sup> per hectare.	One veteran tree <sup>12</sup> per hectare.	No veteran trees <sup>12</sup> present in woodland.		
<b>L</b>	<b>Amount of deadwood</b>	50% of all survey plots within the woodland parcel have deadwood, such as standing deadwood, large dead branches and or stems, branch stubs and stumps, or an abundance of small cavities <sup>13</sup> .	Between 25% and 50% of all survey plots within the woodland parcel have deadwood, such as standing deadwood, large dead branches and or stems, stubs and stumps, or an abundance of small cavities <sup>13</sup> .	Less than 25% of all survey plots within the woodland parcel have deadwood, such as standing deadwood, large dead branches and or stems, stubs and stumps, or an abundance of small cavities <sup>13</sup> .		
<b>M</b>	<b>Woodland disturbance</b>	No nutrient enrichment or damaged ground evident <sup>14</sup> .	Less than 1 hectare in total of nutrient enrichment across woodland area and or less than 20% of woodland area has damaged ground <sup>14</sup> .	More than 1 hectare of nutrient enrichment and or more than 20% of woodland area has damaged ground <sup>14</sup> .		

**Total Score (out of a possible 39)**

Condition Assessment Result	Condition Assessment Score	Result Achieved
Total score >32 (33 to 39)	Good (3)	
Total score 26 to 32	Moderate (2)	
Total score <26 (13 to 25)	Poor (1)	

Suggested enhancement interventions to improve condition score



G	Woodland regeneration	All three classes present in woodland <sup>8</sup> ; trees 4 - 7 cm Diameter at Breast Height (DBH), saplings and seedlings or advanced coppice regrowth.	One or two classes only present in woodland <sup>8</sup> .	No classes or coppice regrowth present in woodland <sup>8</sup> .	1	2	2											
H	Tree health	Tree mortality less than 10%, no pests or diseases and no crown dieback <sup>9</sup> .	11% to 25% tree mortality and or crown dieback or low-risk pest or disease present <sup>9</sup> .	Greater than 25% tree mortality and or any high-risk pest or disease present <sup>9</sup> .	3	3	3											
I	Vegetation and ground flora	Recognisable NVC plant community <sup>10</sup> at ground layer present, strongly characterised by ancient woodland flora specialists.	Recognisable woodland NVC plant community <sup>10</sup> at ground layer present.	No recognisable woodland NVC plant community <sup>10</sup> at ground layer present.	1	1	1											
J	Woodland vertical structure	Three or more storeys across all survey plots, or a complex woodland <sup>11</sup> .	Two storeys across all survey plots <sup>11</sup> .	One or less storey across all survey plots <sup>11</sup> .	2	2	1											
K	Veteran trees	Two or more veteran trees <sup>12</sup> per hectare.	One veteran tree <sup>12</sup> per hectare.	No veteran trees <sup>12</sup> present in woodland.	1	1	1											
L	Amount of deadwood	50% of all survey plots within the woodland parcel have deadwood, such as standing deadwood, large dead branches and or stems, branch stubs and stumps, or an abundance of small cavities <sup>13</sup> .	Between 25% and 50% of all survey plots within the woodland parcel have deadwood, such as standing deadwood, large dead branches and or stems, stubs and stumps, or an abundance of small cavities <sup>13</sup> .	Less than 25% of all survey plots within the woodland parcel have deadwood, such as standing deadwood, large dead branches and or stems, stubs and stumps, or an abundance of small cavities <sup>13</sup> .	1	1	1											
M	Woodland disturbance	No nutrient enrichment or damaged ground evident <sup>14</sup> .	Less than 1 hectare in total of nutrient enrichment across woodland area and or less than 20% of woodland area has damaged ground <sup>14</sup> .	More than 1 hectare of nutrient enrichment and or more than 20% of woodland area has damaged ground <sup>14</sup> .	3	3	3											
<b>Total Score (out of a possible 39)</b>					27	30	27											
<b>Condition Assessment Result</b>		<b>Condition Assessment Score</b>			<b>Result Achieved</b>													
Total score >32 (33 to 39)		Good (3)																
Total score 26 to 32		Moderate (2)			2	2	2											
Total score <26 (13 to 25)		Poor (1)																
<b>Suggested enhancement interventions to improve condition score</b>																		

Condition Sheet: WOOD-PASTURE AND PARKLAND Habitat Type			
UK Habitat Classification (UKHab) Habitat Type			
Woodland and forest - Wood-pasture and parkland			
Habitat Description			
<a href="#">See UKHab</a>			
Site name and location		On-site or off-site	
Limitations (if applicable)		Survey reference (if relating to a wider survey)	
Grid reference		Habitat parcel reference	
Condition Assessment Criteria		Criterion passed (Yes or No)	Notes (such as justification)
A	Presence of ancient and or veteran trees <sup>1</sup> . <b>NB - this criterion is essential for achieving Good condition.</b>		
B	Three different life-stages (for example young, mature or veteran) of open grown or pollarded trees <sup>1</sup> are present, to ensure replacement and continuity of tree cohort, veteran characteristics and habitat.		
C	Native scrub is present with a variety of heights, widths, shapes and species compositions - as planted or naturally established individual plants, or clumps of trees or shrubs <sup>2</sup> .		
D	Frequent <sup>3</sup> presence of decaying wood providing ecological niches – such as standing, attached and fallen deadwood (for example, dead stems, branches and branch stubs), trees with heart-rot, or hollowing in the trunk or major limbs. Decay features might be revealed by certain types of fungal fruiting bodies.		
E	There is no evidence of recent adverse impact on tree health by human activities, livestock, wild animals, pests or diseases (this excludes veteran features valuable for wildlife). For example, no evidence of poaching, damage from machinery use or storage, ground compaction, grazing damage to bark and roots, competition or shading from surrounding trees.		
F	Ground cover comprises open habitats, for example grassland or heathland, which are unimproved or semi-improved (medium distinctiveness or higher).		
G	Ground cover is subject to an appropriate management regime providing structural diversity for vertebrates and invertebrates, which is not being or threatened by infill of trees and scrub by natural establishment or forestry plantation, native or non-native. See Footnote 4 for details.		
H	There is an absence of invasive non-native plant species <sup>5</sup> (as listed on Schedule 9 of WCA <sup>6</sup> ), and species indicative of sub-optimal condition <sup>7</sup> make up less than 5% cover (this excludes ancient and veteran trees).		
Number of criteria passed			
Condition Assessment Result (out of 8 criteria)	Condition Assessment Score	Score Achieved ×/✓	
Passes 7 or 8 criteria and meets criterion A	Good (3)		
Passes 5 or 6 criteria OR Passes 7 criteria but fails criterion A	Moderate (2)		
Passes 4 or fewer criteria	Poor (1)		
Suggested enhancement interventions to improve condition score			

Condition Sheet: WOOD-PASTURE AND PARKLAND Habitat Type																				
UK Habitat Classification (UKHab) Habitat Type																				
Woodland and forest - Wood-pasture and parkland																				
Habitat Description																				
<a href="#">See UKHab</a>																				
Site name and location											On-site or off-site									
											Survey reference (if relating to a wider survey)									
Limitations (if applicable)											Habitat parcel reference									
											Grid reference									
Condition Assessment Criteria										Criterion passed (Yes or No)		Notes (such as justification)								
A	Presence of ancient and or veteran trees <sup>1</sup> . <b>NB - this criterion is essential for achieving Good condition.</b>																			
B	Three different life-stages (for example young, mature or veteran) of open grown or pollarded trees <sup>1</sup> are present, to ensure replacement and continuity of tree cohort, veteran characteristics and habitat.																			
C	Native scrub is present with a variety of heights, widths, shapes and species compositions - as planted or naturally-established individual plants, or clumps of trees or shrubs <sup>2</sup> .																			
D	Frequent <sup>3</sup> presence of decaying wood providing ecological niches – such as standing, attached and fallen deadwood (for example, dead stems, branches and branch stubs), trees with heart-rot, or hollowing in the trunk or major limbs. Decay features might be revealed by certain types of fungal fruiting bodies.																			
E	There is no evidence of recent adverse impact on tree health by human activities, livestock, wild animals, pests or diseases (this excludes veteran features valuable for wildlife). For example, no evidence of poaching, damage from machinery use or storage, ground compaction, grazing damage to bark and roots, competition or shading from surrounding trees.																			
F	Ground cover comprises open habitats, for example grassland or heathland, which are unimproved or semi-improved (medium distinctiveness or higher).																			
G	Ground cover is subject to an appropriate management regime providing structural diversity for vertebrates and invertebrates, which is not being or threatened by infill of trees and scrub by natural establishment or forestry plantation, native or non-native. See Footnote 4 for details.																			
H	There is an absence of invasive non-native plant species <sup>5</sup> (as listed on Schedule 9 of WCA <sup>6</sup> ), and species indicative of sub-optimal condition <sup>7</sup> make up less than 5% cover (this excludes ancient and veteran trees).																			
Number of criteria passed																				
Condition Assessment Result (out of 8 criteria)		Condition Assessment Score		Score Achieved ×/✓																
Passes 7 or 8 criteria and meets criterion A		Good (3)																		
Passes 5 or 6 criteria OR Passes 7 criteria but fails criterion A		Moderate (2)																		
Passes 4 or fewer criteria		Poor (1)																		
Suggested enhancement interventions to improve condition score																				