KEY:

DO NOT SCALE

PRIVATE ACCESS APPROXIMATE EXTENTS

EXISTING WAITING RESTRICTION

PROPOSED WAITING RESTRICTION (SEE NOTE 3)

NOTES:

1. PRELIMINARY LAYOUT SUBJECT TO DETAILED DESIGN INCLUDING FULL CDM COMPLIANCE, STATUTORY UNDERTAKERS SEARCH/DIVERSION REQUIREMENTS, HIGHWAY DRAINAGE PROVISION, LAND AVAILABILITY CAPACITY ASSESSMENT AND LOCAL AUTHORITY APPROVAL.
2. FULL DETAILS OF PROPOSED IMPROVEMENT SCHEME SHOWN ON OPTIMA DRAWING NO. 18092/GA/07.
3. DOUBLE YELLOW LINES 'NO WAITING AT ANY TIME' TRAFFIC REGULATION ORDER TO BE PROVIDED IN ACCORDANCE WITH TSRGD DIAGRAM NO. 1018.1
4. PROPOSED DOUBLE YELLOW LINES SHOWN INDICATIVELY SUBJECT TO TRAFFIC REGULATION ORDER PROCESS IN DUE COURSE.

SEE INSET 1

SEE INSET 3

SEE INSET 2

STORTHES HALL LANE

A629 PENISTONE ROAD

BR1/8 NORTH ROAD

Weir

Storthes Hall Bridge

Depot

Spring Grove

Grove House

Eldon House

SCHEME OVERVIEW WITH VISIBILITY SPLAYS (SCALE 1:500@A0)

PROPOSED 'NO WAITING AT ANY TIME' TRO TO ASSIST VEHICLES TURNING RIGHT OUT OF STORTHES HALL LANE

INSET 1 - A629 PENISTONE ROAD/STORTHES HALL LANE/WOODSOME LEES LANE IMPROVEMENT SCHEME (SCALE 1:250@A0)

4 NO. ZIG-ZAG MARKS PROVIDED TO MINIMISE IMPACT ON PARKING ADJACENT TO FISH AND CHIP SHOP

KEEP CLEAR

KEEP CLEAR

NO WAITING RESTRICTIONS ON BOTH SIDES FOR INITIAL 35M LENGTH OF NORTH ROAD TO PROTECT CROSSING VISIBILITY

INSET 2 - A629 PENISTONE ROAD/NORTH ROAD CYCLE IMPROVEMENT SCHEME (SCALE 1:250@A0)

PROPOSED 37M LONG BUS STOP CLEAR-WAY TO TSRGD DIAGRAM NO. 1025.1 IN ACCORDANCE WITH WYCA 'BUS STOP INFRASTRUCTURE STANDARDS GUIDANCE' NOVEMBER 2020

BUS STOP

EXTENDED 'NO WAITING' RESTRICTIONS ON FULL LENGTH OF STORTHES HALL LANE AND TO SOUTHWEST OF PROPOSED SIGNAL STOP LINE

INSET 3 - STORTHES HALL LANE PROPOSED THREE-WAY TRAFFIC SIGNALS AND PEDESTRIAN IMPROVEMENT SCHEME (SCALE 1:250@A0)

REV	DATE	BY	DESCRIPTION	CHK	APP
-	02/04/25	JS	INITIAL ISSUE	MEW	MEW

STATUS: PRELIMINARY

PROJECT: STORTHES HALL LANE, KIRKBURTON

CLIENT: UBRIQUE INVESTMENTS LIMITED.

DRAWING TITLE: PROPOSED PENISTONE ROAD/STORTHES HALL LANE/ NORTH ROAD IMPROVEMENTS - OPTION C - INDICATIVE TRAFFIC REGULATION ORDERS

CHECKED	APPROVED	DRG No.
MEW	MEW	18092/IN/07

DRAWN BY:	SCALE @ A0	DATE	REV.
JS	AS SHOWN	02/04/25	-

OPTIMA
Intelligent Highway Solutions
Suite 5, 3rd Floor, Goodyear House, Infirmary Street
Leeds LS1 2JP
optima@highways.com
T 0113 245 1679