

**12 GEORGE STREET, RAVENSTHORPE, DEWSBURY, WF13 3LL**  
**SPECIFICATION FOR RESIDENTIAL VEHICULAR CROSSING**

48 Hours notice must be given before starting work, which must be carried out during normal working hours, Monday to Friday.

The applicant is responsible for ensuring the compliance with this specification. If it is subsequently found that the vehicular crossing is not constructed to this specification, the council may rectify any sub-standard work and charge all costs incurred to the applicant.

**Foundation.**

Foundation shall consist of 150mm consolidated thickness of 40mm to dust graded limestone on a properly prepared foundation.

**Surfacing.**

Surfacing 75mm thickness of surfacing consisting of a base course of 55mm consolidated thickness of 20mm graded bitumen macadam (Limestone aggregate) and a wearing course of 20mm consolidated thickness of 6mm graded bitumen macadam (Gritstone aggregate). (All specified in accordance with BS EN 13108).

**Kerbing.**

The spraying of weedkiller to be carried out over prepared foundation as required.

The minimum width of crossing at the kerb line to be 3 centre kerbs plus 2 tapered kerbs

All work to be carried out to the satisfaction of the Strategic Director of Regeneration.

All precautions during the works to be taken to ensure public safety i.e. fencing and lighting  
The person responsible for the works to satisfy himself by contracting the statutory undertakers (British Telecom, Thames Water, Electricity Authorities, British Gas, Cable Providers etc) to ensure that their plant will not be affected. Affected plant to be protected as required by the statutory undertaker.

The cost, if necessary, of moving plant (i.e. street lighting columns) will be charged to the person responsible for the work. Or contact to the local authorities if their will be equity for the work.