

The use of drawings by the Customer as an agreement to the following terms. The Customer must not use the drawings if it does not agree with any of the following conditions:

All drawings are based upon site information supplied by third parties and as such their accuracy cannot be guaranteed. All features are approximate and subject to clarification by a detailed topographical survey, statutory service enquiries and confirmation of the legal boundaries. Do not scale the drawings. If ground is shown, it must be used in all cases. All dimensions must be checked on site. Any discrepancies must be reported in writing to Colours Ltd, before proceeding. All drawings are copyright protected. Refer to full Terms & Conditions at www.colour-ud.com

	Species-Rich Meadow Mix	
	Habitat Aid Grazing Meadow Seed Mix	4g / m2
	Pond Edge Mix	
	Emergent BMS Special General Purpose Meadow Mixture	4g / m2
	Hedgegrove Mix	
	Emergent EHI Hedgegrove Mix	4g / m2
	Grass Seeding Mix	
	General WFG20 Eco Species-rich Lawn	10g / m2

	Turfing	
	Hard-wearing fibre-reinforced Amenity Grass	
	ALG Advanced Turf Rootzone Reinforcement System with Lindum LTB Festival Plus Turf	

Ornamental Shrub Planting

Trees	Key	Girth cm	Height cm	Root Zone	Specification
Acer campestre 'Streetwise'	Ac	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 200cm; 5 breaks
Malus domestica 'Cox's Self Fertile'	Mc	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 200cm; 5 breaks
Malus domestica 'Egremont Russet'	Mc	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 175-200cm; 5 breaks
Malus domestica 'Sunset'	Mc	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 175-200cm; 5 breaks
Carpinus betulus	Cb	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 175-200cm; 5 breaks
Prunus avium 'Pena'	Pd	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 175-200cm; 5 breaks
Prunus domestica 'Thelma Claude D'Oulline'	Pd	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 175-200cm; 5 breaks
Prunus padus 'Albent'	Pd	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 175-200cm; 5 breaks
Pinus communis 'Conference'	Pc	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 175-200cm; 5 breaks
Sorbus aucuparia 'Sheerwater Seeding'	So	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 175-200cm; 5 breaks
Tilia cordata 'Greenspire'	Tc	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem 175-200cm; 4 breaks
Salix alba (yellow trees to be regularly pollarded to provide goat food)	Sa	10-12	300-350	RB	3x, Selected Standard, clear stem 175-200cm; 4 breaks
Hedge		Height cm		Density per m	Specification
50% Fagus sylvatica (mix alternata)		120-150		4	3 year, bare root, 1+2 transplant, double-staggered, 500 mm c/c
50% Carpinus betulus					
Planting Mixture (100%)	Ratio	Height cm	Pot size	Density per m2	Specification
Shrubs	%				
Choisya ternata	5	40-60	3L	3	Bushy; 4 breaks
Lavandula angustifolia 'Hidcote'	6	15-20	2L	4	Bushy; 5 breaks
Hebe 'Green Glosse'	8	20-30	3L	4	Bushy; 3 breaks
Lonicera nitida 'May Green'	10	30-40	2L	3	Bushy; 3 breaks
Sarcococca confusa	8	3L	3L	4	Bushy; 7 breaks
Stimonia x confusa 'New Green'	7	3L	3L	4	Bushy; 3 breaks
Herbaceous					
Geranium macrorrhizum 'Spessart'	24	0.5L			
Grasses					
Stipa calamagrostis 'Lemping'	12	2L		3	
Stipa tenuissima	12	2L		5	

Active / Passive Outdoor Spaces

Trees	Key	Girth cm	Height cm	Root Zone	Specification
Acer campestre 'Streetwise'	Ac	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 200cm; 5 breaks; underground rootball geying system
Acer saccharum	As	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 200cm; 5 breaks; underground rootball geying system
Betula papyrifera	Bp	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 175-200cm; 5 breaks; underground rootball geying system
Prunus avium 'Pena'	Pd	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem 175-200cm; 5 breaks; underground rootball geying system
Tilia cordata 'Greenspire'	Tc	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem 175-200cm; 5 breaks; underground rootball geying system
Hedge		Height cm		Density per m	Specification
50% Fagus sylvatica (mix alternata)		120-150		4	3 years, bare root, 1+2 transplant, double-staggered, 500 mm c/c
50% Carpinus betulus					
Planting Mixture (100%)	Ratio	Height cm	Pot size	Density per m2	Specification
Shrubs	%				
Choisy ternata	5	40-60	3L	3	Bushy; 4 breaks
Sarcococca confusa	10	3L	3L	4	Bushy; 7 breaks
Hebe 'Green Glosse'	5	20-30	3L	4	Bushy; 3 breaks
Lavandula angustifolia 'Hidcote'	6	15-20	2L	4	Bushy; 5 breaks
Lonicera nitida 'May Green'	5	20-40	2L	3	Bushy; 3 breaks
Rosmarinus officinalis 'Blue Boy'	5	30-40	3L	3	Bushy; 4 breaks
Stimonia x confusa 'New Green'	10	3L	3L	4	Bushy; 3 breaks
Herbaceous					
Aljula reptans 'Cathin's Giant'	10	0.5L		6	
Geranium macrorrhizum 'Spessart'	15	0.5L			
Grasses					
Stipa tenuissima	8	2L		3	
Stipa calamagrostis 'Lemping'	8	2L		3	
Stipa tenuissima	10	2L		5	

Native Shrub and Woodland Planting

Trees	Key	Girth cm	Height cm	Root Zone	Specification
Acer campestre 'Streetwise'	Ac	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 200cm; 5 breaks
Carpinus betulus	Cb	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 175-200cm; 5 breaks
Prunus avium 'Pena'	Pd	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 175-200cm; 5 breaks
Prunus padus 'Albent'	Pd	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 175-200cm; 5 breaks
Quercus robur	Qr	14-16	400-450	RB	3x, Extra Heavy Standard, clear stem minimum 175-200cm; 5 breaks
Planting Mixture (100%)	Ratio	Height cm	Pot size	Density per m2	Specification
Shrubs	%				
Corylus avellana	10	80-100	10L	1	Branched; 4 breaks
Viburnum opulus	10	40-60	2L	3	Bushy; 7 breaks
Sambucus nigra	10	40-60	2L	2	Branched; 3 breaks
Fruit bushes					
Ribes nigrum	5	60-80	3L	3	Bush 3/5 shoots
Ribes rubrum	5	60-80	3L	3	Bush 3/5 shoots
Rubus idaeus 'Autumn Bliss'	5	40-60	2L	3	Strong cane
Rubus fruticosus	5	20-30	0.5L	3	
Herbaceous					
Allium ursinum	5	0.5L		7	
Anemone pulsatilla	5	2L		4	
Galium odoratum	5	0.5L		7	
Geranium macrorrhizum	5	0.5L		7	
Ferns					
Dryopteris filix mas	10	2L		1	
Grasses					
Carex pendula	10	2L		3	
Luzula sylvatica	10	2L		4	



Class Gardens	
Trees	
Prunus 'Shogetsu'	Key: 14-16, 400-450, RB, 3x, Extra Heavy Standard, clear stem 175-200cm; 5 breaks; underground rootball geying system
Hedge to fence	
Grasshopper 'Green Hedge'	Height cm: 120-150, Density per m: 2, Pot grown, 20L pot
Elaeagnus x elaeagnifolia	Height cm: 120-150, Density per m: 2, Pot grown, 20L pot
Planting Mixture (100%)	
Shrubs	
Choisy ternata	10, 40-60, 3L, 3, Bushy, 4 breaks
Hebe 'Green Glosse'	10, 20-30, 3L, 4, Bushy, 3 breaks
Sarcococca confusa	10, 3L, 3L, 4, Bushy, 7 breaks
Stimonia x confusa 'New Green'	10, 3L, 3L, 4, Bushy, 3 breaks
Herbaceous	
Alchemilla mollis	6, 0.5L, 7
Seranium macrorrhizum 'Spessart'	6, 0.5L, 7
Thymus serpyllum 'Tiger'	6, 0.5L, 8
Thymus vulgaris 'Compectus'	6, 0.5L, 8
Linaria cathartica	6, 2L, 5
Grasses	
Briza media	6, 2L, 6
Deschampsia 'Goldbra'	6, 2L, 9
Festuca galeata	6, 0.5L, 9
Penstemon thunbergii 'Red Buttons'	6, 2L, 3

Existing Woodland to be improved	
Trees	
Sorbus aucuparia (1 no. per 200 m2)	22, 14-16, 400-450, RB, 3x, Extra Heavy Standard, clear stem minimum 200cm; 5 breaks
Malus sylvestris (1 no. per 200 m2)	22, 14-16, 400-450, RB, 3x, Extra Heavy Standard, clear stem minimum 200cm; 5 breaks

Planting/ Seeding Mixture (100%)	Ratio	Height cm	Pot size	Density per m2	Specification
Shrubs	%				
Cornus sanguinea	3	40-60	3L	1	Branched; 3 breaks
Corylus avellana	3	80-100	10L	1	Branched; 4 breaks
Crataegus monogyna	3	175-200	10-15L	1	1+1; Transplant - seed raised; branched; 4 breaks
Illex aquifolium	3	60-80	3L	1	Leader with laterals
Prunus cerasifera	3	40-60	2L	2	Leader with laterals; 3 breaks
Sambucus nigra	3	40-60	2L	2	Branched; 3 breaks
Viburnum opulus	3	40-60	10L	1	Branched; 3 breaks
Climbers					
Lonicera periclymenum	3	60-80	2L	1	Cane; several shoots; 2 breaks
Fruit bushes					
Ribes rubrum	3	60-80	3L	3	Bush 3/5 shoots
Rubus fruticosus	3	20-30	0.5L	3	
Grasses					
Carex pendula	4	2L		4	
Luzula sylvatica	4	2L		4	
Ferns					
Asplenium scolopendrium	4	2L		4	
Blechnum spicant	4	2L		4	
Dryopteris affinis	4	2L		2	
Woodland groundcover seed mix					
Emergent EWI Woodland Mixture	50	4g / m2			

NOT FOR CONSTRUCTION

05 Tender Issue 18/04/24 TK PD
Rev Amendments Date Drawn Chd
Project Joseph Norton Academy, Deighton
Drawing Title Planting Schedule

Project No. 2352 Scale @ A0 1:250 Project Status For Tender
Drawing No. L-2352-PP-5000 Revision 05
0203 924 9888
0191 24 24 224
01904 925 888
colour-ud.com

