

Flood Risk Assessment Tick Sheet

Flood Risk Assessments for Householder and other minor extensions in Flood Zones 2 & 3

Applications for planning permission within either Flood Zones 2 & 3 should be accompanied by a flood risk assessment. This guidance is for domestic applications and non-domestic extensions where the additional footprint created by the development does not exceed 250 sq. metres (minor development¹). It does NOT apply if an additional dwelling is being created e.g. a self-contained annex. This Tick Sheet is consistent with the Environment Agency's Standing Advice. It is a pragmatic and proportionate response to low risk developments in order to reduce the burden on applicants, the LPA and consultees.

Make sure that **floor levels are either no lower than existing floor levels or 300 millimetres (mm) above the estimated flood level**. If your floor levels aren't going to be 300mm above existing flood levels, you will need to consider appropriate flood resistance and resilience measures. If floor levels are proposed to be set lower than existing floor levels they should be above the known or modelled 1 in 100 annual probability river flood (1%) or 1 in 200 annual probability sea flood (0.5%) in any year.

Further information and guidance on flood resistance and resilience measures is available at

www.gov.uk regarding flood risk assessment standing advice.

<https://www.gov.uk/guidance/flood-risk-assessment-standing-advice#advice-for-minor-extensions>

State in your Flood Risk Assessment all levels in relation to Ordnance Datum (the height above average sea level). You may be able to get this information from the Ordnance Survey². If not, you'll need to get a land survey carried out by a qualified surveyor.

Applicants/Agents: Please complete the table overleaf and include it with the planning application submission. The table, together with a plan showing the finished floor levels and estimated flood levels, will form the Flood Risk Assessment (FRA) and will act as an assurance to the Local Planning Authority that flood risk issues have been adequately addressed.

You may be able to get the estimated flood level from the Environment Agency. Please contact enquiries@environment-agency.gov.uk. If not, you'll need a flood risk specialist to calculate this for you.

You can use the Tick Sheet over page or provide your written flood risk assessment in another format but it must include the relevant plans, surveys and assessments.

Any proposed works or structures, in, under, over or within 8m of the top of the bank of a main river, or 16m of a tidal main river, may require a permit under the Environmental Permitting (England and Wales) Regulations 2010 from the Environment Agency. This was formerly called a Flood Defence Consent. Some activities³ are also now excluded or exempt. A permit is separate to and in addition to any planning permission granted.

Further details and guidance are available at:

<https://www.gov.uk/guidance/flood-risk-activities-environmental-permits>. Or by contacting:

floodriskpermit@environment-agency.gov.uk

¹ Minor development in relation to flood risk:

<http://planningguidance.communities.gov.uk/blog/guidance/flood-risk-and-coastal-change/what-is-meant-by-minor-development-in-relation-to-flood-risk/>

² OS MAPS <https://www.ordnancesurvey.co.uk/>

³ Flood risk activities: environmental permits

<https://www.gov.uk/guidance/flood-risk-activities-environmental-permits#check-if-what-you-are-doing-is-an-excluded-activity>

Flood Risk Assessment

Flood Risk Assessments for Householder and other minor extensions in Flood Zones 2 & 3

Applicant to choose one or other of the flood mitigation measures below	Applicant to indicate their choice in the box below. Enter 'yes' or 'no'
<p>Either; Floor levels within the proposed development will be set no lower than existing levels AND, flood resilient and/or flood resistant measures have been incorporated in the proposed development where appropriate</p>	yes
<p>Or; Floor levels within the proposed development will be set 300mm above the known or modelled 1 in 100 annual probability river flood (1%) or 1 in 200 annual probability sea flood (0.5%) in any year. This flood level is the extent of the Flood Zones. Please remember to include a plan showing the finished floor levels and the estimated flood levels.</p>	no

Site Address	6 Whitley Willows Lepton HD8 0GD United Kingdom
Proposal Description	Single-storey rear extension to form sun room and roof terrace, side extension and internal alterations
Estimated flood level (i.e. The 1 in 100 year flood level)	Low risk. Chance of flooding of between 0.1% and 1%
Details of flood resilience and resistance measures	Horizontal DPC's to be a minimum 150mm above adjacent ground level & to be 500 microns' black polythene (2000g) to BS 6515:1984. DPC to be stepped up as necessary to maintain 150mm clearance. Proprietary cavity closers to be used so vertical DPCs are not required top openings. 75mm K3 Insulation over 2000 Gauge Visqueen, to be lapped and taped back to wall DPC. 50mm Reinforced liquid screed up to finished floor level. Minimum of 150mm clear void under the floor beams with all voids been vented with telescopic air bricks at every 1.5m centres or similar approved. Void below ground level to be drained. Proposed floor level to remain level with the existing.