

Tree Tag No	Age	Species	Latin Name	Height (m)	Crown Height (m)	Diameter (cm) at 1.5m	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (y)	Recommendations	Priority Target Value	BS5837 Retention Category	Re-Inspection Timing (y)
66	Mature	Sycamore	<i>Acer pseudoplatanus</i>	18	9	68	13	Crown overhangs the footpath and road. Single stemmed and vertical with a balanced crown. Multiple pruning wounds due to crown lifting. No major visible defects.	Good	Good	20-40	No action required	n/a	A	2
67	Mature	Sycamore	<i>Acer pseudoplatanus</i>	15	5	50	10	Crown overhangs the footpath and road. Single stemmed and leaning with an unbalanced crown. Multiple pruning wounds due to crown lifting. Poor form. Large vertical scar from base to 3m.	Good	Fair	10-20	Monitor annually	Moderate	B	1
68	Early Mature	Sycamore	<i>Acer pseudoplatanus</i>	17	8	42	11	Crown overhangs the footpath and road. Single stemmed and leaning with an unbalanced crown. Multiple pruning wounds due to crown lifting. Poor form. Large vertical scar from base to 3m.	Good	Fair	10-20	Monitor annually	Moderate	B	1
69	Mature	Sycamore	<i>Acer pseudoplatanus</i>	19	8	65	14	Single stemmed and vertical with a balanced crown. Multiple pruning wounds due to crown lifting. No major visible defects. Not fully inspected due to vegetation.	Good	Good	20-40	No action required	n/a	A	2
70	Semi Mature	Pine	<i>Pinus sp.</i>	6	1.5	22	6	Single stemmed and vertical with a balanced crown. Occasional pruning wounds due to crown lifting. No major visible defects.	Good	Good	20-40	No action required	n/a	A	5
71	Semi Mature	Horse Chestnut	<i>Aesculus hippocastanum</i>	13	3	23	7	Crown overhangs the road and footpath. Single stemmed and leaning with an unbalanced crown. Occasional pruning wounds. No major visible defects.	Good	Good	20-40	No action required	n/a	A	5
72	Early Mature	Cherry	<i>Prunus sp.</i>	16	1.5	est. 30	10	Crown overhangs the road and footpath. Single stemmed and leaning with a balanced crown. No evidence of significant pruning. No major visible defects. Ivy prevented detailed inspection.	Good	Good	20-40	Remove ivy and re-inspect	Low	B	2
73	Early Mature	Oak	<i>Quercus sp.</i>	16	3	est. 35	11	Crown overhangs the road and footpath. Single stemmed and leaning with an unbalanced crown. No evidence of significant pruning. Poor form and ivy prevented detailed inspection.	Good	Fair	20-40	Remove ivy and re-inspect	Low	B	2
74	Early Mature	Cherry	<i>Prunus sp.</i>	16	2	est. 38	13	Single stemmed and vertical with a balanced crown. No evidence of significant pruning. No major visible defects. Ivy prevented detailed inspection.	Good	Good	20-40	Remove ivy and re-inspect	Low	B	2

Doc 3