Heneghan ARCHITECTURE

Issue Date: 20/02/24
Job No: 2390
Client Name: Mr. J. Mellor
Site Address:
Granby Farm, Woodbottom Road, Netherton
Revisions:

MATERIALS SCHEDULE

WALLING STONE

Where walls require repair or rebuilding, existing stone on site to be re-used or reclaimed stone to match where required.

Any newly introduced stone is to match as appropriate.

ASHLAR STONE

Existing farm house extension to frontage to have feature ashlar stone to gable.

ROOF SLATES

Barn conversion to be stripped of existing cladded roof and replaced with blue slate roof finish.

Existing natural stone slates to be retained and re-used. Where replacements are needed, these are to be natural stone slates to match the existing building.

FLAT ROOF

Dark Grey flat roof in metal / grp cladding to single storey extensions.

ALUMINUM WINDOWS & DOORS

Windows and Door frames to be cream or sage slim aluminium frames.

BOUNDARY TREATMENTS

Garden boundaries to be 1.2m high drystone walls

Boundaries to paddocks and fields to be 1.5m high post and rail timber fences.

RAINWATER GOODS

Rainwater goods to be mock Cast Metal with gutters to have Ogee Profile

GARAGES

Garages to be constructed in natural stone with stone slates