



Key:



- * Intermediary homes
- * Social rented units
- * First homes
- VP Visitor parking
- ORP On road visitor parking

Enclosures:

- 1.8m close boarded fence with lattice
- 1.1m vertical/ horizontal railing (subject to site levels)
- 0.9m dry stone wall
- 0.9m dry stone wall with 1.8m close boarded fence with lattice
- 1.8m high art stone wall
- 1.1m post and wire fence with mesh panels
- Timber trellis fence - height varies across development (please refer to site sections for further information)
- Retaining wall faced with art stone, height varies across development, please refer to Engineer's drawing for site specific information
- Retaining wall faced with art stone, height varies across development, please refer to Engineer's drawing for site specific information, with 1200mm trellis above
- 450mm coursed stone wall with 1350mm trellis above
- Concrete wall faced with open trellis panels with 1200mm high open trellis fence above
- Cast in situ concrete wall faced with open trellis panels with stone plinth planters (1m high) set in front with 1200mm high open trellis fence above
- Retaining walls - coursed stone or similar
- Retaining walls - earth bank system, details TBC
- Timber knee rail

Enclosures detail:

- 1100mm HORIZONTAL RAILING
- 1100mm VERTICAL RAILING
- 1000mm DRY STONE WALL
- 1000mm DRY STONE WALL
- CONCRETE WALL FACED WITH OPEN TRELLIS PANELS AND 1200mm TRELLIS ABOVE - height varies
- CONCRETE WALL FACED WITH OPEN TRELLIS PANELS AND 1200mm TRELLIS ABOVE - height varies
- CAST IN SITU CONCRETE WALL FACED WITH OPEN TRELLIS PANELS WITH STONE PLINTH PLANTERS SET IN FRONT (1m HIGH) AND 1200mm TRELLIS ABOVE - height varies
- 450mm COURSED STONE WALL WITH 1350mm TRELLIS ABOVE
- 450mm HIGH TIMBER KNEE RAIL
- TRELLIS FENCE - height varies
- 1800mm CLOSE BOARDED FENCE W. LATTICE TOP
- 1100mm POST AND WIRE FENCE WITH MESH PANELS



P10 Colours amended in key	02/07/24	KL	KL
P9 Minor amends following feedback from client	02/07/24	KL	KL
P8 Minor amends following feedback from client	01/07/24	KL	KL
P7 Minor amends following client/ SE/ local authority feedback	12/06/24	KL	KL
P6 Minor amends following client feedback	24/04/24	KL	KL
P5 Minor amends following client feedback	24/04/24	KL	KL
P4 Additional enclosures added following client feedback and further amends throughout	23/04/24	KL	KL
P3 Amendments to enclosures following client feedback	19/04/24	KL	KL
P2 Minor amends following client comments	15/04/24	KL	KL
P1 First issue for comment	10/04/24	KL	CB

Revision	Date	By	Chk

All dimensions to be verified on site, and the Architect informed of any discrepancy. All drawings and specifications should be read in conjunction with the Health and Safety Plan; all conflicts should be reported to the appointed Principal Designer.

YORKSHIRE
COUNTRY PROPERTIES

Yorkshire Country Properties
Phase 2
Abbey Road, Shepley

Sheet Name: Enclosures plan

Purpose of Issue: Planning Status: 1

Date: 08/04/24 Checked By: CB

Drawn By: KL Scale @ A2: 1:500

Project No: 8834 Revision: P10

Drawing No: 8834-BOW-A0-00-DR-A-1021

BOWMAN RILEY
ARCHITECTS • BUILDING CONSULTANTS • INTERIORS