

LEGEND

	Survey Station		Bench Mark
	Direction of Footings		Level Position
	Stop Up		Sloping Ceiling
	Fencing		Sloping Masonry
	Hedge		Gates
	Foul Drainage (100mm Pipe)		Tree
	Storm Drainage (100mm Pipe)		Height Spread
	Electricity G/H		Telephone G/H
	Electricity U/G		Fresh Water (100mm Pipe)
	Central Heating		Gas (100mm Pipe)
			Change in Ceiling Height

FENCE TYPES

BW Barbed Wire	IR Iron Railings
CB Close Boarded	LL Larch Lap
CI Corrugated Iron	PR Post and Rail
CL Chain Link	PM Post and Wire
CPG Chestnut Paling	OB Open Boarded
INT Interwoven	WM Wire Mesh

ABBREVIATIONS (Where Applicable)

AGL Above Ground Level	MC Mercury IC
AV Air Valve	MH Manhole
BSL Bollard	MKR Marker
BT British Telecom IC	MNR Metal Railings
BRW Brick Wall	NB Notice Board
BRWBrk Brick Foot Wall	NI No Further Info
CATV Cable TV	OH Overhead
CD Cable Duct	R From Records
CE Clearing Eye	RGS Road Gully
CL Cover Level	RNB Road Name Board
CM Cable Marker	RS Road Sign
CP Catch Pit	RSL Rolled Steel Joist
CPS Conc Paving Slabs	RW Retaining Wall
D Door	RWP Rain Water Pipe
DP Down Pipe	SA Soakaway
ECP Elec Cable Pit	SC Stop Cock
EB Elec Joint Box	ST Stone
EP Electricity Pole	SV Skive Valve
FB Flower Bed	T Trunking
FI Fire Hydrant	TL Threshold Level
FIG Feeds into Ground	TLT Traffic Light
FL Floor Level	TP Telephone Pole
G Gully	TPS Tactile Paving
GAF Gas Meter	U Underground
GSC Gas Stop Cock	U/L Unable to Lift
GV Gas Valve	V Vent
H High/Lighting	VP Vent Pipe
HD Heating Duct	W Window
Hyd Hydrant	WHB Wash Hand Basin
I Inspection Cover	WSC Water Stop Cock
IL Invert Level	WM Water Meter
IO IOB Outlet	WP Water Valve
IP Lamp Post	

BUILDING

ARL Arch Head Level	FCSL False Ceiling
ASL Arch Spring Level	Suffit Level
BSL Beam Soffit Level	LL Landing Level
CBSL Clad Beam	RL Roof Level
SOFL Soffit Level	WASL Window Arch
CH Change in Height of Ceiling	Spring Level
CSL Ceiling Soffit Level	WHM Window Arch Head Level
DHL Door Head Level	WSL Window Sill Level
OSL Duct Soffit Level	WHL Window Head Level

NOTES
LEVEL DATUM OS GPS
THE ORIGIN AND ORIENTATION OF THE SURVEY GRID ARE THOSE OF THE NATIONAL GRID.

DETAIL OBTAINED BY VEHICLES, SKIPS, OR OTHER ITEMS AT TIME OF SURVEY MAY HAVE BEEN MISSED.

UNDERGROUND SERVICES INFORMATION

DRAINAGE	N/A
ELECTRICITY	N/A
GAS	N/A
TELECOM	N/A
WATER	N/A

While all reasonable care has been taken in locating the underground services shown on this plan the completeness or accuracy of the information cannot be guaranteed. Users are advised to satisfy themselves before connections are made.

REV	DATE	PREV JOB NO.	REVISION DETAILS

PARK DESIGNED THE LOFT, UNIT 13 CARLETON MILLS TRADING ESTATE, LEEDS LS12 2QG

JOB TITLE
MYERS GROUP LEEDS ROAD HUDDERSFIELD

DRAWING TITLE
SITE SURVEY

DRAWING 1 OF 1	AUTOCAD DRAWING FILE NAME
SCALE: 1:500 ON A0	SITE.DWG
SHEET SIZE	DATE
A0 841x1189mm	JUN 2018
SURVEYOR	DRAWN
PC	PC
CHECKED	LBP



STATION COORDINATE SCHEDULE

STN	EASTING	NORTHING	LEVEL	DESCRIPTION
101	415260.511	417919.374	59.630	PIPE NAIL IN FARMAC
102	415211.563	417956.680	59.037	HELI NAIL IN FARMAC
103	415227.118	417985.390	58.746	HELI NAIL IN SETTS
104	415233.319	417996.223	58.423	HELI NAIL IN CONCRETE
105	415232.774	418024.423	58.810	HELI NAIL IN CONCRETE
106	415270.111	418076.284	58.930	HELI NAIL IN CONCRETE
107	415263.270	418110.731	58.770	HELI NAIL IN CONCRETE
108	415263.527	418116.175	58.996	PIPE NAIL IN CONCRETE
109	415183.897	418139.082	62.854	PIPE NAIL IN UNMADE
110	415179.996	418164.051	63.279	PIPE NAIL IN UNMADE
111	415198.219	418196.592	63.027	HELI NAIL IN CONCRETE
112	415215.181	418194.628	62.898	HELI NAIL IN CONCRETE
113	415238.364	418241.876	62.667	MAG NAIL IN CONCRETE
114	415262.015	418253.998	59.819	HELI NAIL IN CONCRETE
115	415269.611	418265.541	60.136	TEMPORARY STATION
116	415278.444	418280.951	59.409	HELI NAIL IN CONCRETE
117	415286.634	418337.408	62.881	HELI NAIL IN CONCRETE
118	415289.846	418357.330	63.005	HELI NAIL IN CONCRETE
119	415323.557	418286.453	58.935	HELI NAIL IN CONCRETE
120	415363.724	418253.314	58.514	MAG NAIL IN CONCRETE
121	415311.686	418242.771	58.694	HELI NAIL IN CONCRETE
122	415280.438	418207.293	59.179	MAG NAIL IN FARMAC
123	415220.238	418204.582	58.396	HELI NAIL IN CONCRETE
124	415295.502	418162.551	58.863	HELI NAIL IN CONCRETE
125	415277.691	418050.056	58.724	BOUL IN CONCRETE
126	415320.778	418016.500	58.445	HELI NAIL IN CONCRETE
127	415300.517	417983.214	58.381	HELI NAIL IN CONCRETE
128	415283.083	417990.166	58.417	MAG NAIL IN FARMAC
129	415247.340	417971.254	58.297	HELI NAIL IN CONCRETE
130	415233.918	417948.631	59.761	HELI NAIL IN CONCRETE
131	415278.216	418185.516	58.328	TEMPORARY STATION

418400N
418350N
418300N
418250N
418200N
418150N
418100N
418050N
418000N
417950N
417900N
417850N



418300E
418250E
418200E
418150E
418100E
418050E
418000E
417950E
417900E