

Anstone[®]
Olde Heather Gold



Product samples

The colours reproduced within this product information card are as accurate as the photographic and printing processes will allow. Where colour matching is critical, you are advised to view actual product samples.

These are readily available via our Anstone office by calling **01909 775000** or the sample request area of our website – **www.forticrete.co.uk**

For larger projects, sample panels can be provided.



Anstone[®] Premier Olde Heather Gold Split at David Wilson Homes, Menston, West Yorkshire.

Anstone[®]

Anstone[®] walling products have been developed to match and blend in with the natural stone types found in Northern Britain. All products can be supplied Split or Pitched depending on the requirements of the client.

This document does not form part of any contract and Forticrete cannot accept liability for any errors or omissions.

In order to maintain its position as a market leader, Forticrete operates a policy of continuous product development and therefore reserves the right to alter specifications without notice.

Anstone®

Olde Heather Gold



Texture shown: Split

Texture

The Forticrete Anstone® Premier Range offers a choice of the two most popular types of natural stone finish, Split and Pitched.

Pitched



Tel: 01909 775000 | E-mail: walling@forticrete.com | www.forticrete.com

Specifications

Thermal Conductivity: as Table 3.1, CIBSE Guide A:2007:

Protected: 1.45 W/mK

Exposed: 1.56 W/mK

Typical Dry Material Density: 2050 Kg/m³

Mean Compressive Strength: 25 N/mm²

Coverage: Dependent on the combination of units chosen

Fire Resistance: Class 1A

Drying Shrinkage: Forticrete Walling Stone products have a drying shrinkage value of less than 0.06%

Permeability: Typical 24 hour water absorption = 6%

Forticrete[®]stone
Confidence you can build on

Although the information contained in this product information card and any other information published by Forticrete are believed to be accurate at the date of publication, they are strictly for guidance only and Forticrete accepts no liability in relation to their use or for any losses, howsoever caused. You are responsible for taking all reasonable steps to ensure your use of the goods/products conforms to all applicable health and safety requirements from time to time. If in doubt, please consult appropriately qualified persons. All products sold by Forticrete are sold subject to Forticrete's Terms and Conditions of Sale, a copy of which is available on request.

© Forticrete Ltd. 2013. All rights reserved.

