



Surface Car Park:  
32no Parking spaces incl  
2no Disabled spaces

Parking spaces to be defined with hot applied thermoplastic line markings laid in accordance with IS EN 1436:  
sprayed markings 2.0 +/- 0.5mm  
screed markings 4.0 +/- 1.0mm.  
Colours to be as follows:  
white\_all directional arrows, bay markings, give way signs and floor lettering/ yellow\_disabled bay markings and signage and restricted parking areas



Galv ms Sheffield hoop rack:  
6no Cycle spaces



Trade waste storage/ presentation point:  
1no 1100l, 1no 240l wheelie bins

