

HABITAT WORKS

Weather Hill House, Holmfirth
Biodiversity Net Gain Assessment

23rd September 2024

PREPARED BY: ELLIE COLLIER BSc (Hons), GRADUATE ECOLOGIST

Habitat Works Ltd

Issued By: Ellie Collier

Date: 23rd September 2024

Approved By: Joe Travis

Date: 23rd September 2024

Contents

EXECUTIVE SUMMARY	IV
1. INTRODUCTION	1
1.1 BACKGROUND.....	1
2. METHODOLOGY	2
2.1 BACKGROUND.....	2
2.2 BIODIVERSITY METRIC INPUTS	2
3. BIODIVERSITY METRIC CALCULATIONS	5
3.1 BACKGROUND.....	5
3.2 TRADING RULES.....	5
3.3 ASSUMPTIONS AND LIMITATIONS	6
4. FINDINGS AND EVALUATION	7
4.1 BASELINE HABITATS	7
4.2 POST-DEVELOPMENT HABITATS	7
4.3 NET CHANGE IN BIODIVERSITY	8
4.4 OFF-SITE BASELINE HABITATS.....	9
4.5 RECOMMENDED CHANGES TO POST-DEVELOPMENT HABITATS	9
4.6 NET CHANGE IN BIODIVERSITY INCLUDING OFF-SITE HABITATS.....	10
5. DISCUSSION AND RECOMMENDATIONS	11
5.1 SUMMARY OF BIODIVERSITY NET GAIN DELIVERY	11
5.2 DISCUSSION	11
5.3 HABITAT MANAGEMENT AND MONITORING	11
5.4 BNG GOOD PRACTICE PRINCIPLES.....	11
6. REFERENCES	12
FIGURE 1. BASELINE HABITATS MAP	14
FIGURE 2. POST-DEVELOPMENT HABITATS MAP	16
FIGURE 3. RECOMMENDED POST-DEVELOPMENT HABITATS MAP	18
APPENDIX 1. BNG GOOD PRACTICE PRINCIPLES	20
APPENDIX 2. BIODIVERSITY METRIC CALCULATIONS SUMMARY	22
APPENDIX 3. BIODIVERSITY METRIC WITH RECOMMENDATIONS CALCULATIONS SUMMARY	23

Executive Summary

Habitat Works Limited (Habitat Works) was commissioned in August 2024 by Paul Matthews Architectural to undertake a Biodiversity Net Gain Assessment (BNGA) for approximately 0.0908 ha area at Weather Hill House, Cartworth Moor, Holmfirth, Kirklees, West Yorkshire (central Ordnance Survey National Grid Reference (OS NGR) SE 13685 05888), hereafter referred to as 'the Site'.

This BNGA has been carried out to determine the potential change in biodiversity value of the Site based upon the proposed development and associated post development habitats, using the Department for Environment, Food & Rural Affairs (DEFRA) 'Statutory Biodiversity Metric User Guide' (SBM) (February, 2024).

The Site boundary is detailed within the Paul Matthews Architectural drawing 'Proposed Block Plan' (Dwg No. 24/1044/03, dated 07/2024). The proposals are for alterations and extensions to the dwelling at Weather Hill House.

The total area of the Site has been calculated at 0.0908 ha and baseline area-based habitats recorded for the Site comprise 'Urban – Vegetated garden', 'Urban – Developed land; sealed surface' and 'Urban – Artificial unvegetated, unsealed surface'.

It is anticipated that the current proposals will see the partial loss of 'Urban – Vegetated garden' and 'Urban – artificial unvegetated unsealed surface' alongside a slight increase in 'Urban – Developed land; sealed surface.' Post-development area-based habitat creation has been predicted to include 'Urban – Vegetated garden', 'Urban – Developed land; sealed surface' and 'Urban – artificial unvegetated unsealed surface'.

The current proposals result in a biodiversity value of 0.12 HU representing a net change of -0.0028 HU equating to a -2.22% loss of HU failing to meet the 10% net gain requirement.

Some slight additions to the Site layout are required to reach the net gain requirements.

An area of Off-Site land measuring 1.3672 ha is available immediately to the north of the Site. The retention of the Off-Site 'Grassland – Modified grassland' and the planting of a minimum of two small 'Individual trees – Urban tree' will result in a net unit change of +0.02 HU which is a net change of +15.76% exceeding the 10% net gain requirement.

Given this significant increase in HU, it is considered that this is a significant increase in the biodiversity across the Site and will provide significantly more ecological value on the Site post-development compared to pre-development.

1. Introduction

1.1 Background

- 1.1.1 Habitat Works Limited (Habitat Works) was commissioned in August 2024 by Paul Matthews Architectural to undertake a Biodiversity Net Gain Assessment (BNGA) for approximately 0.0908 ha area of land at Weather Hill House, Cartworth Moor, Holmfirth, Kirklees, West Yorkshire (central Ordnance Survey National Grid Reference (OS NGR) SE 13685 05888), hereafter referred to as 'the Site' and as displayed in Figure 1. This BNGA has been carried out to determine the potential change in biodiversity value of the Site based upon the proposed development and associated post development habitats, using the Department for Environment, Food & Rural Affairs (DEFRA) '*Statutory Biodiversity Metric User Guide*' (SBM) (February, 2024).
- 1.1.2 The Site boundary is detailed within the Paul Matthews Architectural drawing '*Proposed Block Plan*' (Dwg No. 23/961/05, dated 01/2024). The proposals are for alterations and extensions to the dwelling at Weather Hill House.
- 1.1.3 This report details the results of the BNGA using biodiversity metric calculations which have been completed based upon the Habitat Works site walkover undertaken in August 2024, and calculations of the post-development habitats taken from the '*Proposed Block Plan*'. The methodologies employed and all survey findings are described along with an evaluation and assessment of the biodiversity value of the Site. Any recommendations regarding ensuring Biodiversity Net Gain (BNG) are also detailed as required.

2. Methodology

2.1 Background

- 2.1.1 This BNGA uses the industry recognised best practice methodology within the (DEFRA) ‘Statutory Biodiversity Metric User Guide’ (SBM) (February, 2024).
- 2.1.2 The Statutory Biodiversity Metric (SBM) uses habitat features as a measure for their importance and value to nature. The following information on each habitat are required for the metric input:
- Habitat type;
 - Irreplaceable habitat;
 - Area/length;
 - Habitat distinctiveness (automatically calculated);
 - Habitat condition; and,
 - Strategic significance.

2.2 Biodiversity Metric Inputs

Habitat Type

Baseline

- 2.2.1 The Site was surveyed on 9th August 2024 by Senior Ecologist Joe Travis BSc (Hons) MSc ACIEEM and Graduate Ecologist Ellie Collier BSc (Hons).
- 2.2.2 The Site visit included an ecological walkover survey using the UK Habitat Classification (UKHab) system (Butcher *et al.*, 2020). The habitats present on the Site were identified and classified according to the UKHab system which closely aligns with the SBM. The baseline habitats are displayed in Figure 1.
- 2.2.3 The SBM uses a classification system based mainly on the UKHab with inputs from other systems including the Water Framework Directive (WFD) Lakes Typology (UKTAG, 2003); the European Nature Information System (EUNIS) habitat type hierarchical view (EEA, 2019; and Natura 2000 Annex I habitats (JNCC, 2019) in addition to further habitats specific to the SSM.

Post-Development

- 2.2.4 Proposals for the Site have been assessed and habitats present post-development have been based upon the ‘Proposed Block Plan’ and using best knowledge of the likely habitats to be created/retained/lost.
- 2.2.5 The post-development habitats were classified according to the habitat classification system used by the SBM.

Habitat Area/Length

- 2.2.6 The Site was surveyed on 9th August 2024 by Senior Ecologist Joe Travis BSc (Hons) MSc ACIEEM and Graduate Ecologist Ellie Collier BSc (Hons).
- 2.2.7 The area/length of each baseline and post-development habitat type was mapped using QGIS 3.34.5 'Prizren' Geographical Information System (GIS). Area habitats are recorded in hectares (ha) and linear habitats are recorded in kilometres (km) as per the SBM calculator.

Habitat Condition

- 2.2.8 The condition of a habitat is the measure of the biological 'working order' of a habitat judged against the perceived ecological optimum for that habitat. The condition assessments were undertaken using the 'Statutory Biodiversity Metric – Technical Annexe 1: Condition Assessment Sheets and Methodology' spreadsheet (February, 2024).

Baseline

- 2.2.9 Following the UKHab ecological walkover survey at the Site, the condition of each habitat was assessed and either calculated as 'Good', 'Moderate' or 'Poor', where appropriate. Within the SBM, some habitats are not suitable for condition assessment, and as such are automatically calculated as either 'Condition Assessment N/A' or 'N/A – Other'.
- 2.2.10 If a habitat type varied in condition within the Site, these habitats were mapped and recorded separately to allow this distinction.

Post-Development

- 2.2.11 The condition that post-development habitats have been assigned is based upon reasonable and the likely habitat condition in line with the condition assessment criteria. The condition of each habitat was assessed and either calculated as 'Good', 'Moderate' or 'Poor', where appropriate. Within the SBM, some habitats are not suitable for condition assessment, and as such are automatically calculated as either 'Condition Assessment N/A' or 'N/A – Other'.
- 2.2.12 If a habitat type varied in condition within the Site, these habitats were mapped and recorded separately to allow this distinction.

Habitat Strategic Significance

- 2.2.13 The SBM accounts for whether the habitats are situated within an area locally identified as significant for nature conservation.
- 2.2.14 Data on the areas and habitats locally identified as significant for nature conservation were obtained from the following sources:

-
- Multi-Agency Geographical Information for the Countryside (MAGIC) website for mapped statutory designated sites (<https://magic.defra.gov.uk/MagicMap.aspx>); and,
 - Habitats listed within the Kirklees Biodiversity Action Plan (2007).

3. Biodiversity Metric Calculations

3.1 Background

- 3.1.1 Biodiversity metric calculations provide a numerical score for the value of existing habitats on the Site and their likely value post-development in Habitat Units (HU), Hedgerow Units (HeU) and Watercourse Units (WU) (where present and applicable), to quantitatively assess the impact of the proposed development.
- 3.1.2 Using the SBM, habitat values are calculated via the criteria described within Sections 2.1 and 2.2. This results in individual scores for each habitat, and subsequently baselines for HU, HeU and WU (where present and appropriate).
- 3.1.3 Individual trees are classified as either 'Urban Tree' or 'Rural Tree', depending on the extent of urbanisations surrounding them. The size of an individual tree is dependent on the diameter of the trunk at breast height (centimetres), and categorised as either 'Small', 'Medium', 'Large' or 'Very Large'. A biodiversity metric area equivalent in hectares is automatically calculated within the SBM dependant on the number of trees and their individual sizes. This area is a separate measurement to other habitat areas and as such, is not included within the total habitat area of the Site.
- 3.1.4 The post-development value can also be calculated for habitats where factors including time to target condition and difficulty of creation/enhancement are also taken into consideration. The values for area habitats and linear habitats are calculated separately. This provides an overall picture of the biodiversity net gain or loss because of a development. To achieve BNG, all three of HU, HeU and WU are treated individually, and individual gains cannot be combined to form an overall gain for the Site.

3.2 Trading Rules

- 3.2.1 The SBM considers distinctiveness as described earlier and using this data, SSM applies trading rules that require that any habitat loss is replaced on a 'like for like' or 'like for better' basis. The trading rules are detailed below in Table 1.

Table 1 – Trading Rules within the SSM

Distinctiveness Group	Trading Rules
Very High	Bespoke compensation likely to be required
High	Same habitat required
Medium	Same broad habitat or a higher distinctiveness habitat required
Low	Same distinctiveness or better habitat requires
Very Low	Compensation not required

3.3 Assumptions and Limitations

- 3.3.1 For strategic significance, all habitats on the Site (both baseline and post-development) have been considered '*Area/compensation not in local strategy/no local strategy*' as they do not qualify as priority habitats and are not identified on any strategic plans.
- 3.3.2 An area of land surrounding the Site within the developer's ownership is available for habitat creation if a 10% gain cannot be achieved on the Site. As such, the calculations have been undertaken within the SBM rather than the Small Sites Metric (SSM) as the SSM does not have the functionality to include off-site habitat changes, even though the development meets the criteria to use the SSM.
- 3.3.3 The quantification of biodiversity is one of several factors to be considered when assessing the impact of the proposed development on biodiversity. Note that this BNGA does not cover potential impacts of the proposed development on protected species and designated sites.
- 3.3.4 The information contained within this report is considered valid for a period of 24 months from the date of the survey visit (CIEEM, 2019). If the development has not commenced by August 2026, it is recommended that the Site is fully re-surveyed to determine if there have been any significant changes to baseline habitats within that timeframe.

4. Findings and Evaluation

4.1 Baseline Habitats

- 4.1.1 Baseline area-based habitats recorded for the Site comprise, ‘Urban – Artificial unvegetated, unsealed surface’, ‘Urban – Vegetated garden’ and ‘Urban – Developed land; sealed surface’ (see Figure 1).
- 4.1.2 The total area of the Site has been calculated at 0.0908 ha. The habitat type, irreplaceability, distinctiveness, condition, area and HU of the area-based habitats are provided within Table 2. Baseline area-based habitats have a biodiversity value of 0.13 HU.

Table 2 – Site Baseline Area-based Habitats and Habitat Units

Habitat Type	Irreplaceable Habitat?	Distinctiveness	Condition	Area (ha)	Habitat Units (HU)
Urban – Artificial unvegetated, unsealed surface	No	V. Low	N/A - Other	0.0156	0.00
Urban – Vegetated garden	No	Low	N/A - Condition assessment	0.0631	0.13*
Urban – Developed land; sealed surface	No	V. Low	N/A - Other	0.0121	0.00
Total Habitat Units (HU)					0.13*

*Individual habitat HU are rounded to two decimal places; however, the calculator outputs the Site’s total HU to four decimal places.

4.2 Post-development Habitats

- 4.2.1 The following calculations present a version of the completed feasibility biodiversity metric calculations based upon the post-development proposals as show in the ‘Proposed Block Plan’. A summary of the calculations is provided in Appendix 2.
- 4.2.2 It is anticipated that the proposals will see the partial loss of ‘Urban – Vegetated garden’ and ‘Urban – artificial unvegetated unsealed surface’ alongside a slight increase in ‘Urban – Developed land; sealed surface.’
- 4.2.3 Post-development area-based habitat creation has been predicted to include ‘Urban – Vegetated garden’, ‘Urban – Developed land; sealed surface’ and ‘Urban – Artificial unvegetated, unsealed surface’
- 4.2.4 The predicted area-based habitat type, distinctiveness, condition, area and HU of the area-based habitats are provided within Table 3. The post-development area-based habitats estimated a biodiversity value of 0.12 HU and are displayed within Figure 2.

Table 3 – Post-development Area-based Habitats Condition and Habitat Units

Habitat Type	Distinctiveness	Condition	Area (ha)	Habitat Units (HU)
Lost				
<i>Urban – Vegetated garden</i>	Low	N/A - Other	0.0014	0.01*
<i>Urban – Artificial unvegetated, unsealed surface</i>	V. Low	N/A - Other	0.0026	0.00
Retained				
<i>Urban – Developed land; sealed surface</i>	V. Low	N/A - Other	0.0121	0.00
Created				
<i>Urban – Developed land; sealed surface</i>	V. Low	N/A - Other	0.0040	0.00
Total Habitat Units (HU)				0.12

*Individual habitat HU are rounded to two decimal places; however, the calculator outputs the Site's total HU to four decimal places.

4.3 Net Change in Biodiversity

4.3.1 Considering the reasonable assumptions and estimates made within this report as soft landscape drawings were not available at the time writing the construction of the proposed development is predicted to result in a net unit change of -0.0028 HU which is a net percentage change of -2.22% as detailed in Table 4.

Table 4 – Summary of Biodiversity Net Gain Calculations

Habitat Type	Baseline Units	Post-development Units	Change in Units	% Change in Units
Habitat Units (HU)	0.13*	0.12*	-0.0028	-2.22%

*Individual habitat HU are rounded to two decimal places; however, the calculator outputs the Site's total HU to four decimal places.

4.3.2 For the Site to achieve a greater than 10% net gain in HU, a total of 0.14 HU would have to be proposed post development. This leaves a deficit of 0.02 HU, as detailed in Table 5.

Table 5 – Summary of Biodiversity Units required post-development

Habitat Type	Target	Baseline Units	Units Required	Unit Deficit as per Current Proposals
Habitat Units (HU)	10.00%	0.13*	0.14*	0.02*

*Individual habitat HU are rounded to two decimal places; however, the calculator outputs the Site's total HU to four decimal places.

4.4 Off-Site Baseline Habitats

- 4.4.1 Off-Site Baseline area -based habitats recorded for the Site include 'Grassland – Modified grassland' (see Figure 1 – 'Area 1'). This area is immediately surrounding the Site, and as such, is within the 'Compensation inside LPA boundary or NCA of impact site' spatial risk category.
- 4.4.2 The total Off-Site area has been calculated at 1.3672 ha. The habitat type, irreplaceability, distinctiveness, condition, area and HU of the area-based habitats are provided within Table 6. Baseline area-based habitats have a biodiversity value of 2.73 HU.

Table 6 – Off-Site Baseline Area Based Habitats, Condition and Habitat Units

Habitat Type	Irreplaceable Habitat?	Distinctiveness	Condition	Area (ha)	Habitat Units (HU)
Grassland – Modified Grassland	No	Low	Poor	1.3672	2.73
Total Habitat Units (HU)					2.73

4.5 Recommended Changes to Post-development Habitats

- 4.4.1 Alterations are required to achieve the 10% net gain in HU on the Site. The following calculations present a version of the completed feasibility biodiversity metric calculations based upon suggested alterations to the post-development proposals as show in the 'Proposed Block Plan', as a possible way to achieve the 10% net gain on the Site. A summary of these calculations is provided in Appendix 3.
- 4.4.2 The recommended alterations post-development comprises the planting of a minimum of two 'Individual trees – Urban tree' off site in Area 1 as indicated by Figure 3. This will increase the HU on the Site. All other habitat changes will remain the same.
- 4.4.3 The recommended area-based habitat type, distinctiveness, condition, area and HU of the area-based habitats are provided within Table 7. The post-development area-based habitats estimated a biodiversity value of 2.76 HU and are displayed within Figure 3.

Table 7 – Recommended Post-development Area-based Habitats Condition and Habitat Units

Habitat Type	Distinctiveness	Condition	Area (ha)	Habitat Units (HU)
Retained				
Grassland – Modified Grassland	Low	Poor	1.3672	2.73
Created				
Individual trees- Urban tree	Small	Poor	0.0081	0.02*
Total Habitat Units (HU)				2.76*

* Individual habitat HU are rounded to two decimal places; however, the calculator outputs the Site's total HU to four decimal places.

4.6 Net Change in Biodiversity including Off-Site Habitats

- 4.5.1 Considering the reasonable assumptions and estimates made within this report of recommended changes to the proposed development, it is predicted that the proposed development will result in a net unit change of ± 0.02 HU which is a net percentage change of +15.76% as detailed in Table 8.

Table 8 – Summary of Biodiversity Net Gain Calculations

Habitat Type	Baseline Units	Post-development Units	Change in Units	% Change in Units
Habitat Units (HU)	2.86	2.88	+0.02*	+15.76%

* Individual habitat HU are rounded to two decimal places; however, the calculator outputs the Site's total HU to four decimal places.

5. Discussion and Recommendations

5.1 *Summary of Biodiversity Net Gain Delivery*

5.1.1 The current proposals, with the inclusion of habitat creation within the Off-Site area, result in a biodiversity value of 2.88 HU, representing a net change of +0.02 HU equating to a +15.76%; exceeding the 10% net gain requirement.

5.2 *Discussion*

5.2.1 Given the current proposals, it is considered that a 10% net gain in HU would be achievable.

5.2.2 Changes to the proposed layout comprising the planting of at least 2 '*Individual trees – Urban tree*' off-site (Area 1), would be sufficient to achieve the necessary gains in biodiversity on the Site post development.

5.3 *Habitat Management and Monitoring*

5.3.1 Ordinarily, the production of a Biodiversity Enhancement Management Plan (BEMP) is recommended to ensure that the Site habitats deliver the habitat scores listed within the final design stage BNGA. However, given that the proposed urban trees are the only habitat that requires condition assessment, and this is not integral to the Site achieving the necessary BNG, a BEMP is not considered necessary in this instance.

5.4 *BNG Good Practice Principles*

5.4.1 Appendix 1 details the BNG Good Practice Principles (CIEEM, CIRIA & IEMA, 2016) which should be adhered to when undertaking BNGAs in association with proposed developments. The actions within Appendix 1 should be considered throughout the design stage of a development at this Site.

6. References

- CIEEM (2019). 'Advice Note: On the Lifespan of Ecological Reports and Surveys'. Chartered Institute of Ecology and Environmental Management, Winchester. Available: <https://cieem.net/wp-content/uploads/2019/04/Advice-Note.pdf>
- CIEEM, CIRIA & IEMA (2016). 'Biodiversity Net Gain – Good practice principles for development'. Available: <https://cieem.net/wp-content/uploads/2019/02/Biodiversity-Net-Gain-Principles.pdf>
- DEFRA (2011). 'Biodiversity 2020: A strategy for England's wildlife and ecosystem services. Available: <https://assets.publishing.service.gov.uk/media/5a78c263ed915d04220651ea/pb13583-biodiversity-strategy-2020-111111.pdf>
- DEFRA (2018). 'A Green Future: Our 25 Year Plan to Improve the Environment'. Available: https://assets.publishing.service.gov.uk/media/65fd713d65ca2f00117da89e/CD1.H_HM_Government_A_Green_Future_Our_25_Year_Plan_to_Improve_the_Environment.pdf
- DEFRA (2024) 'The Small Sites Metric (Statutory Biodiversity Metric): User Guide'. Available: https://assets.publishing.service.gov.uk/media/65c60ec19c5b7f0012951bdd/The_Small_Sites_Metric_Statutory_Biodiversity_Metric_-_User_Guide.pdf
- Department for Levelling Up, Housing & Communities (DLUHC) (2023). 'National Planning Policy Framework'. Available: https://assets.publishing.service.gov.uk/media/65a11af7e8f5ec000f1f8c46/NPPF_December_2023.pdf
- European Environment Agency (EEA) (2023). 'Eunis habitat distribution plots (spatial data)'. Available: <https://www.eea.europa.eu/en/datahub/datahubitem-view/ce3e4bf4-e929-404a-88c7-37f2c614fd1d>
- DEFRA (2011). 'Biodiversity 2020: A strategy for England's wildlife and ecosystem services. Available: <https://assets.publishing.service.gov.uk/media/5a78c263ed915d04220651ea/pb13583-biodiversity-strategy-2020-111111.pdf>
- His Majesty's Stationery Office (HMSO) (2006). 'Natural Environment and Rural Communities Act 2006'. Available: https://www.legislation.gov.uk/ukpga/2006/16/pdfs/ukpga_20060016_en.pdf
- HMSO (2024). 'The Biodiversity Gain Requirements (Irreplaceable Habitat) Regulations 2024'. Available: https://www.legislation.gov.uk/uksi/2024/48/pdfs/uksi_20240048_en.pdf
- Joint Nature Conservation Committee (JNCC) (2019). 'Annex I Habitats List'. Available: <https://sac.jncc.gov.uk/habitat/>


Kirklees Council Kirklees Council (2007). 'Kirklees Biodiversity Action Plan'. Available: <https://www.kirklees.gov.uk/beta/delivering-services/pdf/biodiversity-species.pdf>

Natural England (2024). 'The Statutory Biodiversity Metric – Technical Annex 1: Condition Assessment Sheets and Methodology'. Available: <https://www.gov.uk/government/publications/statutory-biodiversity-metric-tools-and-guides>

UKHab Ltd (2023). 'The UK Habitat Classification: Version 2.0'. Available: <https://www.ukhab.org>


UK Technical Advisory Group (UKTAG) on the Water Framework Directive (2003). 'Guidance on Typology for Lakes for the UK'. Available: https://www.wfduk.org/sites/default/files/Media/Characterisation%20of%20the%20water%20environment/Lakes%20typology_Final_010604.pdf

Figure 1. Baseline Habitats Map



Legend


-  Redline Boundary
-  Urban - Developed land, sealed surface (buildings)
-  Urban - Artificial unvegetated; unsealed surface
-  Urban - Vegetated garden
-  Grassland - Modified grassland
-  Off-Site Area (Area 1)



Paul Matthews Architectural
Weatherhill House


Figure 1
Baseline Habitats Map

Figure 2. Post-development Habitats Map



Legend

- Redline Boundary
- Urban - Developed land, sealed surface (buildings)
- Urban - Artificial unvegetated; unsealed surface
- Urban - Vegetated garden
- Grassland - Modified grassland
- Off-Site Area (Area 1)



Paul Matthews Architectural
Weatherhill House


Figure 2
Post Development Habitats Map

Figure 3. Recommended Post-development Habitats Map



Legend

-  Redline Boundary
-  Urban - Developed land, sealed surface (buildings)
-  Urban - Artificial unvegetated; unsealed surface
-  Urban - Vegetated garden
-  Grassland - Modified grassland
-  Individual trees - Urban tree (Indicative locations)
-  Off-Site Area (Area 1)



Paul Matthews Architectural
Weatherhill House

Figure 3
Recommended Post Development Habitats Map

Appendix 1. BNG Good Practice Principles

The BNG Good practice principles for development are based upon issued joint guidance from the Chartered Institute for Ecology and Environmental Management (CIEEM), the Construction Industry Research and Information Association (CIRIA) and the Institute for Environmental Management and Assessment (IEMA) (CIEEM, CIRIA & IEMA, 2019).

The Good practice principles for development outlines 10 principles which should be followed to ensure that BNG is undertaken in the most beneficial and appropriate manner possible. These principles are outlined in the table below.

Principle	Description
Principle 1. Apply the Mitigation Hierarchy	Do everything possible to first avoid and then minimise impacts on biodiversity. Only as a last resort, and in agreement with external decision-makers where possible, compensate for losses that cannot be avoided. If compensating for losses within the development footprint is not possible or does not generate the most benefits for nature conservation, then offset biodiversity losses by gains elsewhere.
Principle 2. Avoid losing biodiversity that cannot be offset by gains elsewhere	Avoid impacts on irreplaceable biodiversity – these impacts cannot be offset to achieve No Net Loss or Net Gain.
Principle 3. Be inclusive and equitable	Engage stakeholders early, and involve them in designing, implementing, monitoring and evaluating the approach to Net Gain. Achieve Net Gain in partnership with stakeholders where possible, and share the benefits fairly among stakeholders.
Principle 4. Address risks	Mitigate difficulty, uncertainty and other risks to achieving Net Gain. Apply well-accepted ways to add contingency when calculating biodiversity losses and gains in order to account for any remaining risks, as well as to compensate for the time between the losses occurring and the gains being fully realised.
Principle 5. Make a measurable Net Gain contribution	Achieve a measurable, overall gain ¹ for biodiversity and the services ecosystems provide while directly contributing to wards nature conservation priorities. <small>¹ – Net Gain has been described as a measurable target for development projects where impacts on biodiversity are outweighed by a clear mitigation hierarchy approach to first avoid then minimise impacts, including through restoration and / or compensation. Adhering to these Net Gain principles (i.e. pursuing all principles together) will help in under-pinning good practice for achieving and sustaining Net Gain.</small>
Principle 6. Achieve the best outcomes for biodiversity	Achieve the best outcomes for biodiversity by using robust, credible evidence and local knowledge to make clearly-justified choices when: <ul style="list-style-type: none"> • Delivering compensation that is ecologically equivalent in type, amount and condition, and that accounts for the location and timing of biodiversity losses • Compensating for losses of one type of biodiversity by providing a different type that delivers greater benefits for nature conservation

	<ul style="list-style-type: none"> • Achieving Net Gain locally to the development while also contributing towards nature conservation priorities at local, regional and national levels • Enhancing existing or creating new habitat • Enhancing ecological connectivity by creating more, bigger, better and joined areas for biodiversity
Principle 7. Be additional	Achieve nature conservation outcomes that demonstrably exceed existing obligations (i.e. do not deliver something that would occur anyway).
Principle 8. Create a Net Gain legacy	<p>Ensure Net Gain generates long-term benefits by:</p> <ul style="list-style-type: none"> • Engaging stakeholders and jointly agreeing practical solutions that secure Net Gain in perpetuity² • Planning for adaptive management and securing dedicated funding for long-term management • Designing Net gain for biodiversity to be resilient to external factors, especially climate change • Mitigating risks for other land uses • Avoiding displacing harmful activities from one location to another • Supporting local-level management of Net Gain activities <p><small>² – Biodiversity compensation should be planned for a sustained Net Gain over the longest possible timeframe. For development in the UK, the expectation is that compensating sites will be secured for at least the lifetime of the development (e.g. often 25-30 years) with the objective of Net Gain management continuing in the future.</small></p>
Principle 9. Optimise sustainability	Prioritise Biodiversity Net Gain and, where possible, optimise the wider environmental benefits for a sustainable society and economy.
Principle 10. Be Transparent	Communicate all Net Gain activities in a transparent and timely manner, sharing the learning with all stakeholders.

Appendix 2. Biodiversity Metric Calculations Summary

Weatherhill House		Return to results menu		
Headline Results				
Scroll down for final results ▲				
On-site baseline	Habitat units	0.13		
	Hedgerow units	0.00		
	Watercourse units	0.00		
On-site post-intervention <small>(including habitat retention, creation & enhancement)</small>	Habitat units	0.12		
	Hedgerow units	0.00		
	Watercourse units	0.00		
On-site net change <small>(units & percentage)</small>	Habitat units	0.00	-2.22%	
	Hedgerow units	0.00	0.00%	
	Watercourse units	0.00	0.00%	
On-site net gain is less than target set ▲				
Off-site baseline	Habitat units	2.73		
	Hedgerow units	0.00		
	Watercourse units	0.00		
Off-site post-intervention <small>(including habitat retention, creation & enhancement)</small>	Habitat units	2.73		
	Hedgerow units	0.00		
	Watercourse units	0.00		
Off-site net change <small>(units & percentage)</small>	Habitat units	0.00	0.00%	
	Hedgerow units	0.00	0.00%	
	Watercourse units	0.00	0.00%	
Combined net unit change <small>(including all on-site & off-site habitat retention, creation & enhancement)</small>				
Spatial risk multiplier (SRM) deductions	Habitat units	0.00		
	Hedgerow units	0.00		
	Watercourse units	0.00		
FINAL RESULTS				
Total net unit change <small>(including all on-site & off-site habitat retention, creation & enhancement)</small>	Habitat units	0.00		
	Hedgerow units	0.00		
	Watercourse units	0.00		
Total net % change <small>(including all on-site & off-site habitat retention, creation & enhancement)</small>	Habitat units	-2.22%	Total net gain achieved is less than target set ▲	
	Hedgerow units	0.00%		
	Watercourse units	0.00%		
Trading rules satisfied?	No - Check Trading Summaries ▲			
Unit Type	Target	Baseline Units	Units Required	Unit Deficit
Habitat units	10.00%	0.13	0.14	0.02
Hedgerow units	10.00%	0.00	0.00	0.00
Watercourse units	10.00%	0.00	0.00	0.00
				No additional hedgerow units required to meet target ✓
				No additional watercourse units required to meet target ✓

Appendix 3. Biodiversity Metric with Recommendations Calculations Summary

Weatherhill House					
Headline Results				Return to results menu	
Scroll down for final results ▲					
On-site baseline	Habitat units			0.13	
	Hedgerow units			0.00	
	Watercourse units			0.00	
On-site post-intervention <small>(including habitat retention, creation & enhancement)</small>	Habitat units			0.12	
	Hedgerow units			0.00	
	Watercourse units			0.00	
On-site net change <small>(units & percentage)</small>	Habitat units			0.00	
	Hedgerow units			0.00%	
	Watercourse units			0.00%	
				-2.22%	
On-site net gain is less than target set ▲					
Off-site baseline	Habitat units			2.73	
	Hedgerow units			0.00	
	Watercourse units			0.00	
Off-site post-intervention <small>(including habitat retention, creation & enhancement)</small>	Habitat units			2.78	
	Hedgerow units			0.00	
	Watercourse units			0.00	
Off-site net change <small>(units & percentage)</small>	Habitat units			0.02	
	Hedgerow units			0.00%	
	Watercourse units			0.00%	
				0.83%	
Combined net unit change <small>(including all on-site & off-site habitat retention, creation & enhancement)</small>	Habitat units			0.02	
	Hedgerow units			0.00	
	Watercourse units			0.00	
Spatial risk multiplier (SRM) deductions	Habitat units			0.00	
	Hedgerow units			0.00	
	Watercourse units			0.00	
FINAL RESULTS					
Total net unit change <small>(including all on-site & off-site habitat retention, creation & enhancement)</small>	Habitat units			0.02	
	Hedgerow units			0.00	
	Watercourse units			0.00	
Total net % change <small>(including all on-site & off-site habitat retention, creation & enhancement)</small>	Habitat units			16.78%	
	Hedgerow units			0.00%	
	Watercourse units			0.00%	
Trading rules satisfied?	Yes ✓				
Unit Type	Target	Baseline Units	Units Required	Unit Deficit	
Habitat units	10.00%	0.13	0.14	0.00	No additional area habitat units required to meet target ✓
Hedgerow units	10.00%	0.00	0.00	0.00	No additional hedgerow units required to meet target ✓
Watercourse units	10.00%	0.00	0.00	0.00	No additional watercourse units required to meet target ✓