



## Wall Lights

### Description

This range of stainless steel and powdered black outdoor wall lights are highly decorative and available in fixed and up/down models (PIR version available)

### Features

- Ideal for residential applications including domestic gardens and walkways
- Stainless steel durable 304 grade body and glass diffuser
- Black fittings are black powder coated
- Modern aesthetically pleasing design
- PIR fittings have manual override function
- PIR has adjustable lux, time and sensitivity settings with fixed 8m detection range
- Supplied without lamp
- 2-year Guarantee

### Range

GF621	Fixed Wall Light-Stainless steel
GF6010	Fixed Wall Light-Black
GF623	Adjustable Wall Light-Stainless steel
GF6011	Adjustable Wall Light-Black
GF622	Up/Down Wall Light-Stainless steel
GF6012	Up/Down Wall Light-Black
GF625	Up/Down Wall Light with PIR-Stainless steel
GF6013	Up/Down Wall Light with PIR-Black

### Technical Specification

Voltage	220V-240V
Frequency	50-60Hz
Construction	304 Stainless Steel & Glass
IP Rating	IP44
Dimmable	No
Light Source	35W GU10 LED
Lifespan	30,000hrs
Standards	BS EN 60598-1

### Dimensions

	Height	Width	Diameter
GF621	110mm	92mm	60mm
GF6010	110mm	92mm	60mm
GR623	132mm	92mm	60mm
GF6011	132mm	92mm	60mm
GF622	210mm	92mm	60mm
GF6012	210mm	92mm	60mm
GF625	220mm	95mm	60mm
GF6013	220mm	95mm	60mm

Contact your local authority for information concerning the correct disposal of your product.