



PLANT SCHEDULE											
Feature Trees											
Abbrev.	BotanicalName	Form	Age	GirthDia.(cm)	Height(cm)	Clear Stem(cm)	Root Type	Container Size	Habit	Min.no.ofBreaks	Comments
ACE KIN	Acer campestre 'Streetwise'	Standard (Extra Heavy)	3x	16-18	450-625	min 200	RB		/	/	/
ACE SEN	Acer platanoides 'Crimson Sentry'	Standard (Extra Heavy)	3x	16-18	450-625	min 200	RB		/	/	/
BET FAS	Betula albosinensis 'Fascination'	Standard (Extra Heavy)	3x	16-18	400-450	min 200	RB		/	/	/
CAR FON	Carpinus betulus 'Frons Fontane'	Standard (Extra Heavy)	3x	16-18	400-450	min 200	RB		/	/	/
LIR TUL	Liriodendron tulipifera	Standard (Extra Heavy)	3x	16-18	400-450	min 200	RB		/	/	/
PRU PLE	Prunus avium 'Plena'	Standard (Extra Heavy)	3x	16-18	400-450	min 200	RB		/	/	/
PRU ACC	Prunus 'Accolade'	Standard (Extra Heavy)	3x	16-18	400-450	min 200	RB		/	/	/
PYR CHA	Pyrus calleryana 'Chanticleer'	Standard (Extra Heavy)	3x	16-18	400-450	min 200	RB		/	/	/
ULM HOR	Ulmus 'New Horizon'	Standard (Extra Heavy)	3x	16-18	400-450	min 200	RB		/	/	/

Feature Multistem Trees						
Abbrev.	BotanicalName	CommonName	Heightcm	Root Condition / Container Size		Specification
ACE CAM	Acer campestre	Common Maple	300-350	RB		3x; EHS; clear stem min. 200cm; 5 brks
AME LAM	Amelanchier lamarckii	Juneberry	300-350	RB		3x; Multi-stem; bushy; 3 stems min.
BET JAC	Betula utilis jacquemontii	White-barked Himalayan Birch	300-350	RB		Multi-stem; bushy; 3 stems min.

Standard Boundary Trees											
Abbrev.	BotanicalName	Form	Age	GirthDia.(cm)	Height(cm)	Clear Stem(cm)	Root Type	Container Size	Habit	Min.no.ofBreaks	Comments
PIN NIG	Pinus nigra	Standard (Extra Heavy)	5x	25-30	500-550	min 200	RB		Leader with laterals; clear stem 150-175cm	/	/

Feathered Boundary Trees											
Abbrev.	BotanicalName	Form	Age	GirthDia.(cm)	Height(cm)	Clear Stem(cm)	Root Type	Container Size	Habit	Min.no.ofBreaks	Comments
BET NIG	Betula nigra	Standard (Extra Heavy); Feathered; 7 breaks	3x	16-18	400-450	/	RB		Leader with laterals; clear stem 150-175cm	/	/

Woodland Trees						
Abbrev.	BotanicalName	CommonName	Heightcm	Root Condition / Container Size		Specification
ACE CAM	Acer campestre	Common Maple	16-18	400-450	RB	3x; EHS; clear stem min. 200cm; 5 brks
BET PEN	Betula pendula	Common Silver Birch	16-18	400-450	RB	3x; EHS; clear stem min. 200cm
BET PUB	Betula pubescens	Dowry Birch	16-18	400-450	RB	3x; Large Feathered
CAR BET	Carpinus betulus	Common Hornbeam	16-18	400-450	RB	3x; EHS; clear stem min. 200cm
SOR AUC	Sorbus aucuparia	Rowan	16-18	400-450	RB	3x; EHS; clear stem min. 200cm
PIN SYL	Pinus sylvestris	Scots Pine	16-18	400-450	RB	3x; EHS; clear stem min. 200cm

Woodland Multistem Trees						
Abbrev.	BotanicalName	CommonName	Heightcm	Root Condition / Container Size		Specification
ACE CAM	Acer campestre	Common Maple	16-18	400-450		3x; EHS; clear stem min. 200cm; 5 brks

Woodland Whip Barrier Planting Mix							
Mix/s	BotanicalName	CommonName	Form	Age	Heightcm	Root Condition / Container Size	Comments
15	Acer campestre	Common Maple	Transplant - seed raised	1+1	60-80	RB	Rabbit guards with canes to be used for all whips.
10	Betula pubescens	Common Silver Birch	Transplant - seed raised	1+1	60-80	RB	
15	Corylus avellana	Hazel	Transplant - seed raised	1+1	60-80	RB	
10	Malus sylvestris	Crab Apple	Transplant - seed raised	1+1	60-80	RB	Chestnut cleft post with wire and mesh fencing to run along east facing boundary of east Woodland Whip Barrier Planting area.
10	Prunus avium	Wild Cherry	Transplant - seed raised	1+1	60-80	RB	
10	Prunus padus	Bird Cherry	Transplant - seed raised	1+1	60-80	RB	
10	Quercus robur	English Oak	Transplant - seed raised	1+1	60-80	RB	

Woodland Understorey Meadow Seed Mix			
ID Code	Seed Mixture Product Name	Supplier	Sowing Rate
EH1	Hedgerow Mixture	Emorsgate Seeds	5g/ sqm

Instant Hedging A							
Abbrev.	BotanicalName	CommonName	Heightcm	Root Condition / Container Size	Specification		Density (no./ linear m)
GRI LIT	Griselinia littoralis	Kapuka	100-120	76L	Readyhedge instant hedging; 35cm wide x 100cm long; pre-formed with continuous root-strip, dense, straight-sided, feathered to base, neatly clipped		1

Instant Hedging B							
Abbrev.	BotanicalName	CommonName	Heightcm	Root Condition / Container Size	Specification		Density (no./ linear m)
FAG SYL	Fagus sylvatica	Common Beech	180	76L	Readyhedge instant hedging; 35cm wide x 100cm long; pre-formed with continuous root-strip, dense, straight-sided, feathered to base, neatly clipped		1

Sensory Mix							
Mix/s	BotanicalName	CommonName	Root Condition / Container Size	Specification		Density (no./ m²)	Groupings
10	Alchemilla mollis	Lady's Mantle	2L	Full pot	7	3 or 5	
15	Geranium macrorrhizum 'White-ness'	Big-root Cranebill 'White-Ness'	2L	Full pot			
10	Lavandula angustifolia 'Hidcotte'	English Lavender 'Hidcotte'	2L	Full pot			
20	Pericaria affinis 'Darjeeling Red'	Knotted 'Darjeeling Red'	2L	Branched; 2 brks			
15	Sedum spectabile 'Autumn Joy'	Stonecrop 'Autumn Joy'	2L	Full pot			
15	Vinca minor 'Gertrude Jekyll'	Lesser Periwinkle 'Gertrude Joy'	2L	Full pot			
15	Stipa tenuifolia	Mexican Feather Grass	2L	Full pot			

Shade Sensory Mix							
Mix/s	BotanicalName	CommonName	Root Condition / Container Size	Specification		Density (no./ m²)	Groupings
5	Anemone hybrida 'September Charm'	Japanese Anemone 'September Charm'	2L	Full pot	7	3 or 5	
5	Astrantia major 'Burgundy Major'	Masterwort 'Burgundy Major'	2L	Full pot			
10	Dryopteris erythrosora	Copper Shield Fern	2L	Full pot			
15	Dryopteris wolffiana	Alpine Wood Fern	2L	Full pot			
20	Hakonechloa macra	Japanese Forest Grass	2L	Full pot			
15	Luzula nivea	Snow Rush	2L	Full pot			
15	Pachysandra terminalis	Japanese Spurge	2L	Full pot			
5	Primula officinalis 'Sissinghurst white'	Lungwort 'Sissinghurst white'	2L	Full pot	2L		
10	Thalictrum cordifolium 'Pink Bouquet'	Foam Flower 'Pink Bouquet'	2L	Full pot			

Semi-shade Amenity Mix							
Mix/s	BotanicalName	CommonName	Root Condition / Container Size	Specification		Density (no./ m²)	Groupings
5	Alchemilla mollis	Lady's Mantle	2L	Full pot	7	5 or 7	
10	Asplenium scolopendrium	Hart's Tongue Fern	2L	Full pot			
8	Aster x frikartii 'Minch'	Michaelmas Daisy 'Minch'	2L	Full pot			
10	Brunnera macrophylla 'Jack Frost'	Siberian bugloss 'Jack Frost'	2L	Full pot			
8	Calamagrostis x acutiflora 'Karl Foerster'	Feather reed grass	2L	Full pot			
8	Geranium phaeum 'Semaphore'	Dusky Cranebill	2L	Full pot			
10	Geranium 'Rozanne'	Cranebill 'Rozanne'	2L	Full pot			
18	Hakonechloa macra	Japanese Forest Grass	2L	Full pot	2L		
5	Primula officinalis 'Sissinghurst White'	Lungwort 'Sissinghurst White'	2L	Full pot			
10	Sarcococca confusa	Sweet Box	2L	Bushy; 3 brks			
8	Veronica bonariensis	Argentinian Vervain	2L	Full pot			

Semi-shade Amenity - Bulb Mix						
Mix/s	BotanicalName	CommonName	Specification	Density (no./ m²)		Groupings
30	Chionodoxa forbesii	Forbes' Glory of the Snow	Grade 5/6	12	5 or 7	
40	Crocus chrysanthus 'Snow Bunting'	Golden Crocus 'Snow Bunting'	Grade 7/+			
30	Muscari armeniacum	Armenian Grape Hyacinth	Grade 8/9			

Shade Amenity Mix						
Mix/s	BotanicalName	CommonName	Root Condition / Container Size	Specification		Density (no./ m²)
15	Brunnera macrophylla	Siberian Bugloss	2L	Full pot	7	5 or 7
15	Geranium x oxonianum 'Wargrave Pink'	French Cranebill 'Wargrave Pink'	2L	Full pot		
15	Linopie muscari	Big Blue Lilyturf	2L	Full pot		
15	Luzula sylvatica	Great Wood-rush	2L	Full pot; Sept to April planting; British native-orign		
20	Pachysandra terminalis	Japanese Spurge	2L	Shedl shoots; 7 brks		
20	Polypodium vulgare	Common Polypody	2L	Full pot		

Shade Amenity - Bulb Mix						
Mix/s	BotanicalName	CommonName	Specification	Density (no./ m²)		Groupings
30	Chionodoxa forbesii	Forbes' Glory of the Snow	Grade 5/6	12	5 or 7	
40	Crocus chrysanthus 'Snow Bunting'	Golden Crocus 'Snow Bunting'	Grade 7/+			
30	Muscari armeniacum	Armenian Grape Hyacinth	Grade 8/9			

Meadow Seed Mix			
ID Code	Seed Mixture Product Name	Supplier	Sowing Rate
EM2	Standard General Purpose Meadow Mixture	Emorsgate Seeds	5g/ sqm

Swale Meadow Seed Mix			
ID Code	Seed Mixture Product Name	Supplier	Sowing Rate
EM8	Meadow mixture for wetlands	Emorsgate Seeds	5g/ sqm

Amenity Lawn Seed Mix			
ID Code	Seed Mixture Product Name	Supplier	Sowing Rate
A19	A19 All Purpose Landscaping	Geminal Amenity	50g/ sqm

Meadow Turf				
MT1	PRODUCT	SPECIFICATION (in accordance with NPS)	DENSITY no./sqm	NOTES
	WFT-Landscape-34 by WildflowerTurf.co.uk or equal and approved	To suppliers recommendations		Install as per supplier recommendations. To have plastic free reinforcement meshing.

Reinforced Grass Turf Lawn				
AL1	PRODUCT	SPECIFICATION (in accordance with NPS)	DENSITY no./sqm	NOTES
	Golpa Grass & Gravel Reinforcement by Geosynthetics or equal and approved	To suppliers recommendations		Install as per supplier recommendations. To have plastic free reinforcement meshing.

Note

1. Do not scale from this drawing
2. To be read in conjunction with Project Risk Register REF: XXX
3. To be read in conjunction with all other Landscape Architect's drawings

KEY

*For Planting Plan refer to drawing 22315-ALA-00-XX-DR-L-0030

DATE	REV	DESCRIPTION OF REVISION	DRAWN BY	APPROVED BY
28/02/2025	P07	Re-issued for planning following Sport England objection withdrawn. Changes as follows: 1. Shade sensory planting mix added to schedule.	MG	MM
REVISIONS				

STATUS
S2 - For Planning



Ares Landscape Architects LTD
Gatecrasher,
51 Eyre Lane
Sheffield
S1 4RB
t: 0114 276 2000
e: hello@aresdesign.co.uk
w: aresdesign.co.uk

CLIENT :
Kirklees Council

PROJECT TITLE :
Woodley School and College

DRAWING TITLE :
Planting Schedule

DRAWING SCALE : NTS	DRAWN BY : AT	DRAWN DATE : 07/03/2024
PAPER SIZE : A1	APPROVED BY : RS	ALA PROJECT CODE : ALA 823

DRAWING NUMBER :
22315-ALA-00-XX-DR-L-0032

STATUS :
S2

REVISION :
P07