Key

- Application site boundary.
- Land within applicant control.
- Existing vegetation to be retained.
- Existing vegetation to be removed.
- Existing/Proposed easements

Ground Modeling & Levels

- Proposed ground modeling/contours.
- +235.00 Proposed spot/contour levels.
- 1:40 Proposed falls/gradients.

Note: All landform and gradients not shown on this plan is design by the project Engineers. Refer to the relevant designer drawings.

Street Furniture

Seat
Coerphilly Steel Framed Timber Seat (ref: BX14 4280-S), as supplied by Broxap (www.broxap.com), or similar approved. Supplied with FSC Hardwood timber & painted steelwork (Colour Holly green - BS4800 14 C 39)

Bench
Coerphilly Steel Framed Timber Bench (ref: BX14 4280-B), as supplied by Broxap (www.broxap.com), or similar approved. Supplied with FSC Hardwood timber & painted steelwork (Colour Holly green - BS4800 14 C 39)

Picnl Bench
Coerphilly Steel Framed Timber Picnic Unit (ref: BX14 4280), as supplied by Broxap (www.broxap.com), or similar approved. Supplied with FSC Hardwood timber & painted steelwork (Colour Holly green - BS4800 14 C 39)

Litter Bin
Derby Standard Litter Bin 120L (ref: BX45G 2550), as supplied by Broxap (www.broxap.com), or similar approved. Bin to be labeled as accepting both refuse and dog waste.

Boundary Treatments

Drystone Wall
Refer to Architects drawings for further details.

Knee Rail
Refer to Architects drawings for further details.

Softworks Schedule

Trees - Plots

Abbr	Species	Supply	Size	Girth	Number
AMLA	Amelanchier lamarkii	HStd: RB	350-425cm	12-14cm	8
BEPE	Betula pendula	HStd: RB	350-425cm	12-14cm	1
LIGLIES	Ligustrum lucidum 'Excelsum Superbum'	HStd: RB	350-425cm	12-14cm	13
MAGKOIS	Magnolia kobus 'Isis'	HStd: RB	350-425cm	12-14cm	12
GLETRS	Gleditsia triacanthos 'Skyline'	EHStd: RB	425-600cm	14-16cm	2

Total :36

Trees - Public Open Space

Abbr	Species	Supply	Size	Girth	Number
PRUAVPL	Prunus avium 'Plena'	SStd: RB	300-350cm	10-12cm	9
QUEPA	Quercus palustris	SStd: RB	300-350cm	10-12cm	4
QUERO	Quercus robur	SStd: RB	300-350cm	10-12cm	2
SORAU	Sorbus aucuparia	SStd: RB	300-350cm	10-12cm	9
ACECAM	Acer campestre	HStd: RB	350-425cm	12-14cm	20
BEPE	Betula pendula	HStd: RB	350-425cm	12-14cm	15
CARBET	Carpinus betulus	HStd: RB	350-425cm	12-14cm	15
FAGSY	Fagus sylvatica	HStd: RB	350-425cm	12-14cm	6
TILCO	Tilia cordata	HStd: RB	350-425cm	12-14cm	15
LIQST	Liquidambar styraciflua	EHStd: RB	425-600cm	14-16cm	3
MALTRI	Malus trilobata	EHStd: RB	425-600cm	14-16cm	14
AMARH	Amelanchier arborea 'Robin Hill'	EHStd: RB	450-625cm	16-18cm	7
MAGKOIS	Magnolia kobus 'Isis'	EHStd: RB	450-625cm	16-18cm	17
TILCOGR	Tilia cordata 'Greenspire'	EHStd: RB	450-625cm	16-18cm	7
TILCOGR	Tilia cordata 'Greenspire'	EHStd: RB	450-650cm	18-20cm	1

Total :144

Specimen Shrubs

Abbr	Species	Pot Size	Height	Habit	Number
PHOAR	Phormium 'Amazing Red'	25L	100-125cm	Trp Cm	11
PHOJE	Phormium 'Jester'	25L	100-125cm	Trp Cm	16
PHOWAVA	Phormium 'Yellow Wave'	25L	100-125cm	Trp Cm	23
PHOFRR	Photinia x fraseri 'Red Robin'	25L	100-125cm	HStd	4

Total :54

Single-Species Hedgerows

Abbr	Species	Pot Size	Height	Habit	Density	Length	Number
PRULU	Prunus lusitanica	10L	80-100cm	Bushy	0.4Ctr	424.8m	1092
PHOFRR	Photinia x fraseri 'Red Robin'	10L	80-100cm	Bushy	0.4Ctr	196.56m	505
						Total :621.36m	Total :1597

Shrubs - Plots

Abbr	Species	Pot Size	Height	Habit	Density	Area	Number
CORALE	Cornus alba 'Elegantissima'	3L	60-80cm	Branched	0.8Ctr	21.44m²	36
AUCJACR	Aucuba japonica 'Crotonifolia'	10L	40-60cm	Bushy	0.8Ctr	21.44m²	36
AUCJACR	Aucuba japonica 'Crotonifolia'	10L	60-80cm	Bushy	0.8Ctr	4.14m²	7
BRASU	Brachyglottis 'Sunshine'	10L	40-60cm	Bushy	0.7Ctr	93.69m²	212
CEATHR	Ceanothus thyrsiflorus repens	10L	40-60cm	Bushy	0.7Ctr	48.32m²	111
CHOAP	Choisya 'Aztec Pearl'	10L	40-60cm	Bushy	0.7Ctr	52.77m²	119
CHOTE	Choisya ternata	10L	40-60cm	Bushy	0.8Ctr	4.62m²	8
CHOTES	Choisya ternata 'Sundance'	10L	40-60cm	Bushy	0.7Ctr	192.97m²	447
ELAPUMA	Elaeagnus pungens 'Maculata'	10L	80-100cm	Bushy	0.8Ctr	21.44m²	36
EUOFOENG	Euonymus fortunei 'Emerald 'n' Gold'	10L	30-40cm	Bushy	0.7Ctr	176.11m²	408
EUOFOEG	Euonymus fortunei 'Emerald Gaiety'	10L	30-40cm	Bushy	0.7Ctr	117.99m²	269
FATJA	Fatsia japonica	10L	80-100cm	Bushy	0.8Ctr	5.52m²	9
HEBMAR	Hebe 'Marjorie'	10L	40-60cm	Bushy	0.8Ctr	24.93m²	43
HEBMW	Hebe 'Mrs Winder'	10L	40-60cm	Bushy	0.7Ctr	81.13m²	190
HEBPQ	Hebe 'Purple Queen'	10L	40-60cm	Bushy	0.7Ctr	72.55m²	170
HEBALRE	Hebe albicans 'Red Edge'	10L	30-40cm	Bushy	0.7Ctr	207.64m²	474
HEBPIS	Hebe pinguifolia 'Sutherlandii'	10L	30-40cm	Bushy	0.7Ctr	90.09m²	204
HYPHI	Hypericum 'Hidcote'	10L	40-60cm	Bushy	0.8Ctr	28.89m²	50
LAVANHI	Lavandula angustifolia 'Hidcote'	10L	30-40cm	Bushy	0.7Ctr	131.86m²	303
LAVANMU	Lavandula angustifolia 'Munstead'	10L	30-40cm	Bushy	0.7Ctr	32.29m²	75
PHOFRRER	Photinia x fraseri 'Red Robin'	10L	80-100cm	Bushy	0.8Ctr	25.58m²	43
PITETT	Pittosporum tenuifolium 'Tom Thumb'	10L	30-40cm	Bushy	0.7Ctr	37.06m²	83
PRULAOL	Prunus laurocerasus 'Otto Luyken'	10L	60-80cm	Bushy	0.7Ctr	210.98m²	494
PRULAOL	Prunus laurocerasus 'Otto Luyken'	10L	60-80cm	Bushy	0.8Ctr	21.37m²	39
SARHOHU	Sarcococca humilis	10L	30-40cm	Bushy	0.7Ctr	62.63m²	148
SKIJARU	Skimmia japonica 'Rubella'	10L	40-60cm	Bushy	0.7Ctr	43.63m²	100
VIBDA	Viburnum davidii	10L	40-60cm	Bushy	0.7Ctr	58.1m²	136
VIBTIEVP	Viburnum tinus 'Eve Price'	10L	40-60cm	Bushy	0.8Ctr	4.62m²	8
						Total :1893.8m²	Total :4258

Grasses - On Plot

Abbr	Species	Pot Size	Height	Habit	Number
CALACKF	Calamagrostis acutiflora 'Karl Foerster'	2L		Full Pot	19
STIPGIG	Stipa gigantea	2L		Full Pot	6

Total :25

Herbaceous - On Plot

Abbr	Species	Pot Size	Height	Habit	Number
ACHTIE	Achillea 'Terracotta'	2L		Full Pot	12
GERSAA	Geranium sanguineum 'Album'	2L		Full Pot	27
PERLS	Perovskia 'Little Spire'	2L		Full Pot	23
PHLRU	Phlomis russeliana	2L		Full Pot	9
RUDFLG	Rudbeckia fulgida 'Little Goldstar'	2L		Full Pot	24
SEDSP	Sedum spectabile	2L		Full Pot	30

Total :125

Shrubs - POS

Abbr	Species	Pot Size	Height	Habit	Density	Area	Number
ACHTE	Achillea 'Terracotta'	3L		Full Pot	0.6Ctr	7.12m²	21
CORALE	Cornus alba 'Elegantissima'	3L	60-80cm	Branched	0.6Ctr	5.19m²	15
CORALK	Cornus alba 'Kesselringii'	3L	60-80cm	Branched	0.6Ctr	5.19m²	15
CORSAMF	Cornus sanguinea 'Midwinter Fire'	3L	60-80cm	Branched	0.8Ctr	27.52m²	45
CORSAWB	Cornus sanguinea 'Winter Beauty'	3L	60-80cm	Branched	0.6Ctr	5.19m²	15
CORSTF	Cornus stolonifera 'Flaviramea'	3L	60-80cm	Branched	0.6Ctr	5.19m²	15
ASTRS	Astilbe 'Red Sentinel'	5L		Full Pot	0.6Ctr	9.46m²	27
CAROSE	Carex oshimensis 'Evergold'	5L	20-30cm	Full Pot	0.4Ctr	3.40m²	22
HYPMOTR	Hypericum moserianum 'Tricolor'	5L	30-40cm	Bushy	0.6Ctr	43.27m²	124
KNIPY	Kniphofia 'Pyromania'	5L		Full Pot	0.6Ctr	9.44m²	27
POTFRBS	Potentilla fruticosa 'bella sol'	5L	30-40cm	Bushy	0.6Ctr	29.15m²	84
BRASU	Brachyglottis 'Sunshine'	10L	40-60cm	Bushy	0.7Ctr	20.1m²	42
HEBALRE	Hebe albicans 'Red Edge'	10L	40-60cm	Bushy	0.7Ctr	7.44m²	16
						Total :177.68m²	Total :468

Native Hedgerow - Species-Rich (Transplants)

Abbr	Species	Supply	Height	Density	Mix %	Length	Number
CORSA	Cornus sanguinea	1T+1: 3 Brks	60-80cm	0.3Ctr Double Staggered at 0.3m offset	10%	23.57m	158
CRAMON	Crataegus monogyna	1T+1: 3 Brks	60-80cm	0.3Ctr Double Staggered at 0.3m offset	35%	82.49m	551
EUOEPS	Euonymus europaeus	1T+1: 3 Brks	60-80cm	0.3Ctr Double Staggered at 0.3m offset	10%	23.57m	158
ILEAQ	Ilex aquifolium	2L: 3 Brks	40-60cm	0.3Ctr Double Staggered at 0.3m offset	15%	35.36m	236
LIGVU	Ligustrum vulgare	1T+1: 3 Brks	60-80cm	0.3Ctr Double Staggered at 0.3m offset	15%	35.36m	236
ROSCA	Rosa canina	1T+1: 3 Brks	60-80cm	0.3Ctr Double Staggered at 0.3m offset	5%	11.79m	79
VIBOP	Viburnum opulus	1T+1: 3 Brks	60-80cm	0.3Ctr Double Staggered at 0.3m offset	10%	23.57m	158
						Total :235.71m	Total :1576

Native Scrub - Species-Rich

Abbr	Species	Supply	Height	Mix %	Density	Area	Number
CORAV	Corylus avellana	1T+1: 3 Brks BR	60-80cm	10%	1/m²	294.46m²	298
CRAMON	Crataegus monogyna	1T+1: 3 Brks BR	60-80cm	45%	1/m²	1325.05m²	1329
EUOEPS	Euonymus europaeus	1T+1: 3 Brks BR	60-80cm	10%	1/m²	294.46m²	298
ILEAQ	Ilex aquifolium	2L: 3 Brks	40-60cm	10%	1/m²	294.46m²	298
LIGVU	Ligustrum vulgare	1T+1: 3 Brks BR	60-80cm	10%	1/m²	294.46m²	298
ROSCA	Rosa canina	1T+1: 3 Brks BR	60-80cm	5%	1/m²	147.21m²	151
VIBOP	Viburnum opulus	1T+1: 3 Brks BR	60-80cm	10%	1/m²	294.46m²	298
						Total :2944.56m²	Total :2970

Turf & Seeding

Turf
Turf to gardens to be laid as Rolawn 'Medallion', or similar approved.

Amenity Grass
A22 low maintenance seed mixture, as supplied by Germinal (www.germinalamenity.com) or similar approved.

Meadow Grassland
EM1, seed mixture for meadows, as supplied by Emorgate Seeds (www.wildseed.co.uk) or similar approved.

Drawing to be read in conjunction with GLY0043 SP 01 Landscape Specification.

Landscape Institute Registered Practice

Scale Bar
0m 5m 10m 15m 20m 25m

tel: 01530 265688 | email: info@golbyandluck.co.uk | web: www.golbyandluck.co.uk

This drawing has been produced by GOLBY AND LUCK LTD © all rights reserved. Ordnance Survey Licence No. AC0000818156 registered with PlanningOffice: 207 Leicester Road, Ibstock, Leicestershire, LE67 6HP

Location Plan

Rev	Date	Notes	Int.

Project
Blackmoorfoot, Huddersfiled

Drawing title
Landscape Proposals
(Sheet 1 of 5)

Status
PLANNING

Client
Miller Homes

Scale	Drawn By	Checked By
1:250 @ A0	APF	DC

Date	Reference
07/03/2025	**GLY0043 LP 03**

golby+luck
landscape architects