



- Key**
- Ground Modelling & Levels**  
Proposed ground modelling/contours. Refer to GLY0043 LP 04 for Levels & gradients.
- Surface Treatments**
- P1** Jungle Mutch - Camouflage  
Wet pour rubber Jungle Mutch Surfacing (Colour: Camouflage) as supplied by Playmat UK (www.playmat.co.uk) or similar approved. Thickness to suppliers specification. Total: 156m<sup>2</sup>
  - P2** Jungle Mutch - Woodland Red  
Wet pour rubber Jungle Mutch Surfacing (Colour: Woodland Red) as supplied by Playmat UK (www.playmat.co.uk) or similar approved. Thickness to suppliers specification. Total: 94m<sup>2</sup>
  - P3** Tarmac  
Tarmac path with standard pcc edge. (Colour: Black). Associated construction build up to the Project Engineers specification. Total: 854M<sup>2</sup> (854M<sup>2</sup> MUGA + 1015m<sup>2</sup>)
  - SP1** Surface Paint - Tan  
Britannia Playground Paint (Colour: tan) as supplied by Britannia Paints (www.britanniapaints.co.uk) or similar approved. Application details to suppliers specification.
  - SP2** Surface Paint - Tan  
Britannia Playground Paint (Colour: Tarmacoff) as supplied by Britannia Paints (www.britanniapaints.co.uk) or similar approved. Application details to suppliers specification.
- Steel Furniture**
- Seat**  
Coersply Steel framed Timber Seat (Ref: BX14 4200-3), as supplied by Brovap (www.brovap.com), or similar approved. Supplied with FSC hardwood timber & painted steelwork (Colour: Holly green - 854800 14 C 39)
  - Bench**  
Coersply Steel framed Timber Bench (Ref: BX14 4200-8), as supplied by Brovap (www.brovap.com), or similar approved. Supplied with FSC hardwood timber & painted steelwork (Colour: Holly green - 854800 14 C 39)
  - Plastic Bench**  
Coersply Steel framed Timber Plastic (Ref: BX14 4200), as supplied by Brovap (www.brovap.com), or similar approved. Supplied with FSC hardwood timber & painted steelwork (Colour: Holly green - 854800 14 C 39)
  - Litter Bin**  
Dorly Standard Litter Bin 120L (Ref: BX45G 25X), as supplied by Brovap (www.brovap.com), or similar approved. Bin to be labeled as accepting both refuse and dog waste.
- Natural Play elements**
- Play Log**  
3.6m long with nom. 0.5-0.6m dia. boulders set of variable heights (max. 0.6m high off adjacent ground). Logs all bark removed and finished with rounded edges free of burrs or catches. Logs within banks to be buried by min. 40% of log height and secured to avoid future movement.
  - MUGA**  
44.8 x 24m Multi Use Games Area formed using materials noted on plan and specified above. Sports pitches to be formed using white line marking paint.
  - Amenity Planting**  
Amenity shrub planting separating the two sports pitches. Refer to GLY0043 LP 04 for specification.
  - Compacted Aggregate with Timber Edge**  
Self-binding gravel (Brescon Gravel - Colour: Buff or similar approved with standard FSC treated timber edging to plant bed extents.
- Play Equipment**
- PE1** Emerald  
Ref: COR20700  
Colour: Green
  - PE2** Block 3  
Ref: BK4103  
Colour: Orange
  - PE3** Wheelchair Carousel  
Ref: FCW153  
Colour: Red
  - PE4** Dino Swing  
Ref: NR987
  - PE5** Swing Combination  
Ref: NR9707
  - PE6** Cableway, timber (25m)  
Ref: NR9576
  - PE7** Dynamic Bar  
Ref: NR9300
  - PE8** SSM  
Ref: NR9306
  - PE9** Balance Post With Ropes  
Ref: NR9821
  - PE10** Balance Beam on Springs  
Ref: NR9827
  - PE11** Little Spider Swing  
Ref: NR9793
  - PE12** Pony  
Ref: NR10102
  - PE13** Mule  
Ref: NR10101
  - PE14** Goal (3m)  
Ref: FR1601401
  - PE15** Basketball Goal (freestanding, Reinforced Net)  
Ref: FR16322
- All play equipment as supplied by Kompan (www.kompan.com) or similar product from an approved manufacturer. All equipment to be installed with grass safety surfacing in line with manufacturer guidelines unless shown within wet pour rubber surfacing.
- All play equipment and layout proposals to be specified in accordance with the requirements set out under BS EN 1176 and Equality Act 2010. Following the agreement of play equipment and the general arrangement the selected manufacturer details will be submitted to the local council for approval along with the finished proposals and accompanying certificates and details. Signs are to be supplied and erected that the play area is a Dog Free zone and any other information required. Exact wording to be agreed with the Local Planning Authority.

Drawing to be read in conjunction with GLY0043 SP 01 Landscape Specification.