



**Softworks Schedule**

**Trees - Plots**

Abbr	Species	Supply	Site	Girth	Number
LAGHS	Ligularia lucida 'Tudor Superbum'	H518 RB	350-425cm	12-14cm	7
MAGKCS	Magrostis holcus 'W'	H518 RB	350-425cm	12-14cm	10
AMARH	Amorpha fruticosa 'Robin Hill'	H518 RB	425-600cm	14-16cm	11

**Trees - Public Open Space**

Abbr	Species	Supply	Site	Girth	Number
ACECAM	Acer campestre	Std BR	250-300cm	8-10cm	7
PRUPA	Prunus padus	Std BR	250-300cm	8-10cm	6
PYCOM	Pinus commisus	Std BR	250-300cm	8-10cm	11

**Specimen Shrubs**

Abbr	Species	Supply	Site	Height	Number
PHOAR	Phytolacca 'Amazing Red'	25L	100-125cm	Tip Cm	6
PHOAR	Phytolacca 'Amazing Red'	25L	100-125cm	Tip Cm	14
PHOAR	Phytolacca 'Yellow Wonder'	25L	100-125cm	Tip Cm	12

**Single-Species Hedgerows**

Abbr	Species	Supply	Site	Height	Number
ELAB	Elaeagnus ebbingei	10L	80-100cm	Bushy	4

**Shrubs - Plots**

Abbr	Species	Supply	Site	Height	Number
CORAL	Cornus alba 'Variegata'	3L	60-80cm	Branches	65
BRASU	Brachyglottis 'Sunshine'	3L	30-40cm	Bushy	65

**Grasses - On Plot**

Abbr	Species	Supply	Site	Height	Number
CALCAF	Calamagrostis acutifloris 'Karl Foerster'	2L	Full Pot	20	1
STIPIG	Stipa galgatica	2L	Full Pot	3	1

**Herbaceous - On Plot**

Abbr	Species	Supply	Site	Height	Number
ACHIE	Actinella Tomcat	2L	Full Pot	12	1
HEBE	Hebe 'Spiraea'	2L	Full Pot	4	1
FELIS	Ferula Little Spire	2L	Full Pot	20	1

**Shrubs - POS**

Abbr	Species	Supply	Site	Height	Number	
CALCAF	Calamagrostis acutifloris 'Karl Foerster'	3L	Full Pot	0.6Cm	44	
CORAL	Cornus alba 'Variegata'	3L	60-80cm	Branches	34.5cm	56

**Native Hedgerow - Species-Rich (Transplants)**

Abbr	Species	Supply	Site	Height	Number
CORSA	Cornus sanguinea	11-1.3 BxS	60-80cm	0.3Cm Double Staggered on 0.3m offset	105
COBAV	Cornus alba 'Variegata'	11-1.3 BxS	60-80cm	0.3Cm Double Staggered on 0.3m offset	325

**Native Fruiting Hedgerow - Species-Rich (Transplants)**

Abbr	Species	Supply	Site	Height	Number
CORSA	Cornus sanguinea	11-1.3 BxS	60-80cm	0.3Cm Double Staggered on 0.3m offset	105
COBAV	Cornus alba 'Variegata'	11-1.3 BxS	60-80cm	0.3Cm Double Staggered on 0.3m offset	325

**Native Scrub - Species-Rich - 4m Offset**

Abbr	Species	Supply	Site	Height	Number
CORAL	Cornus alba	1+1.3 BxS	60-80cm	15%	647
CORSA	Cornus sanguinea	1+1.3 BxS	60-80cm	15%	4442mm

**Native Scrub - Species-Rich - 6m Offset**

Abbr	Species	Supply	Site	Height	Number
CORSA	Cornus sanguinea	1+1.3 BxS	60-80cm	15%	58.1mm
COBAV	Cornus alba 'Variegata'	1+1.3 BxS	60-80cm	35%	136.5mm

**Native Scrub - Species-Rich - 13m Offset**

Abbr	Species	Supply	Site	Height	Number
CORSA	Cornus sanguinea	1+1.3 BxS	60-80cm	15%	58.1mm
COBAV	Cornus alba 'Variegata'	1+1.3 BxS	60-80cm	35%	136.5mm

**Turf & Seeding**

**Turf**  
Turf to gardens to be laid as 'old man' sods, or similar approved.

**Amenity Grass**  
A22 low-maintenance seed mixture, as supplied by Gemini ([www.geminiamenity.com](http://www.geminiamenity.com)) or similar approved.

**Meadow Grassland**  
EM1 seed mixture for meadows, as supplied by Emorgate Seeds ([www.wildseed.co.uk](http://www.wildseed.co.uk)) or similar approved.

**Key**

- Application site boundary.
- Existing vegetation to be retained.
- Existing/Proposed easements.
- Maintenance access track surfacing to suit the requirements of the adopting Water Authority.

**Surface Treatments**

- Terrace Paving**: Terraced paths with standard pcc edge. (Colour: Black). Associated construction build ups to the Project Engineers specification.
- Block Paving**: Mosaic Paving (Colour: Traditional) in 120x160, 160x160 & 240x160mm sizes. Laid in a radial pattern to match the arc of the paths shown. Paver thickness and associated construction detail set to the Project Engineers specification.
- Gravel**: 20-45mm loose gravel laid over a standard weedproof membrane.

**Street Furniture**

- Seat**: Copersly Steel Framed Timber Seat with back & armrests (ref: BK14 4280-5), as supplied by Broxap ([www.broxap.com](http://www.broxap.com)), or similar approved. Supplied with FSC Hardwood timber & painted steelwork (Colour: Holly green - BS4800 14 C 39).
- Bench**: Copersly Steel Framed Timber Bench (ref: BK14 4280-5), as supplied by Broxap ([www.broxap.com](http://www.broxap.com)), or similar approved. Supplied with FSC Hardwood timber & painted steelwork (Colour: Holly green - BS4800 14 C 39).
- Picnic Bench**: Copersly Steel Framed Timber Picnic Unit (ref: BK14 4280-5), as supplied by Broxap ([www.broxap.com](http://www.broxap.com)), or similar approved. Supplied with FSC Hardwood timber & painted steelwork (Colour: Holly green - BS4800 14 C 39).
- Picnic Bench - Accessible**: Copersly Steel Framed Timber Picnic Unit with bench to one side only to allow for wheelchair accessibility (ref: BK14 4280-5), as supplied by Broxap ([www.broxap.com](http://www.broxap.com)), or similar approved. Supplied with FSC Hardwood timber & painted steelwork (Colour: Holly green - BS4800 14 C 39).

**Boundary Treatments**

- Litter Bin**: Dwyler Standard Litter Bin 120L (ref: BK45G 2350), as supplied by Broxap ([www.broxap.com](http://www.broxap.com)), or similar approved. Bin to be labeled as accepting both refuse and dog waste.
- Cycle Stands**: Sheffield Cycle Stands (ref: BKXW/GS/shelfield), as supplied by Broxap ([www.broxap.com](http://www.broxap.com)), or similar approved. Set on an asphalt surround with standard pcc pin kerb edge.
- Timber Gate Posts**: 0.3m x 0.3m FSC Hardwood timber posts set either side of footpaths where shown on plan. Posts to be set 1.2m high with pyramid top with pointed faces.

**Notes**

All furniture to be root fixed to supplier specification.

**Notes**

- Refer to Architects drawings for further details.
- Refer to Architects drawings for further details.
- Refer to Architects drawings for further details.
- Refer to Boundary Treatments Plan for full details of all site-wide proposed boundaries.

**Location Plan**

**Revision Table**

Rev	Date	Notes	By	Project
A	30/05/23	Revised to latest layout	APP	Blackmoorfoot, Huddersfield
B	26/08/23	Revised to latest layout and to respond to planning comments.	APP	Blackmoorfoot, Huddersfield
C	16/10/23	Revised to latest layout and to respond to planning comments.	APP	Blackmoorfoot, Huddersfield
D	21/11/23	Revised to latest layout and to respond to planning comments.	APP	Blackmoorfoot, Huddersfield

**Scale Bar**

0m 5m 10m 15m 20m 25m

**Scale**  
1:250 @ A0

**Client**  
Vistry

**Date**  
15/05/2025

**Reference**  
GLY0043 LP-V 12-D

**Project**  
Blackmoorfoot, Huddersfield  
Landscape Proposals  
Issue 12 of 18

**Author**  
PLANNING

**Client**  
Vistry

**Scale**  
1:250 @ A0

**Drawn by**  
APP

**Checked by**  
DC

**Date**  
15/05/2025

**Reference**  
GLY0043 LP-V 12-D

**golby+luck**  
landscape architects