



Remove garage door and replace with white PVC window to match existing with stone cill to match existing.

Buildup wall in 100 natural stone to match existing with PIR cavity insulation and 100 breeze block inner leaf with DPC to both leaves with SS wall ties staggered on 200 thick concrete footing.

